For personal use only

ASX ANNOUNCEMENT
7 September 2026

NAL Expansion Pre-Feasibility Study

North American lithium producer Elevra Lithium Limited (“Elevra" or "Company”) (ASX:ELV; NASDAQ:ELVR) is pleased to announce the results of a Pre-Feasibility Study ("PFS") for the staged North American Lithium ("NAL") Brownfield Expansion in Québec. The PFS confirms the NAL Expansion as a high-value growth project that is expected to significantly increase annual spodumene concentrate production while reducing unit operating costs and generating attractive returns on capital invested.

Highlights:

- Consistent with the Updated NAL Expansion Scoping Study, the NAL Expansion will be delivered through a three-stage brownfield development, with Stage 1 increasing process plant throughput to the currently permitted rate of 4,500 tpd from mid-CY27, Stage 2 increasing milling capacity to 6,500 tpd from mid CY28, and Stage 3 delivering a permanent crushing solution aligned with increased milling capacity by mid CY29.

- On a post expansion basis, average annual spodumene concentrate production increases to 373 thousand tonnes per annum (ktpa) (nominal SC5.4, post ramp up), nearly double the no expansion scenario ("Base Case") and 10% above the 338 ktpa estimate from May 2026[1]. Production above the 338 ktpa capacity is attributable to improved mill feed grades largely due to benefits of ore sorting equipment.

- Life of mine (**LOM**) C1 cost of C$876/t (US$649/t) [2] of spodumene concentrate, reducing to C$851/t (US$630/t)[2] post-expansion with AISC of C$918/t (US$680/t)[2].

- The NAL Expansion is fully funded based on the total initial CAPEX remaining unchanged at C$366M (US$271M)[2] (AACE Class 4 estimate with a target accuracy range of ±40%), including C$73M (US$54M) [2] of contingency, with Stage 1 CAPEX of C$92M (US$68M) [2], Stage 2 CAPEX of C$101M (US$75M) [2] and Stage 3 CAPEX of C$173M (US$128M) [2].

- NAL Expansion delivers a post-tax NPV (8%) of C$3,218M (US2,384M)[2], or an incremental post-tax NPV (8%) of C$943M (US$699M)[2] compared to the C$969M (US$718M)[2] incremental post-tax NPV (8%) declared in May 2026[1] due primarily to a 4% increase in the mining cost compared to the previous announcement following further detailed haulage modelling.

- The Company’s existing NAL Ore Reserves of 47.2Mt at 1.12% Li_2O, comprising 0.2MT Proven and 47.0MT Probable Mineral Reserves, solely underpin the NAL Expansion production profile with a revised life of mine of 20 years.

- The PFS demonstrates that the NAL Expansion can increase production, reduce unit costs and generate significant incremental value from an existing operating asset and established infrastructure.

---

[1] ASX release "*Updated NAL Expansion Scoping Study*" dated 12 May 2026.
[2] Figures converted from Canadian dollar to United States dollar at CAD/USD 1.35 as per the PFS.

For personal use only

- The NAL Expansion is fully funded through Elevra's Strategic Financing Package announced in May 2026[3].

Elevra's Managing Director and Chief Executive Officer, Mr Lucas Dow, said: "*The NAL Expansion PFS confirms a compelling value proposition for Elevra, with a high-return brownfield expansion that materially increases production while reducing unit operating costs.*

The ability to increase average annual production to 373,000 tonnes post-expansion, while reducing LOM average C1 unit costs post expansion to approximately C$851/t (US$630/t)[4], demonstrates the significant operating leverage available at NAL. The production target and cost profile are underpinned by existing Ore Reserves and historical operating data, providing a strong foundation for the production and financial outcomes outlined in the PFS.

The staged development approach allows us to bring additional production online from mid-2027, by progressively increasing throughput and capturing operating efficiencies while managing project execution and prudent capital deployment."

Study Confirms Compelling Economics for NAL Expansion

The PFS confirms a compelling economic case for the staged expansion of NAL, with the project expected to materially increase spodumene concentrate production while reducing unit operating costs and generating significant incremental value from an existing operating asset.

The PFS estimates an expansion-only post-tax NPV8% of C$943MM (US$699M)[4], post-tax IRR of 49.9% and post-tax payback period of 34 months.

The expansion requires initial capital expenditure of C$366 M (US$271M)[4], with total sustaining expenditure of C$527M (US$390M)[4] over the expansion case. The financial analysis is unlevered and based on the Mineral Reserves estimated as part of the PFS.

The PFS establishes an average annual production rate of 348ktpa (5.4% Li_2O spodumene concentrate) and an average annual post-expansion production rate of 373ktpa (5.4% Li_2O spodumene concentrate).

Importantly, 100% of the Production Target is underpinned by Proven and Probable Ore Reserves. No Inferred Mineral Resources are included in the economic analysis or Production Target. The PFS states that the economic analysis was based on Measured and Indicated Mineral Resources only, with Inferred Mineral Resources excluded as too geologically speculative for mining and economic considerations to be applied.

Study Confirms Strong Operating Metrics for NAL Expansion

The PFS demonstrates significant operating leverage from increasing the scale of NAL's existing operation.

Average annual post-expansion spodumene concentrate production is expected to increase from 199ktpa in the base case to 373ktpa post-expansion, while LOM average production increases from 196ktpa to 348ktpa.

LOM C1 operating costs are estimated at C$876/t (US$649/t)[4] of concentrate, compared with C$1,048/t (US$776/t)[4] for the base case, while the post-expansion C1 cost is estimated at C$851/t (US$630/t)[4].

LOM AISC is estimated at C$954/t (US$707/t)[4], reducing to C$918/t (US$680/t)[4] post-expansion.

The PFS estimates total LOM operating expenditure of C$5.95B (US$4.41B)[4] for the expansion case, with the cost estimates supported by actual NAL operating information including salaries, consumables, maintenance costs and established contracts.

---

[3] ASX release "*Transformational Financing Package to Accelerate Growth*" dated 12 May 2026.
[4] Converted at CAD/USD 1.35.

For personal use only

Staged Expansion Delivery

The NAL Expansion Project has been designed as a three-stage brownfield development that progressively increases production and reduces unit costs while leveraging existing infrastructure.

Stage 1

Stage 1 is expected to deliver an initial 15-20% increase in annual spodumene concentrate production within NAL's existing 4,500 tpd milling permit, together with a reduction in unit operating costs.

Stage 2

Stage 2 will expand downstream milling, flotation and filtration capacity to 6,500 tpd, with additional feed initially supported by a temporary mobile crushing circuit. Production from Stage 2 is expected to commence in mid CY28.

Stage 3

Stage 3 will replace the temporary and existing crushing circuits with a new crushing circuit capable of supporting the targeted 373ktpa post-expansion production profile, together with additional ore sorting capacity. Completion is expected in mid CY29.

The staged development approach was adopted to reduce execution risk, bring forward production growth and stage capital deployment.

Pre-Feasibility Study Metrics

Analysis of the financial model on the key economic assumptions indicates that the Project is robust in terms of operational and financial metrics. The Project is most sensitive to changes in commodity prices, exchange rates, head grades and recoveries, with the key Project assumptions and outputs shown in the tables below (please note that any reference to Base Case means NAL on an unexpanded or "as is" basis):

Table 1 – Main Financial Assumptions and Results Summary for the NAL Expansion Project

Parameters	Unit	Base	May-26 Updated Scoping[5]	PFS
Average Price 6% Li_2O[6]	USD$/t	$2,260	$2,154	$2,137
Life of mine (from FY27)	yrs	35	21	20
Total Waste	Mt	336	335	336
Total Ore Processed	Mt	47	47	44
Strip Ratio	-	7.1	7.2	7.1
Average Annual ROM	Mt/y	1.36	2.22	2.41
Average Feed Grade	% Li_2O	1.12%	1.11%	1.17%
LOM 5.4% Li_2O Produced	Mt	6.77	6.85	6.79
Average Annual 5.4% Li_2O Production (post expansion)	kt/y	199	338	373

[5] May-26 Scoping shows the results of the Updated Scoping Study for the NAL Expansion. See ASX release "*Updated NAL Expansion Scoping Study*" dated 12 May 2026.
[6] Average Price 6% Li_2O varies between the cases due to longer mine life at the long-term US$2,340 price for the base case.

For personal use only

Table 2 – Project Economics

Project Economics	Unit	Base	May-26 Updated Scoping	PFS
LOM C1 Cost Concentrate	C$/t conc	1,048	868	876
LOM AISC	C$/t conc	1,126	946	954
LOM C1 Cost of Concentrate (post expansion)	C$/t conc	1,045	847	851
LOM AISC (post expansion)	C$/t conc	1,112	922	918
Total Sustaining Capital (SUSEX)	C$M	512	526	527
Total Initial CAPEX	C$M	-	366	366
NPV (8%) (post-tax)	C$M	2,274	3,112	3,218
IRR Expansion (post-tax)	%	-	42%	50%
Payback (post-tax)	Months	-	25	34

Notes:

- All costs and sales are presented in constant 2026 CAD, with no inflation or escalation factors considered.
- $M = millions of dollars.
- The financial analysis was performed on existing Mineral Reserves as outlined in this report.
- The valuation calculations are unlevered.
- The average metallurgical recovery over the LOM is 71.2% for the expansion and 69.2% for the base case due to improvement in the flowsheet attributable to wet high-intensity magnetic separator (WHIMS) improvements.
- Plant availability is calculated at 90%.
- Tonnes of concentrate are presented as dry metric tonnes.
- An exchange rate of 1.35 CAD/USD was fixed over the LOM for the Project.
- The average 6% Li_2O concentrate (SC6) price is based on a market analysis from Benchmark Mineral Intelligence for Q1 2026 as described in the market section and varies over the LOM from US$1,260/t to US$2,430/t.
- Average LOM SC6 pricing may vary between the cases due to longer mine life at the long term US$2,430 price for the base case (2036 and beyond).
- A discount rate of 8% was used for the base case and expansion scenarios.
- Net Cash Flow and valuation calculations include investment tax credit on CAPEX.
- The numbers have been rounded. Any discrepancy in the totals is due to rounding effects.

Purpose of this ASX Release

This ASX release provides readers with a bridge between prior ASX disclosure on 12 May 2026 "*Updated NAL Expansion Scoping Study*" and a National Instrument 43-101 Pre-Feasibility Study (**attached**) that has been prepared for compliance with Quebec, Canada regulatory requirements and to enable subsequent permitting activities for the NAL expansion. The NI43-101 report will also be available on SEDAR.

For personal use only

The Company can confirm that the Resource and Reserve tables reproduced in this ASX release and the NI43-101 report are compliant with both ASX/JORC requirements and those related to NI43-101 reporting. It should also be noted the ore reserves are: (1) not being reported for the first time; and (2) the same as those estimates which were previously reported in the FY26 Annual Report released to the ASX on 28 August 2026.

Mineral Resources and Ore Reserves

The project database contains data from 1,575 diamond drillholes surfaces and underground collared, spanning a total of 27,183 records of Li_2O assays with a mean sample length of approximately 0.884 m. Li_2O grade varies from 0.000% to 5.318%. Global average Li_2O grade for raw samples (excluding 0.00% assays) is 0.783%. From this database, a subset of 562 surface collared drillholes totalling 153,047 m was used for the Mineral Resource estimate.

The current Mineral Resource Estimate and Ore Reserve Estimate are presented in Table 4 and Table 5 below. The Mineral Resource and Ore Reserve estimates were prepared by Competent Persons in accordance with the 2012 JORC Code.

Table 3 – North American Lithium – Mineral Resource Estimates (0.60% Li_2O cut-off grade for the RPEEE pit and 0.70% Li_2O cut-off grade for underground domain)

Resource Classification	Method	Tonnes (Mt)	Li_2O Grade (%)	Cut-Off Grade (%)
Indicated	Open Pit	74.4	1.17	0.60
Inferred	Open Pit	8.6	1.13	0.60
Indicated	Underground	-	-	-
Inferred	Underground	10.3	1.01	0.70
Total		93.3	1.15	

Table 4 – North American Lithium – Ore Reserves Estimate, as at of June 30, 2026

Resource Classification	Tonnes (Mt)	Li_2O Grade (%)	Cut-Off Grade (%)	Fe Grade (%)
Proved Ore Reserves	0.2	0.93	0.60	1.48
Probable Ore Reserves	47.0	1.12	0.60	0.81
Total	47.2	1.12	0.60	0.81

The information on Mineral Resources and Ore Reserves is extracted from the announcement entitled “2026 Annual Report” published on the ASX on August 28th, 2026, and is available to view on the Elevra’s website on the ASX. The company confirms that it is not aware of any new information or data that materially affects the information included in the original market announcement and, in the case of estimates of Mineral Resources or Ore Reserves, that all material assumptions and technical parameters underpinning the estimates in the relevant market announcement continue to apply and have not materially changed. The company confirms that the form and context in which the Competent Person’s findings are presented have not been materially modified from the original market announcement.

For personal use only

Background

The North American Lithium operation is a hard-rock lithium mining and concentration facility located in La Corne, within the Abitibi-Témiscamingue region of Quebec, Canada. The NAL facility was successfully restarted in March 2023, and the plant is currently permitted for 4,500 tpd of average annual milling rate.

The processing operation consists of three distinct processing areas:

- The primary, secondary and tertiary crushing, and ore sorting circuits to produce an upgraded plant feed for downstream processing.
- The spodumene processing plant including grinding, desliming, magnetic separation, flotation and dewatering circuits to produce a final spodumene concentrate.
- The process water and utilities circuits including tailings thickeners, reagents preparation, reverse osmosis treatment, and tailings management.

The objective of the NAL expansion project is to increase the plant's milling throughput to an annual level of 6,500 tpd. Elevra determined that permitting is the critical path constraint and identified a project development sequence that provides a shorter timeframe to achieve increased production from NAL. The additional new permitting information, combined with existing permits, provides a pathway to stage the expansion of production volumes at NAL in a disciplined, agile and more time efficient manner.

The expansion pathway is now proposed to take the form of a series of debottlenecking steps which are expected to:

- Increase production capacity above current levels in a staged and incremental manner;
- Improve plant recovery by the introduction of additional LIMS and WHIMS, and additional flotation conditioning capacity;
- Reduce the timeframe to achieve the expanded average annual production volume of 373ktpa of spodumene concentrate; and
- Enable the capital investment to be staged and, in doing so, reduce the initial upfront capital requirements.

The debottlenecking steps are anticipated to be delivered as below:

1. An initial 15-20% increase in annual spodumene concentrate production above current production levels commencing in mid-CY27 with an incremental reduction in unit operating costs. This increase is within the current limits of the milling permit, which is set at 4,500 tpd;
2. A subsequent expansion of the milling, flotation and filtration capacity to 6,500 tpd. The incremental feed material will be processed using a temporary mobile crushing circuit operating in conjunction with the existing crushing circuit. The further expanded production is expected to commence mid CY28, with an additional incremental reduction in unit operating costs; and
3. The replacement of the temporary mobile crushing circuit and the existing crushing circuit with a new crushing circuit capable of meeting feed requirements for a LOM average production of 373 ktpa post-expansion. This final step will include additional ore sorting capacity and is expected to be completed in mid CY29 delivering crushing cost efficiencies which are required to meet the anticipated LOM cost reduction.

Announcement authorised for release by Elevra's Managing Director and Chief Executive Officer.

For personal use only

About Elevra Mining

Elevra Lithium Limited is a North American lithium producer (ASX:ELV; NASDAQ:ELVR) with projects in Québec, Canada, United States and a joint venture in Western Australia.

Elevra's assets comprise North American Lithium (100%), a 60% stake in the Moblan Lithium Project in Central Québec and the Carolina Lithium project (100%) in the United States[8].

For more information, please visit us at www.elevra.com.

Competent Person's Statement

The information on Mineral Resources and Ore Reserves are extracted from the announcement entitled "2026 Annual Report" published on the ASX on 28th August 2026 and is available to view on the Elevra's website or on the ASX. The Company confirms that it is not aware of any new information or data that materially affects the information included in the original market announcement and all material assumptions and technical parameters continue to apply and have not materially changed. The Company confirms that the form and context in which the Competent Person's findings are presented have not been materially modified from the original market announcements

The ASX release dated 28th August 2026 that relates to Mineral Resources for the NAL project – referred to in this announcement – is based on and fairly represents information compiled by Mr Stephen John Andrew, an independent consultant employed by Measured Group and who is a member of the Australasian Institute of Mining and Metallurgy (AusIMM). Mr Andrews has sufficient experience which is relevant to the style of mineralisation and type of deposit under consideration and to the activity which he is undertaking to qualify as a Competent Person as defined in the JORC Code (2012 Edition) of the "Australasian Code for Reporting of Exploration Results, Mineral Resources and Ore Reserves." The Company confirms that the form and context in which the Competent Person's findings are presented have not been materially modified from the original market announcements

The information in this announcement and the ASX release dated 28th August 2026 relating to Ore Reserves for the North American Lithium project is based on, and fairly represents, information and supporting documentation prepared by Mr. Tony O'Connell an independent consultant employed by Optimal Mining Solutions Pty Ltd and is a member of the Australasian Institute of Mining and Metallurgy (AusIMM). Mr O'Connell has sufficient experience which is relevant to the type of deposits and mining method under consideration and to the activity which has been undertaken to qualify as a Competent Person as defined in the 2012 Edition of the "Australasian Code for Reporting of Exploration Results, Mineral Resources and Ore Reserves". The Company confirms that the form and context in which the Competent Person's findings are presented have not been materially modified from the original market announcements.

Forward Looking Statements

This press release contains certain forward-looking statements. Such statements include, but are not limited to, statements relating to "reserves" or "resources". Forward-looking statements are based on certain assumptions and involve known and unknown risks, uncertainties and other factors, many of which are beyond Elevra's control. Actual events or results may differ materially from the events or results expressed or implied in any forward-looking statement. There can be no assurance that such information will prove to be accurate as actual results and future events could differ materially from those anticipated in such forward-looking statements.

[8] See ASX release dated 11 May 2026, "*Elevra enters agreement to sell Ewoyaa Project Interest*".

For personal use only

Cautionary Statements

The Pre-Feasibility Study ("**PFS**") discussed in this announcement has been undertaken to assess the technical and economic viability of the brownfield expansion of the existing North American Lithium ("**NAL**") operation. The PFS is a comprehensive technical and economic study of the expansion project and includes a financial analysis based on reasonable assumptions regarding the applicable Modifying Factors and other relevant factors. The PFS has been prepared to a level of confidence sufficient to support the assessment of technical and economic viability and the estimation of Ore Reserves, as applicable. A PFS is, however, at a lower level of confidence than a Feasibility Study and the estimates and assumptions contained in the PFS remain subject to further refinement through subsequent engineering, design and project execution activities.

The PFS has provided Pre-Feasibility Study level estimates of production, capital and operating costs and financial returns. The production target and forecast financial information included in the PFS are based solely on the current NAL Ore Reserves reported in Elevra Lithium Limited's 2026 Annual Report released to ASX on 28 August 2026. No Inferred Mineral Resources or Exploration Targets are included in the production target or the economic analysis underpinning the PFS.

The PFS is based on the material assumptions outlined in the attached National Instrument 43-101 Pre-Feasibility Study, including assumptions regarding production rates, metallurgical recoveries, capital and operating costs, commodity prices, foreign exchange rates, permitting, project schedule and other applicable Modifying Factors. While Elevra considers that the material assumptions used in the PFS have a reasonable basis, actual results may differ materially from those anticipated in the PFS and there is no certainty that the assumptions will prove to be correct or that the outcomes indicated by the PFS will be achieved.

Based on the Company's current cost estimates and existing funding arrangements, Elevra considers the NAL Expansion to be fully funded. However, there can be no assurance that actual project costs will not exceed current estimates or that delays, changes in project scope, permitting requirements, market conditions or other circumstances will not result in additional funding requirements.

This announcement contains forward-looking statements, including statements concerning production targets, production rates, mine life, metallurgical recoveries, capital and operating costs, project timing, commodity prices, financial performance and other economic outcomes. These forward-looking statements are based on assumptions and expectations which Elevra considers reasonable as at the date of this announcement. However, forward-looking statements are subject to known and unknown risks, uncertainties and other factors, many of which are outside Elevra's control, which may cause actual results, performance or achievements to differ materially from those expressed or implied by those statements.

Given the uncertainties associated with forward-looking information and the fact that a PFS is at a lower level of confidence than a Feasibility Study, investors are cautioned not to place undue reliance on the PFS, the production target, forecast financial information or other forward-looking statements contained in this announcement.

For more information, please contact:

Andrew Barber

Investor Relations

Ph: +617 3369 7058

For personal use only

SEDGMAN
NOVOPRO

NAL Expansion FS

Mineral Reserves Pre-Feasibility Study

NI 43-101 Final Report Prepared for Elevra

ELEVRA

SN Document No.: B198-D01-02054-RT-0010 – MDV/mdv
Elevra Document No.: C102-0000-G-RAP-0002
Revision: 0

Sedgman Novopro Projects Inc
Registration Number: 1517259-4

SEDGMAN
© Copyright all rights reserved

A MEMBER OF THE CIMIC GROUP
CIMIC

For personal use only

Revision Status

Revision Number	Author	Description	Date	Approved By
A	MDV	Internal Review	07-Jul-2026	AM
B	MDV	Client Review	07-Jul-2026	AM
0	MDV	Final Issue	14-Aug-2026	AM

Distribution

Company Name	Contact Name	Revision	Date
Elevra	Patrick Wood	B	07-Jul-2026
Elevra	Patrick Wood	0	14-Aug-2026

Montreal Office
1350 Sherbrooke West, Suite 600
Montreal QC H3G 1J1
CANADA

T:+(514) 286-0004
E: montreal.admin@sedgman.com
W: www.sedgmannovopro.com

© Copyright all rights reserved

For personal use only

Table of Contents

1 Executive Summary 1
1.1 Introduction 1
1.2 Forward Looking Notice 2
1.3 Background 2
1.4 Property Description 3
1.5 Accessibility, Climate and Local Resources 4
1.6 History 4
1.7 Geology and Mineralization 4
1.8 Mineral Resource Estimate 5
1.9 Mineral Reserve Estimate 6
1.10 Mining Methods 6
1.11 Mineral Processing and Metallurgical Testing 10
1.12 Recovery Methods 10
1.13 Project Infrastructure 13
1.14 Environmental Studies, Permitting and Social or Community Impact 15
1.15 Market Studies and Contracts 16
1.16 Capital Cost and Operating Cost Estimates 17
1.17 Economic Analysis 18
1.18 Project Execution and Risk Assessment 20
1.19 Interpretations and Conclusions 21
1.20 Recommendations 22

2 Introduction 23
2.1 Purpose of the Report 23
2.2 Context 23
2.3 Study Contributors and Report Responsibility 24
2.4 Site Visits 25
2.4.1 Sedgman Novopro Site Visit 25
2.4.2 BBA Site Visit 25
2.4.3 Previous Site Visits 25
2.4.3.1 Sedgman Novopro Site Visit 25
2.4.3.2 Optimal Mining Site Visit 25
2.4.3.3 Other Site Visits 27
2.5 Sources of Information 27
2.6 Units of Measure and Glossary of Terms 27

3 Reliance on Other Experts 32
3.1 General 32
3.2 Mineral Claims and Surface Rights 32
3.3 Environmental and Social 32
3.4 Taxation 32

4 Property Description and Location 33
4.1 Property Location, Country, Regional and Government Setting 33
4.2 Mineral Tenure, Agreement and Royalties 36
4.2.1 Surface Rights 36

4.2.2 Mineral Rights and Permitting 38
4.2.3 Agreements and Royalties 38
4.3 Environmental Liabilities and Other Permitting Requirements 38
4.4 Mineral and Surface Purchase Agreements 39
4.5 Other Significant Factors and Risks 40
5 Accessibility, Climate, Local Resources, Infrastructure and Physiography 41
5.1 Accessibility 41
5.2 Topography, Elevation, Vegetation and Climate 41
5.2.1 Physiography 41
5.2.2 Vegetation 42
5.2.3 Climate 45
5.3 Local Infrastructure and Resources 45
5.3.1 Airports, Rail Terminals, and Bus Services 45
5.3.2 Local Workforce 46
5.3.3 Additional Support Services 46
6 History 47
6.1 General History 47
6.2 Historical Ownership & Activities 49
6.3 Historical Production 50
6.3.1 2012 – 2014 Production 51
6.3.2 2017 – 2019 Operations 51
6.4 2021 Acquisition to Present 52
7 Geology and Mineralization 53
7.1 Regional Geology 53
7.2 Local Geology 53
7.3 Property Geology 56
7.3.1 Volcanics 57
7.3.2 Granodiorite 57
7.3.3 Pegmatite Dykes 58
7.4 Mineralization 60
8 Deposit Types 62
8.1 Rare-Element Pegmatites of the Superior Province 62
8.2 La Corne Pluton Rare-Element Pegmatites 63
9 Exploration 65
10 Drilling 66
10.1 Drilling History 66
10.1.1 Historical (1942 – 1985) 66
10.1.2 Canada Lithium Corp. (2009 – 2011) 66
10.1.3 North American Lithium Corp. (2016 – 2019) 68
10.1.4 Sayona (2022) 68
10.1.5 Sayona (2023 – 2024) 69
10.2 Drilling Procedures 69
10.2.1 Collar Surveys 69
10.2.2 Downhole Surveys 70
10.3 Core Logging Procedures 70
10.3.1 Historical (1942 – 1985) 70
10.3.2 Canada Lithium Corp. (2009 – 2011) 70
10.3.3 North American Lithium Corp. (2016 – 2019) 71
10.3.4 Sayona (2022 – 2024) 71

For personal use only

10.4 Qualified Person's Opinion 72

11 Sample Preparation, Analyses and Security 73

11.1 Sample Preparation Methods 73
11.1.1 Historical (1942 – 1985) 73
11.1.2 Canada Lithium Corp. (2009 – 2011) 73
11.1.3 North American Lithium Corp. (2016 – 2019) 74
11.1.4 Sayona (2022-2024) 75
11.2 Analytical Laboratory Procedures 75
11.2.1 Canada Lithium Corp. (2009 – 2011) 75
11.2.2 North American Lithium Corp. (2016 – 2019) 75
11.2.3 Sayona (2022 – 2024) 76
11.3 QA/QC (Analytical) Procedures 76
11.3.1 Canada Lithium Corp. (2009 – 2011) 76
11.3.2 North American Lithium Corp. (2016 – 2019) 76
11.3.3 Sayona (2022) 77
11.3.4 Sayona (2023 – 2024) 77
11.4 Qualified Person's Opinion 77

12 Data Verification 78

12.1 Previous Audits and Reviews 78
12.2 Site Visits 78
12.2.1 Field Collar Validation 79
12.2.2 Drilling and Sampling Procedure Validation 79
12.2.3 Log and Core Box Validation 82
12.2.4 Validation Of Sample Preparation, Analytical, QA/QC and Security Procedures 82
12.3 Database Validation 82
12.4 Qualified Person's Opinion 82

13 Mineral Processing and Metallurgical Testing 83

13.1 North American Lithium – Historical Process Plant Operations 83
13.1.1 Québec Lithium Concentrator Operations (2013 – 2014) 83
13.1.2 North American Lithium Concentrator Operations (2017 – 2019) 84
13.1.3 Sayona Quebec Concentrator Operations (2023 – Present) 85
13.2 North American Lithium Testwork Program 86
13.2.1 North American Lithium Testwork Review Summary 86
13.2.2 Optical Ore Sorting Testwork (2011) 87
13.2.3 WHIMS Testwork (2014) 88
13.2.4 NAL Re-Start Metallurgical Testing (2016) 89
13.3 Blended Ore (NAL and Authier) Testwork Program 91
13.3.1 Preliminary Testwork (2019) 91
13.3.2 Prefeasibility Study Testwork (2021 – 2022) 93
13.3.2.1 Tailings Filtration Tests 96
13.3.3 Feasibility Study Testwork Program (2022 – 2023) 96
13.3.3.1 Composite Samples 96
13.3.3.2 Variability Samples 98
13.3.3.3 Composite Sample Testwork Results 99
13.3.3.4 Variability Sample Testwork Results 102
13.3.3.5 Testwork Analysis 103
13.4 Testwork Analysis 104
13.5 Current Testwork 105

14 Mineral Resource Estimate 106

14.1 Methodology 106

For personal use only

14.2 Database 107
14.3 Geological Interpretation and Domaining 107
14.4 Data Preparation 112
14.4.1 Exploratory Data Analysis 112
14.4.2 Compositing 112
14.4.3 Grade Capping 113
14.5 Density Estimation 114
14.6 Geostatistics and Grade Estimation 114
14.6.1 Variography 114
14.6.2 Block Model 116
14.6.3 Grade Interpolation 116
14.7 Block Model Validation 117
14.7.1 Visual Inspection 117
14.7.2 Swath Plots 118
14.8 Mineral Resource Classification 120
14.9 Economic Parameters and Cut-off Grade 121
14.10 Mineral Resource Statement 122
14.11 Grade Sensitivity Analysis 123
14.12 Iron Content 123
15 Mineral Reserve Estimate 125
15.1 Summary 125
15.2 Mineral Reserve Estimate 125
15.3 Mineral Reserve Estimation Process 126
15.4 Resource Block Model 126
15.5 Reserves Topography 127
15.6 Pit Optimization 128
15.6.1 Geotechnical Parameters 128
15.6.2 Loss and Dilution 129
15.6.3 Cut-off Grades 129
15.6.4 Costs and Revenue 129
15.6.5 Open Pit Optimization Results 130
15.7 Pit Designs 131
15.7.1 Pit Design Criteria 131
15.8 Life-of-Mine Schedule 131
15.9 Mineral Reserve Estimate Compared to Expanded Feasibility Study 131
16 Mining Methods 133
16.1 Pit Optimization 134
16.1.1 Optimization Inputs 134
16.1.2 Optimization Results 136
16.2 Mining Method 137
16.3 Geotechnical Consideration 137
16.3.1 Planning Around Underground Workings 137
16.3.2 Operational Considerations 138
16.4 Pit Design Parameters 138
16.4.1 Block Models 138
16.4.2 Pit Wall Parameters 139
16.4.3 Ramp Design Parameters 140
16.4.4 Final Pit Design 142
16.4.5 Material Flow Diagram 144
16.4.6 Modifying Factors 145

For personal use only

16.4.6.1 Metallurgical Recoveries *145*
16.4.6.2 Cut-Off Grade *147*
16.4.7 Main Pit Phase Designs 147
16.4.8 Lortie Lake 157
16.5 Life-Of-Mine Plan 158
16.5.1 Dig Solids 158
16.5.2 Waste Dump Designs 158
16.5.3 Waste Dump Solids 160
16.5.4 Dig Schedule Strategy 160
16.5.5 Mining Processes 160
16.5.6 Equipment 161
16.5.6.1 Time Usage Models *161*
16.5.6.2 Production Rates *162*
16.5.7 Mining Dependencies 162
16.5.8 Mining Constraints 162
16.5.9 Schedule Results 163
16.6 Key Dates 172
16.7 Mining Activities 172
16.7.1 Drilling and Blasting 173
16.7.2 Haulage Assumptions 174
16.7.3 Haulage Results 175
16.7.4 Road Maintenance 176
16.7.5 Mobile Mining Equipment 176
16.7.6 Water Management Strategy 177
16.7.7 Mine Personnel 177
17 Recovery Methods 178
17.1 Existing Plant Description 178
17.2 Process Improvements 178
17.2.1 HPGR Trade-off and Grinding Simulations 178
17.2.2 Plant Layout Considerations 179
17.2.3 Tailings Management 179
17.3 PFS Expansion Design 179
17.3.1 Process Design Criteria 180
17.3.2 Process Flowsheets 181
17.4 Process Description 183
17.4.1 Stage 1 Description 183
17.4.2 Stage 2 Description 184
17.4.3 Stage 3 Description 185
17.5 Production and Recoveries 185
17.6 Recommendations 186
18 Project Infrastructure 187
18.1 Access Roads 188
18.1.1 Public Roads 188
18.1.2 Site Roads 188
18.1.3 Security and Access Point 188
18.2 Electrical Power Supply and Distribution 190
18.2.1 Site Electrical Utility Supply 190
18.2.2 Site Electrical Distribution 190
18.2.3 Emergency Power Supply 190
18.3 Fuel Storage 190
18.4 Natural Gas and Propane 190

For personal use only

18.5 Water Supply 191
18.5.1 Water Reclaim System 191
18.5.2 Water for Fire Protection 191
18.5.3 Potable Water 191
18.5.4 Sewage and Waste 191
18.6 Tailings Storage Facility 192
18.6.1 Estimated Needs 192
18.6.2 Project Overview 192
18.6.2.1 Existing TSF-1 192
18.6.2.2 Planned Expansion Details: TSF-2 193
18.6.2.3 Planned Expansion Details: TSF-3 194
18.6.3 Regulatory and Compliance Requirements 197
18.6.4 Design Considerations 198
18.6.4.1 Tailings Material Characterization 198
18.6.4.2 Subsurface investigation extent 198
18.6.4.3 Embankment Configuration 198
18.6.4.4 Water Management 200
18.6.4.5 Seepage mitigation and control 201
18.6.4.6 Closure design 201
18.6.4.7 Monitoring 201
18.6.5 Risk Assessment and Challenges 201
18.6.6 Recommendations 202
18.7 Quebec Lithium Tailings Storage Facility Retaining Structure 203
18.7.1 Preliminary Geotechnical Design of the Retaining Structure for the Tailings Storage Facility (QL-TSF) at the Québec Lithium Tailings Management Area 203
18.7.2 Site Conditions 204
18.7.2.1 Assessment of Liquefaction Potential 204
18.7.3 Stability and Settlement Analysis of the Proposed Retaining Structure 206
18.7.3.1 Stability 206
18.7.3.2 Settlements 206
18.7.4 Risks 206
18.8 Lortie Lake Dyke 206
18.8.1 Design of the Lortie Lake Dyke 206
18.8.2 Sites Conditions 207
18.8.3 Stability and Settlement Analysis of the Lortie Lake Dyke 209
18.8.3.1 Stability 209
18.8.3.2 Settlement 209
18.8.4 Foundation Seepage Control 209
18.8.5 Lortie Lake Emergency Spillway 209
18.8.6 Risks 211
18.9 Site Water Management 211
18.9.1 Water Management Strategy 211
18.9.2 Basins and Ditches Design Criteria 212
18.9.3 Sediment Basins 212
18.9.3.1 Waste Rock Storage 4 Sedimentation basin 212
18.9.3.2 Pit Sedimentation Pond 213
18.9.4 Wastewater Treatment 214
18.9.5 Uncertainties 216
18.10 On-Site Buildings 216
18.10.1 Non-Mineral Waste Management 216
18.10.2 Explosives Magazines 216

For personal use only

18.10.3 Administration Office 216
18.10.4 Mine Workshop 216
18.10.5 Process Plant Building 217
18.10.6 Assay Lab 217
18.11 Communications 217
19 Market Studies and Contracts 218
19.1 Market Balance 218
19.2 Demand Forecast 219
19.3 Supply Forecast 219
19.4 Product Pricing 220
19.5 Contract Sales 220
19.6 Packaging and Transportation 221
19.7 Risks and Uncertainties 221
20 Environmental Studies, Permitting and Social or Community Impact 222
20.1 Summary 222
20.1.1 Permitting Stage 1.0 - Current Activities 222
20.1.2 Permitting Stage 2.0 - Milling Capacity Increase 222
20.1.3 Permitting Stage 3.0 Pit Expansion 223
20.2 Environmental Baseline and Impact Studies 223
20.2.1 Physical Environment 223
20.2.1.1 Climate 223
20.2.1.2 Topography 223
20.2.1.3 Geology 224
20.2.1.4 Geomorphology 224
20.2.1.5 Hydrography 224
20.2.1.6 Background Surface Water Quality 225
20.2.1.7 Background Sediment Quality 226
20.2.1.8 Hydrogeology 226
20.2.1.9 Groundwater Quality 227
20.2.2 Biological Environment 227
20.2.2.1 Vegetation 227
20.2.2.2 Wetlands 227
20.2.2.3 Aquatic Fauna 227
20.2.3 Social Considerations 228
20.2.3.1 Territory Use 228
20.2.3.2 Development and Activities 229
20.2.3.3 Land Use 229
20.2.3.4 Public Utilities Infrastructure 229
20.2.3.5 Recreation and Tourism Activities 229
20.2.3.6 Forestry and Agricultural Activities 229
20.2.3.7 First Nations 230
20.2.3.8 Archaeological and Heritage Potential 231
20.3 Project Permitting 231
20.3.1 Ministry of Environment, Fight Against Climate Change, Fauna, and Parks 231
20.3.2 Existing Permits 232
20.3.3 Ongoing Permitting Activities 232
20.3.4 Ministry of Natural Resources and Forests – Lands Sector 232

For personal use only

20.3.5 Ministry of Natural Resources and Forests – Forestry Sector 232
20.3.6 Department of Fisheries and Oceans of Canada 232
20.4 Other Environmental Concerns 233
20.4.1 Waste Rock, Tailings and Water Management 233
20.4.1.1 Tailings 233
20.4.1.2 Waste rock 233
20.4.1.3 Emissions of air contaminants 234
20.4.2 Regulatory Context 234
20.4.2.1 Provincial Procedure for Environmental Impact Assessment 234
20.4.2.2 Federal Procedure for Environmental Impact Assessment 234
20.4.2.3 Laws and Regulations for Environmental Impact Assessment 234
20.5 Social and Community Impacts 236
20.5.1 Consultation Activities 236
20.5.1.1 Committee Composition 236
20.6 Water Management 237
20.7 Mine Closure and Reclamation Plan 237
20.7.1 Financial Commitment for Mine Closure 238
20.8 Recommendations 238
21 Capital and Operating Costs 239
21.1 Capital Cost Estimate 239
21.1.1 Basis of Estimate 240
21.1.2 Exclusions 241
21.1.3 Sustaining Capital 242
21.2 Operating Cost Estimate 242
21.2.1 Labour 244
21.2.2 Power 245
21.2.3 Reagents 245
21.3 Author's Opinion 245
22 Economic Analysis 246
22.1 Reconciliation with Previous Scoping Study 247
22.2 Sensitivity Analysis 248
23 Adjacent Properties 251
24 Other Relevant Data and Information 252
24.1 Project Execution Plan 252
24.2 Project Risks and Opportunities 253
24.2.1 Risks 253
24.2.2 Opportunities 254
25 Interpretation and Conclusion 255
25.1 Geology and Resources 255
25.1.1 Geology 255
25.1.2 Mineral Resource Estimates 255
25.2 Mining 255
25.3 Metallurgy and Processing 255
25.4 Infrastructure and Water Management 256
25.5 Market Studies 256
25.6 Project Costs and Financial Evaluation 257
25.6.1 Capital Costs 257
25.6.2 Operating Costs 257

For personal use only

25.6.3 Project Economics 257

26 Recommendations 259

26.1 Geology and Resources 259
26.2 Mining and Reserves 259
26.3 Metallurgy and Processing 260
26.4 Waste and Water Management 260
26.5 Project Costs and Financial Evaluation 261

27 References 262

28 Qualified Persons 266

For personal use only

List of Tables

Table 1-1: North American Lithium – Mineral Resource Estimates (0.60% Li_2O cut-off grade for the RPEEE pit and 0.70% Li_2O cut-off grade for the underground domain) 5
Table 1-2: North American Lithium – Mineral Reserves Estimate, as at of June 30, 2026 6
Table 1-3: NAL Physicals by Phase 7
Table 1-4: General Process Design Criteria 11
Table 1-5: Capital Costs Summary ($M CAD) 17
Table 1-6: Sustaining Capital Summary 17
Table 1-7: Total OPEX Summary 17
Table 1-8: Main financial assumptions and results summary for the NAL Expansion Project 18
Table 1-9: Project Economics 18
Table 1-10: Expansion Scenarios - Previous Scoping Study and Present PFS 19
Table 1-11: Expansion $NPV_{8\%}$ Contribution - Staging/Throughput and Price Li_2O. 19
Table 1-12: Mineral Reserves PFS Recommendations 22
Table 2-1: Chapters Responsibility 24
Table 2-2: List of Abbreviations and Units of Measurement 28
Table 4-1: Mining Titles List and Details 37
Table 4-2: NAL Public Land Leases 39
Table 6-1: Summary of Ownership and Historic Activities 47
Table 6-2: Mine Production Statistics 50
Table 7-1: Geological Units 53
Table 7-2: Pegmatite Types in the Property 58
Table 7-3: Mineralogical Zoning of PEG1 Type Pegmatites (as Intersected in Core from Top to Bottom) 58
Table 10-1: Summary of CLC Drillholes 66
Table 10-2: Summary of North American Lithium Corp Holes 68
Table 10-3: Summary of Sayona Drillholes Completed in 2023 and 2024 69
Table 10-4: Summary of Canadian Lithium Corp. Core Logging Procedures 70
Table 10-5: Summary of North American Lithium Corp. Core Logging Procedures 71
Table 10-6: Summary of Sayona Core Logging Procedures 71
Table 11-1: Summary of CLC Sample Preparation Methods 73
Table 11-2: Summary of North American Lithium Corp. Sample Preparation Methods 74
Table 11-3: Summary of Sayona Sample Preparation Methods 75
Table 12-1: Geological Intervals Inspected During Site Visit 82
Table 13-1: Example Mineralogy of NAL Host Rock Types 86
Table 13-2: Example Assays of NAL Host Rock Types 87
Table 13-3: Assays of Ore Samples Tested 91
Table 13-4: Overview of Feed Samples Tested 91
Table 13-5: Final Spodumene Concentrate Grade (3-Stages of Cleaning) 93
Table 13-6: Assays of the Pegmatite and Host Rock Samples 93
Table 13-7: Mineralogy of the Pegmatite and Host Rock Samples 94
Table 13-8: Blended Ore Assays 94
Table 13-9: Reagent Dosages for Optimized Tests 94
Table 13-10: Final Spodumene Concentrate Assays 95
Table 13-11: Composite Sample Assays of the Pegmatite and Host Rock Samples 97
Table 13-12: Mineralogy of the Pegmatite and Host Rock Samples 97

For personal use only

For personal use only

Table 13-13: Blended Feed Assays 98
Table 13-14: Variability Sample Description 98
Table 13-15: NAL Variability Sample Assays: Pegmatite and Host Rock 99
Table 13-16: NAL Variability Sample Mineralogy: Pegmatite and Host Rock 99
Table 13-17: NAL Blended Variability Sample Assays 99
Table 13-18: Spodumene Concentrate Assays 102
Table 13-19: Variability Conditions 102
Table 13-20: Final Spodumene Concentrate Assays 103
Table 13-21: Testwork Conditions 104
Table 14-1: Drilling Data used in the Geological Model and Mineral Resource Estimate 107
Table 14-2: Bulk Density Values Employed for the Mineral Resource Estimate 114
Table 14-3: Variogram Parameters used for All Pegmatite Domains 115
Table 14-4: Search Ellipsoids 116
Table 14-5: Block Model Parameters used in Leapfrog Edge™ 116
Table 14-6: Summary of the Suggested Parameters from the KNA Analysis 117
Table 14-7: Summary of Parameters used for Li_2O Grade Interpolation 117
Table 14-8: Reasonable Extraction Factors 121
Table 14-9: NAL Mineral Resource Estimate – June 6, 2025 122
Table 14-10: Cut-Off Sensitivity Analysis (Open Pit Portion) 123
Table 14-11: Iron Content used for Mineral Resource Estimate 124
Table 15-1: NAL Reserves estimate as of June 30th, 2026 125
Table 15-2: Block Model Parameters 126
Table 15-3: Block Model Prototype 126
Table 15-4: Open Pit Optimization Slope Angles 128
Table 15-5: Open Pit Optimization Parameters 130
Table 15-6: Ultimate Pit Design Parameters 131
Table 16-1: Open Pit Optimization Parameters 134
Table 16-2: Open Pit Optimization Slope Angles 136
Table 16-3: Pit Optimization Results 136
Table 16-4: Block Model Parameters 139
Table 16-5: Block Model Prototype 139
Table 16-6: Material Properties 139
Table 16-7: Ultimate Pit Design Parameters 139
Table 16-8: Haul Road Design Criteria 140
Table 16-9: Cut-Off Grade Calculation Parameters 147
Table 16-10: Material Quantities by Phase 147
Table 16-11: NAL LOM Production Plan and Material Movement 164
Table 16-12: Key Dates 172
Table 16-13 Standard Blast Patterns 173
Table 16-14: Trucking Assumptions by Excavator 174
Table 16-15: Caterpillar 777G Truck Specifications 174
Table 16-16: Haul Road Segment Speed Restrictions 174
Table 16-17: Ramp Speed Restrictions 174
Table 16-18: Corner Speed Restrictions 175
Table 16-19: Mining Equipment Description and Maximum Number of Units 177

Table 17-1: HPGR Trade-off MCA Score Summary 179
Table 17-2: General Process Design Criteria 180
Table 18-1: Design Criteria Based on the Tailings Generation Rate 192
Table 18-2: TSF-2 and TSF-3 200
Table 18-3: Design Criteria for TSFs Water Management 201
Table 18-4: Technical Challenges of the Proposed TSF Design 201
Table 18-5: Technical Recommendations and Further Actions 202
Table 18-6: Results of the Stability Analyses for the Proposed Retaining Structure 206
Table 18-7: Results of the Stability Analyses of the Proposed Lortie Lake Dyke 209
Table 18-8: Risks associated with the Lortie Lake dyke and recommended works 211
Table 19-1: Forecast Sale Prices (USD/t, real 2025) 218
Table 20-1: Provincial and Federal Acts and Regulations 235
Table 20-2: New Water Management Infrastructure 237
Table 20-3: Total Cost of Closure Plan 238
Table 21-1: Capital Costs Summary by Major Area ($M CAD) 239
Table 21-2: Summarised Basis of Estimate 240
Table 21-3: Sustaining Capital Summary 242
Table 21-4: Total OPEX Summary 243
Table 21-5: Staff and Hourly Count (Sayona Employees) 244
Table 22-1: Main Financial Assumptions and Results Summary for the NAL Expansion Project 246
Table 22-2: Project Economics 246
Table 22-3: Expansion Scenarios - Previous Scoping Study and Present PFS 247
Table 22-4: Expansion $NPV_{8\%}$ contribution - Staging/Throughput and Price Li_2O. 247
Table 24-1: Project Risks 253
Table 24-2: Project Opportunities 254
Table 25-1: Main financial assumptions and results summary for the NAL Expansion Project 257
Table 25-2: Project Economics 258

For personal use only

List of Figures

Figure 1-1: NAL Property Location 3
Figure 1-2: Multiple Exposure of Pegmatite Dykes in the Pit (Face Looking West) 5
Figure 1-3: NAL Final Pit Design 6
Figure 1-4: Cross Section Through Final Pit Design and Geological Model 7
Figure 1-5: Annual Ore Processing 9
Figure 1-6: Annual Quantities by Phase 9
Figure 1-7: Simplified Overall Block Flow Diagram 12
Figure 1-8: Plan View of the proposed Retaining Structure 14
Figure 1-9: Plan View of the proposed Lortie Lake dyke 14
Figure 1-10: Lithium Market Balance Forecast 2027 – 2040 16
Figure 1-11: Lithium Product Historical and Forecast Pricing (Base Case) 16
Figure 1-12: Indicative Timeline 20
Figure 2-1: View of the Phase 1 Open Pit Operations 26
Figure 2-2: View of the Phase 2 Open Pit Operations 26
Figure 2-3: View of the Phase 3 Open Pit Operations 26
Figure 4-1: Property Overview Map 33
Figure 4-2: NAL Regional Property Location 34
Figure 4-3: NAL Property Location 35
Figure 4-4: NAL Mineral Titles 36
Figure 5-1: General Arrangement of Existing and Planned Infrastructure at the Mine Site 42
Figure 5-2: View Looking North-Westerly Across the Plant and Mine Site 43
Figure 5-3: View Looking South-Easterly Showing the Plant Facilities in the Foreground of the Tailings Impoundment Area 44
Figure 5-4: Val D'or Weather Normals (Source: climat.meteo.gc.ca) 45
Figure 6-1: Québec Lithium Project Open Pit Mine Operations at Peak in 2014 51
Figure 7-1: Stratigraphy of NAL Property 54
Figure 7-2: Local Geology of NAL Property 55
Figure 7-3: Geology of NAL Property, Centred on the Currently Interpreted Mineralized System 56
Figure 7-4: NE – SW Geological Cross-Section of Mineralized System 57
Figure 7-5: Coarse-Grained Pegmatite Dyke in Hole NAL-16-16 59
Figure 7-6: Spodumene Megacrystals Perpendicular to PEG2 Contact Zone in Hole QL-S09-026 59
Figure 7-7: Preferential Orientation of Spodumene Crystals in Hole NAL-16-024 59
Figure 7-8: Multiple Exposure of Pegmatite Dykes in the pit (Face Looking West) 60
Figure 7-9: Coarse to Fine-Grained Spodumene Mineralization in Hole NAL-16-024 61
Figure 7-10: Pegmatite Dyke Zoning and Alteration in Hole NAL-16-036 61
Figure 8-1: Chemical Evolution of Lithium-Rich Pegmatites 62
Figure 8-2: History of La Motte and La Corne Plutons 63
Figure 10-1: Property Map Showing Location of Drillholes Incorporated Within the Mineral Resource Estimate 67
Figure 10-2: Infill and Extension Drilling Program (Late 2016) 68
Figure 10-3: Core Logging Facilities at RNC Exploration Office in Amos (35 km from Site) 72
Figure 10-4: Core Storage Sheds and Facilities at the NAL Mine Site 72
Figure 12-1: View of the Open Pit Visited During the Site Tour 79
Figure 12-2: Core Storage Facility at the Project Site 80

For personal use only

Figure 12-3: Core Review at the Core Storage Facility 81
Figure 13-1: Monthly Spodumene Concentrate Production 84
Figure 13-2: Concentrate Grade and Lithium Recovery (Monthly Averages) 85
Figure 13-3: Ore Sorting Test Program Material (Pegmatite Upper Left, Granodiorite Upper Right, Basalt Lower) 88
Figure 13-4: Example Images of Sorted Products 88
Figure 13-5: Magnetic and Non-Magnetic Fractions from Test Conducted at 8,000 Gauss 89
Figure 13-6: Iron Rejection and Li Loss to Magnetic Concentrate for Pegmatite with 10% Granodiorite (Left) and 10% Basalt (Right) 90
Figure 13-7: Optimized Flotation Test Results 90
Figure 13-8: Grade – Recovery Curves 92
Figure 13-9: Fe_2O_3 vs. Li_2O in the Concentrate 92
Figure 13-10: Grade – Recovery Curves 95
Figure 13-11: Comparison of WHIMS Performance with Basalt vs. Granodiorite Host Rock 96
Figure 13-12: Composite Samples – Effect of Grind Size 100
Figure 13-13: Effect of Collector (FA-2) Dosage on Flotation Performance 101
Figure 13-14: Example of the Impact of Dilution on Flotation Performance 101
Figure 13-15: Example of the Impact of Dilution on Flotation Performance 102
Figure 13-16: Testwork Analysis: Grade-Recovery Correlation 103
Figure 13-17: 2023 DFS Testwork Grade-Recovery Curve 104
Figure 13-18: Li_2O Grade Recovery Curve including NAL Quarterly Performance 105
Figure 14-1: Area of Mineral Resource Estimate, Showing Mineralized Zone Locations at Elevation 350m 106
Figure 14-2: Plan View Showing Pegmatite Dykes and Drillhole Locations 108
Figure 14-3: Three-Dimensional Interpretation of Pegmatite Domains 109
Figure 14-4: Lithology Model for Volcanics, Granodiorite and Gabbro 110
Figure 14-5: Historical Mining Voids Adjusted to Fit Pegmatite Domains, Shown with Semi-Transparent Pegmatite Domains 111
Figure 14-6 – Distribution of the Length Before (Left) and After (Right) Compositing 112
Figure 14-7: Capping Analysis on All Dykes; Capping at 3.0% Li_2O 113
Figure 14-8: Variography Study in Supervisor (Example from Dyke A) 115
Figure 14-9: Cross-Section Looking West 118
Figure 14-10: Swath Plot for Mineralized Pegmatite Dyke A – Direction X 119
Figure 14-11: Swath Plot for Mineralized Pegmatite Dyke A – Direction Y 119
Figure 14-12: Classification Distribution on a Longitudinal Section of One Pegmatite Dyke, Looking Northeast 120
Figure 15-1: Starting Topographic Surface and Dig Solids 127
Figure 15-2: Geotechnical Regions 128
Figure 15-3: Pit Optimization Results 130
Figure 15-4: Final Pit – Plan View 132
Figure 15-5: Final Pit – Isometric View 132
Figure 16-1: NAL Final Pit Design 133
Figure 16-2: Geotechnical Regions 135
Figure 16-3: Pit Optimization Results 137
Figure 16-4: Underground Solids with Phases 4 to 8 (Phases 1 to 3 Removed) 138
Figure 16-5: Single-Lane in-Pit Haul Ramp Design 141
Figure 16-6: Dual-Lane in-Pit Haul Ramp Design 141

For personal use only

Figure 16-7: Final Pit – Plan View 142
Figure 16-8: Final Pit – Isometric View. 143
Figure 16-9: Final Pit Cross Section with Resource Block Model 144
Figure 16-10: Material Flow Diagram 145
Figure 16-11: Isometric View of Starting Position as of May 1st, 2026 149
Figure 16-12: Isometric View of Pit with Phase 3B Removed 149
Figure 16-13: Isometric View of Pit with Phases 3B to 3F Removed 150
Figure 16-14: Isometric View of Pit with Phases 3B to 4A Removed 150
Figure 16-15: Isometric View of Pit with Phases 3B to 4B Removed 151
Figure 16-16: Isometric View of Pit with Phases 3B to 4F Removed 151
Figure 16-17: Isometric View of Pit with Phases 3B to 5A Removed 152
Figure 16-18: Isometric View of Pit with Phases 3B to 5B Removed 152
Figure 16-19: Isometric View of Pit with Phases 3B to 5C Removed 153
Figure 16-20: Isometric View of Pit with Phases 3B to 5D Removed 153
Figure 16-21: Isometric View of Pit with Phases 3B to 5F Removed 154
Figure 16-22: Isometric View of Pit with Phases 3B to 6A Removed 154
Figure 16-23: Isometric View of Pit with Phases 3B to 6F Removed 155
Figure 16-24: Isometric View of Pit with Phases 3B to 7A Removed 155
Figure 16-25: Isometric View of Pit with Phases 3B to 7F Removed 156
Figure 16-26: Isometric View of Pit with Phases 3B to 8F Removed (Ultimate Pit) 156
Figure 16-27: Lortie Lake Location 157
Figure 16-28: Waste Dump and Tailings Storage Facility Locations 159
Figure 16-29: Annual Processed Tonnes and Li_2O Grade 163
Figure 16-30: NAL Ore Mining Summary 165
Figure 16-31: NAL Total Movements 165
Figure 16-32: Conceptual Isometric View of Mine as of 1st May 2026 166
Figure 16-33: Conceptual Isometric View of Mine as of 1st July 2026 166
Figure 16-34: Conceptual Isometric View of Mine as of 1st July 2028 167
Figure 16-35: Conceptual Isometric View of Mine as of 1st July 2030 167
Figure 16-36: Conceptual Isometric View of Mine as of 1st July 2032 168
Figure 16-37: Conceptual Isometric View of Mine as of 1st July 2034 168
Figure 16-38: Conceptual Isometric View of Mine as of 1st July 2036 169
Figure 16-39: Conceptual Isometric View of Mine as of 1st July 2038 169
Figure 16-40: Conceptual Isometric View of Mine as of 1st July 2040 170
Figure 16-41: Conceptual Isometric View of Mine as of 1st July 2042 170
Figure 16-42: Conceptual Isometric View of Mine as of 1st July 2044 171
Figure 16-43: Conceptual Isometric View of Mine as of 1st October 2045 (end of mining) 171
Figure 16-44: Section View of Mining Method 173
Figure 16-45: Haulage Modelling Results 175
Figure 16-46: Haulage Network 176
Figure 17-1: Simplified Block Flow Diagram 181
Figure 17-2: Simplified Process Flow Diagram 182
Figure 18-1: Preliminary Layout – Expansion 189
Figure 18-2: Plan view – Preliminary Mine Waste Storage Facilities Locations 193
Figure 18-3: TSF-2 Final configuration Layout 195

For personal use only

Figure 18-4: TSF-3 Final configuration Layout 196
Figure 18-5: Revised location of Bassin B5 once WR#4 encroach on the Bassin B5 197
Figure 18-6: Typical Cross Section of Peripheral Embankment 199
Figure 18-7: Plan View of the proposed Retaining Structure 204
Figure 18-8: Typical Cross-Section AA' of the Proposed Retaining Structure shown on Figure 18-7 205
Figure 18-9: Plan view of the proposed Lortie Lake dyke 207
Figure 18-10: Typical section BB' of the proposed dyke identified on Figure 18-9 208
Figure 18-11: Plan View of the Lortie Lake Emergency Spillway 210
Figure 18-12: Sedimentation basin WR#4 213
Figure 18-13: Conceptual design of the Pit Sedimentation basin 213
Figure 18-14: Flow Diagram at NAL Facility – Current Operating Conditions 214
Figure 18-15: Flow Diagram at NAL Site - Projected Operating Conditions 215
Figure 19-1: Lithium Market Balance Forecast 2027 – 2040 219
Figure 19-2: Lithium Product Price Actuals and Forecast 2026 – 2040 220
Figure 20-1: Location of Lakes Around NAL Operations 225
Figure 20-2: Provincial and Regional Routes Around NAL Operations 230
Figure 22-1: Sensitivity Analysis on $NPV_{8\%}$ 249
Figure 22-2: Sensitivity Analysis on $NPV_{8\%}$ Expansion Only (difference of Expansion and Base Cases) 250
Figure 24-1: Indicative timeline for the NAL Expansion Project 252

For personal use only

For personal use only

1 Executive Summary

1.1 Introduction

This Mineral Reserves Pre-Feasibility Study (PFS) National Instrument (NI 43-101) Technical Report was prepared at the request of Elevra Lithium Limited (Elevra). The purpose of this NI 43-101 Report is to provide an update to the mineral reserves estimates for the expansion of the North American Lithium (NAL) mine. Elevra serves as the registrant of this NI 43-101-compliant Report. The statement is based on information provided by Sayona Québec and reviewed by various professionals and Qualified Persons (QP).

The information in this Report related to Mineral Resources is based on, and fairly represents, information compiled by the QPs as of the effective date of the Report. Qualified persons who contributed to the drafting of this Report meet the definition of QPs, consistent with the requirements of the NI 43-101 Code. All QPs are independent of the issuer.

This Report provides information from previous reports as context to support the expansion assessment against a base case scenario. The economic analysis presented in this Report was undertaken on the Mineral Reserves as of May 1st, 2026. The Mineral Reserves are based on measured and indicated mineral resources only. Inferred mineral resources have not been considered in the analysis as these are considered too geologically speculative to have mining and economic considerations applied to them.

The North American Lithium (“NAL”) property is wholly owned and operated by Sayona Québec Inc. (“Sayona Québec”), with Elevra owning 100% of Sayona Québec following the merger between Sayona Mining Limited (“Sayona”) and Piedmont Lithium Inc. The NAL property is considered material to Elevra.

The NAL mine site was established in 2012 and has operated during a number of campaigns based on fluctuating commodity pricing. The plant was most recently restarted in 2022 and following a period of ramp up and process optimisation, Elevra now proposes to increase production through a three-stage approach as follows:

- Stage 1: An initial 15-20% increase in annual spodumene concentrate production above current production levels commencing in mid-CY27 with an incremental reduction in unit operating costs. This increase is within the current limits of the milling permit set at 4,500 tpd.
- Stage 2: A subsequent expansion of downstream milling, flotation and filtration capacity to 6,500 tpd. The incremental feed material will be processed using a temporary mobile crushing circuit operating in conjunction with the existing crushing circuit. The further expanded production is expected to commence early CY28, with an additional incremental reduction in unit operating costs; and
- Stage 3: The replacement of the temporary mobile crushing circuit and the existing crushing circuit with a new crushing circuit capable of meeting feed requirements for a LOM average production of 373ktpa post-expansion. This final step will include additional ore sorting capacity and is expected to be completed in early CY29 delivering crushing cost efficiencies which are required to meet the anticipated LOM cost reduction.

Sedgman Novopro Projects Inc. (Sedgman Novopro) was engaged by Elevra in Q1 2026 to complete the Mineral Reserves PFS for major plant and infrastructure expansions to increase spodumene concentrate production at the NAL operation. This Report was prepared as a collaborative effort between Sedgman Novopro, Optimal Mining Pty Ltd (Optimal Mining), BBA, Measured Group Pty Ltd (Measured Group), and Englobe Corp. (Englobe).

For personal use only

1.2 Forward Looking Notice

Sections of the Report contain estimates, projections and conclusions that are forward-looking information within the meaning of applicable Canadian securities laws. Such statements and information involve known and unknown risks, uncertainties and other factors that may cause the actual results, performance or achievements of Elevra, its project, or industry results, to be materially different from any future results, performance or achievements expressed or implied by such forward-looking statements or information. Such statements can be identified by the use of words such as "may," "would," "could", "will," "intend," "expect," "believe," "plan," "anticipate," "estimate," "scheduled," "forecast," "predict" and other similar terminology, or state that certain actions, events or results "may," "could," "would," "might" or "will" be taken, occur or be achieved. These statements reflect Elevra's current expectations regarding future events, performance and results and speak only as of the date of this Report.

Mineral Resources that are not Mineral Reserves do not have demonstrated economic viability. There is no certainty that any Mineral Resources will be converted into Mineral Reserves. The estimation of Mineral Resources is inherently uncertain and involves subjective judgments about many relevant factors. Assumptions and interpretations underlying resource estimates may change over time as new information becomes available.

Forward-looking statements are based upon the responsible QPs opinion at the time that they are made but, in most cases, involve significant risk and uncertainty. Although the responsible QP has attempted to identify factors that could cause actual events or results to differ materially from those described in this Report, there may be other factors that cause events or results to not be as anticipated, estimated, or projected. None of the QPs undertake any obligation to update any forward-looking information. There can be no assurance that forward-looking information in any section of the Report will prove to be accurate in such statements or information.

Accordingly, readers should not place undue reliance on forward-looking information.

IMPORTANT NOTICE

This document is not for filing or distribution in the US.

1.3 Background

Sayona Québec acquired the North American Lithium Inc. mine and concentrator in La Corne, Québec, in August 2021. The operation, which had been placed on care and maintenance in 2019, and has been restarted since Fall 2022, includes an open pit hard rock mine, exploiting lithium-bearing pegmatite dykes, with mineral processing and lithium carbonate production facilities.

This Report has been prepared at the request of Elevra, the registrant, to present the results of the Mineral Reserves PFS of a NAL expansion.

The Project's property (the "Property") has seen historic production from an underground mine (1950s-1960s) with production of spodumene concentrate and lithium chemicals. More recently the mine and concentrator operated under Québec Lithium (2013-2014) and North American Lithium (2017-2019). Since acquisition on August 26th, 2021, Elevra Lithium has resumed open-pit mining and restarted concentrator operations, producing spodumene concentrate since Q1-2023.

1.4 Property Description

The NAL Expansion Project properties (the “Properties”) are situated in the La Corne Township in the Abitibi-Témiscamingue region in the Province of Québec, Canada (Figure 1-1). The Project is located approximately 38 km southeast of Amos, 15 km west of Barraute and 60 km north of Val-d’Or in the Province of Québec, Canada. The Project is approximately 550 km north of Montréal and is serviced by road, rail, and air.




Figure 1-1: NAL Property Location

For personal use only

For personal use only

1.5 Accessibility, Climate and Local Resources

The town of Val-d'Or, with a population of approximately 32,750 residents (Canadian Census, 2021), is located 60 km south of the Property, along the provincial Highway 111. Since Val-d'Or was founded in the 1920s, it has been a mining service centre. Val-d'Or is one of the largest communities in the Abitibi region and has all major services, including an airport with scheduled service from Montréal. Val-d'Or is a 6-hour drive from Montréal, and there are daily bus services between Montréal and the other cities and towns in the Abitibi region. The town of Amos, with a population of approximately 12,675 residents (Canadian Census, 2021), is located approximately 38 km northwest of the NAL site. Amos is served by highways 109, 111, and 395 and the Amos/Magny airport.

The site is accessible by provincial Highway 111, connecting Val-d'Or and Amos, or alternatively by provincial Highway 397, connecting Val-d'Or and Barraute. An all-weather secondary road, known as Route du Lithium, connecting the site to the Val-d'Or – Amos highway, which was used to traverse the Property and which constrained pit operations, has now been relocated to avoid the mining area. The site is also accessible from Mont-Vidéo, through an all-weather road that connects further east to the Val-d'Or – Barraute highway. Canadian National (CN) railway line is about 49 km east of the Property, connecting east through to Montréal and west to the North American rail network. A high-voltage power line (120 kV) passes approximately 2 km to the west of the Property and a 25 kV electric line, running along the Route du Lithium, services the Mont-Vidéo ski and recreation area

The Val-d'Or area experiences a subarctic continental sub-humid climate, characterized by short, cool summers and long, cold winters. The climatic conditions at the Property do not significantly impede the Project or hinder exploration or mining activities, beyond seasonal consideration for certain works (e.g., drilling muskeg swamps during winter freeze).

1.6 History

There is a significant history of exploration and mining activities on the Property including underground mining operations dating back to the 1950s. Sayona Québec acquired the NAL project in August 2021. A Prefeasibility Study (PFS) was completed in May 2022 for the restart of mining and concentrator operations. Significant process plant upgrades were implemented to ensure production of high-quality chemical-grade spodumene concentrate at nameplate capacity. Operation of the concentrator commenced in March 2023, with first spodumene concentrate sold in August 2023. The mine is a currently operating spodumene producer.

1.7 Geology and Mineralization

Results of past mineral exploration, resource evaluation and mining demonstrate that NAL is an extensively mineralised lithium system. The primary metal is lithium, and it is mainly associated with spodumene, a lithium bearing pyroxene.

North American Lithium's pegmatite dykes occupy an area spanning 3,550 m along strike, 1,300 m in width and 800 m in depth. A total of 117 spodumene-bearing pegmatite dykes each with thicknesses greater than 2 m and up to 70 m are open at depth and have been identified in the NAL geological model shown in Figure 1-2.

Individual spodumene-bearing pegmatite dykes are relatively continuous where exposed over long distances and across several benches in NAL pit. Spodumene-bearing pegmatite dykes vary in width from tens of centimetres, up to 70 m and are interpreted to extend for several hundred meters in length. Most pegmatite dykes greater than 3 m in width are spodumene-bearing.

For personal use only




Figure 1-2: Multiple Exposure of Pegmatite Dykes in the Pit (Face Looking West)

The Project database used in the Mineral Resource estimate includes drillhole and sample information collected from the 2009, 2010, 2011, 2016, 2019, 2023 and 2024 as well as sample information collected from historical drill core during 2022.

The Project database comprises 923 surface-collared and 652 underground-collared diamond drillholes with a cumulative length of 221,404 m. A subset of 562 drillholes totalling 153,047 m were used to create the Mineral Resource estimate.

Quality assurance and quality control ("QA/QC") procedures that conform to current industry standards were developed and implemented for all the drilling and sampling programs.

1.8 Mineral Resource Estimate

The project database contains data from 1,575 diamond drillholes surfaces and underground collared, spanning a total of 27,183 records of Li_2O assays with a mean sample length of approximately 0.884 m. Li_2O grade varies from 0.000% to 5.318%. Global average Li_2O grade for raw samples (excluding 0.00% assays) is 0.783%. From this database, a subset of 562 surface collared drillholes totalling 153,047m was used for the Mineral Resource estimate.

The current Mineral Resource Estimate is presented in Table 1-1 below. The Mineral Resource estimate was prepared by Qualified Persons in accordance with the NI 43-101 Code.

Table 1-1: North American Lithium – Mineral Resource Estimates (0.60% Li_2O cut-off grade for the RPEEE pit and 0.70% Li_2O cut-off grade for the underground domain)

Resource Classification	Method	Tonnes (Mt)	Li_2O Grade (%)	Cut-Off Grade (%)
Indicated	Open Pit	74.46.2	1.17	0.60
Inferred	Open Pit	8.6	1.13	0.60
Indicated	Underground	-	-	-
Inferred	Underground	10.3	1.01	0.70
Total		93.3	1.15	

The information on Mineral Resources and Ore Reserves is extracted from the announcement entitled "2026 Annual Report" published on the ASX on August 28th, 2026, and is available to view on the Elevra's website on the ASX Increases" published on the ASX on August 27th, 2025, and is available to view on Elevra's website on the ASX.

For personal use only

The company confirms that it is not aware of any new information or data that materially affects the information included in the original market announcement and, in the case of estimates of Mineral Resources, that all material assumptions and technical parameters underpinning the estimates in the relevant market announcement continue to apply and have not materially changed. The company confirms that the form and context in which the Qualified Person's findings are presented have not been materially modified from the original market announcement.

1.9 Mineral Reserve Estimate

The NAL Mineral Reserve estimate has been prepared using accepted industry practice and in accordance with NI 43-101 reporting standards, by Mr Tony O'Connell who is an employee of Optimal Mining Solutions Pty Ltd, an independent mining consultancy based in Brisbane, Australia.

The North American Lithium Mineral Reserves have been estimated for a total of 47.2Mt of Proven and Probable Mineral Reserves at an average grade of 1.12% Li_2O, which is comprised of 0.2Mt of Proven Mineral Reserves at an average grade of 0.93% Li_2O and 47.0Mt of Probable Mineral Reserves at an average grade of 1.12% Li_2O, as shown in Table 1-2 below.

Table 1-2: North American Lithium – Mineral Reserves Estimate, as at of June 30, 2026

Resource Classification	Tonnes (Mt)	Li_2O Grade (%)	Cut-Off Grade (%)	Fe Grade (%)
Proved Mineral Reserves	0.2	0.93	0.60	1.48
Probable Mineral Reserves	47.0	1.12	0.60	0.81
Total	**47.2**	**1.12**	**0.60**	**0.81**

1.10 Mining Methods

The NAL final pit design, as shown in Figure 1-3, was based on a pit optimisation assessment which determined the economic limits of the deposit.



Figure 1-3: NAL Final Pit Design

For personal use only

The final pit was designed with one main haul road servicing the entire pit for the life of the mine. The decision to utilise one main haul road was chosen based on reducing the strip ratio, pit shell disturbance area and operating cost for the operation. The main haul road has been designed on the hanging wall side of the deposit to maximize ore recovery within the pit shell and to provide access for the final mining pushback. A secondary haul road has been designed along the south-west limit of the pit to access phase 8, one of the last phases to be mined.

Figure 1-4 shows a cross section through the final pit design and the geological model, with the modelled Li_2O-containing pegmatites clearly visible.




Figure 1-4: Cross Section Through Final Pit Design and Geological Model

A series of six mining phases, numbered 3 through 8 inclusive, were developed including the ultimate pit design. Special attention was given to the historical underground openings when setting the physical limits for every phase. Consideration was taken to ensure that the phase walls did not intersect the old workings. The following criteria was applied during the phase design construction:

- Minimum mining width of 60m considered between phases on the surface and 40m at the phase base.
- Ease of access to different mining areas.
- Mining and processing production rate.
- Physical constraints posed by historical underground workings.

The phase-by-phase quantities and qualities are summarised in Table 1-3.

Table 1-3: NAL Physicals by Phase

Item	Units	Total	Phase 3	Phase 4	Phase 5	Phase 6	Phase 7	Phase 8
Total In-Pit	(dMt)	**385.2**	30.0	54.8	56.5	48.0	180.8	15.1
Waste Rock	(dMt)	**337.9**	24.8	47.4	50.4	41.1	160.9	13.3
ROM Ore	(dMt)	**47.3**	5.2	7.4	6.2	6.9	19.9	1.8
Lithium Grade	(% Li_2O)	**1.12%**	1.15%	1.08%	1.06%	1.24%	1.11%	1.03%
Iron Grade	(% Fe)	**0.81%**	0.89%	0.89%	0.86%	0.72%	0.79%	0.73%
Strip Ratio	(t waste : t ore)	**7.1**	4.8	6.4	8.2	6.0	8.1	7.4

For personal use only

Each of the phases was then subdivided into sub-phases to allow for a more detailed progressive development of the operation. The sub-phases developed were:

- Phase 3 - 3B and 3F,
- Phase 4 - 4A, 4B and 4F,
- Phase 5 - 5A, 5B, 5C, 5D and 5F,
- Phase 6 - 6A and 6F,
- Phase 7 - 7A and 7F,
- Phase 8 - 8F.

A life-of-mine schedule was developed for the PFS using Micromine's Spry software package. The schedule utilised two stages of capital investment which gradually increased the processing production rate up to 6,500 tonnes per day. The dates and subsequent increase in processing rate are summarised below:

- Initial production rate - 3,780 tonnes per day
- Stage 1 - 4,500 tonnes per day from 1st July 2027
- Stage 2 - 6,500 tonnes per day from 1st April 2028

Additionally, an ore sorting circuit came online on 1st July 2029 with a throughput of 1.1mt per annum.

The life-of-mine schedule utilized similar class equipment that is currently operating at site, with a larger 200t-class excavator added to the fleet to assist with maintaining the required stripping quantities.

The key highlights of the LOM plan are summarized below:

- Mine life of approximately 19 years – from May 2026 to September 2045,
- Total of 47.3mt of ore mined.
- Total of 337.9mt of waste mined, leading to an overall strip ratio of 7.14:1, which fluctuates over the years.
- 17.7mt of ore sent to the ore sorting circuit at an average grade of 0.96% Li_2O and 1.00% Fe.
- 14.4mt of product from the ore sorter at an average grade of 1.08% Li_2O and 0.69% Fe.
- 44.0mt of ore sent to the processing plant at an average grade of 1.17% Li_2O and 0.66% Fe.

The annual ore tonnes and ROM Li_2O feed grade are shown in Figure 1-5. Annual movements from each of the phases across the life-of-mine is shown in Figure 1-6.

For personal use only




Figure 1-5: Annual Ore Processing




Figure 1-6: Annual Quantities by Phase

The difference between the Mineral Reserve estimate and the total quantities mined in the Expansion Feasibility Study is due to the differing start dates. The Expansion Feasibility Study commences on 1st May, 2026, however the Mineral Reserves are declared at the slightly later date of June 30th, 2026. The Expansion Feasibility Study mines a total of 47.3mt from the pit, whereas the Mineral Reserve Estimate (pit only) is 47.0mt.

For personal use only

1.11 Mineral Processing and Metallurgical Testing

The NAL deposit has undergone extensive metallurgical test work. Metallurgical recovery assumptions are based on historical metallurgical tests and test work completed during 2018 – 2023. Test work programs began in 2008 to establish the metallurgical character of the orebody, and allow the development of a process flowsheet, testing of that flowsheet, evaluate the impact of head grade on performance and then produce the engineering data for plant design. This test work occurred under the supervision of independent QPs and Sayona representatives.

The test work evaluated a number of processing techniques including flotation, DMS, LIMS and ore sorting. The progression of this test work took the form of batch scale tests looking at flotation, DMS and grindability leading to locked cycle tests flotation tests and then pilot scale continuous tests. WHIMS and DMS were not included in the original flowsheet based on the outcomes of the test work. The test work outcomes formed the design basis of the NAL concentrator that commenced operation in March 2013 but ceased operation in September 2014. This was principally due to higher than anticipated dilution of the ore with host rock, and lower than target spodumene recovery and concentrate grade.

Subsequent test work programs were undertaken to characterise and mitigate the effect of the dilution including hardness testing and WHIMS test work (on both plant samples and pegmatite samples of varying levels of dilution of the two major dilution host rocks). The impact of the WHIMS on flotation was also examined, and the final spodumene flotation concentrate was 6% Li_2O at an estimated test work recovery of 80 to 83%.

Historical metallurgical test work from the above-described previous phases, along with current operational performance has been used as the basis for the NAL expansion Mineral Reserves PFS. The following programs are nearing completion:

- Geometallurgical program based on Life of mine sample selection to provide additional data on ore behaviour throughout the mine life.
- XRT ore sorting testwork.

Based on the previous laboratory test work and current operational performance, an average global recovery of 71.2% at a spodumene concentrate grade of 5.4% Li_2O has been applied to the Expansion Case for the purposes of the study.

1.12 Recovery Methods

The recovery methods for the Project were established based on the existing plant, historical operational data, historical metallurgical testwork, and lessons learned from other spodumene projects. The expansion process design is based on the operational and metallurgical reviews of the past process plant operation and testwork data.

The design developed for the Mineral Reserves PFS captures opportunities which were previously identified during the previous Updated Scoping Study. The work completed established the design basis of the plant, capital costs, and operating costs that were developed in this Mineral Reserves PFS.

The NAL expansion is based on a staged approach to reach authorised processing plant capacities:

- Stage 1: Increase of 15-20% in spodumene concentrate production within the 4,500 tpd permit.
- Stage 2: Expansion to a new milling throughput limit of 6,500 tpd average annual rate.
- Stage 3: New crusher circuit (milling capacity unchanged from Stage 2)

For personal use only

The targeted capacities will be achieved through the following modifications to the existing facility:

- Stage 1: Plant optimization
  - Addition of lump breakers in the ore feed circuit to the plant to prevent ice lumping
  - Increased stacksizer capacity to the existing ball mill circuit
  - Optimization of the desliming and magnetic separation circuit
  - Increased flotation conditioning capacity
  - Refurbishment of carbonate filtration unit for new spodumene dewatering and filtration unit
  - Replacement of existing thickener with a larger process thickener
  - Addition of a flotation thickener circuit to prevent flotation reagent contamination
  - Reconfiguration of tailings pumping to TSF
- Stage 2: Plant expansion
  - Contracting of a temporary crusher to balance plant feed with existing crusher
  - Addition of a second rod mill and ball mill line circuit including stacksizers
  - Addition of a trash screen to remove oversize (+1mm) material before magnetic separation
  - Addition of a third magnetic separation line to match increase throughput
  - Addition of a new rougher unit and conversion of the existing rougher to scavenger duty
- Stage 3: New crusher construction
  - Construction of new crusher to handle target throughput
  - Construction of new fine covered ore stockpile complete with reclaim and conveyors
  - Conversion of the existing crusher circuit to an ore sorting facility

The key design criteria for the various stages of the expansion are summarized in Table 1-4 below. The design will be based on the existing mine and facility, the lithium recovery anticipated is 71.20% and is based on improvements to current plant performance of 69.00% recovery. The recovery is also based on a plant feed Li_2O grades presented below and a target concentrate Li_2O grades of 5.40%. The financial model considers a LOM average annual 5.4% Li_2O concentrate production rate of 348 ktpa (or 373 ktpa post expansion). These rates are superior to the process design criteria due to the production rate being dependant on the plant feed grade; the financial model considers a 1.17% feed grade. The process design is based on lower grades but supports the rates used in the financial model.

Table 1-4: General Process Design Criteria

Criterion	Unit	Base Case	Stage 1	Stage 2	Stage 3
Crushing Plant Availability	%	65	65	65	65
Processing Plant Availability	%	90	90	90	90
Total ROM Crusher Feed	tpd	5,815	6,646	10,000	10,000
Total Processing Plant Feed	tpd	3,780	4,320	6,500	6,500
Plant Feed Li_2O Grade	%	1.01	1.095	1.080	1.080
Target Concentrate Li_2O grade	%	5.40	5.40	5.40	5.40
Target Concentrate Production	tpa	178,058	213,670	338,000	338,000
Concentrate P80	mm	0.200	0.232	0.200	0.200

The recovery benefits will come from the following flowsheet improvements:

- Improved flotation feed sizing due to increased classification capacity and mill power.
- Improved magnetic separation circuit (LIMS and WHIMS)
- Improved flotation conditioning
- Improved rougher flotation control and flexibility
- Improved cleaner tails handling

For personal use only

These improvements targeting specific areas will lead to recovery gradually increasing through the staged approach with the full benefits achieved by Stage 2 with all optimisations captured.

The expansion is scheduled to produce an annual average rate of 6,500 tpd of blended ore. The existing crusher, ore sorting, new crusher and ore storage areas are designed to operate with an availability of 65%. The processing plant, including the grinding, classification, desliming, magnetic separation, flotation and dewatering units, is designed to operate at 90% availability. The processing plant will operate on a 24-hour per day and 7 days per week basis.

The expansion block flow is given below in Figure 1-7.




Figure 1-7: Simplified Overall Block Flow Diagram

For personal use only

1.13 Project Infrastructure

Site infrastructure at the NAL operation is established and operating. Additional infrastructure is required to the meet the requirements of the expansion, which includes:

- An expansion of the open pit and associated water management infrastructure
- Pit sedimentation basin
- New crushing and ore sorting circuit including crushed ore dome
- New grinding, magnetic separation and flotation
- Concentrate dewatering filters
- Tailings thickeners
- An extension of the concentrate storage building
- Additional mechanical workshop, operation room, and supervisor offices
- Additional tailings management facilities and associated water management infrastructure:
  - TSF-2 (required for base case and expansion)
  - TSF-3 (required for base case and expansion)
- An additional waste stockpile area (WR#4) and associated water management infrastructure.
- Multi-service buildings:
  - Additional offices, engineering, administration etc.
  - Additional capacity for the mine change rooms, showers and ablutions
  - Additional mine offices and mining dispatch control room
- Mine maintenance shop:
  - Two additional mining service bays
  - Additional warehouse storage
  - Additional supervisory and administration offices
  - Wash bay
- Auxiliary buildings:
  - Warehouse domes
  - Relocation of the mine fuel depot and additional capacity. (required for base case and expansion)

The spodumene pegmatite deposit on the Québec Lithium property was mined between 1954 and 1965. At that time, the deposit was developed from a vertical shaft, and the mine tailings were contained within two dikes located north of the former mine, in an east–west-oriented valley between Lortie and Roy lakes. Waste rock was deposited around the perimeter of this storage area, thereby contributing to the containment and retention of the mine tailings.

Following the planned expansion of the current pit, the pit walls will intersect the Québec Lithium tailings storage facility (QL-TSF). As a result, a portion of the tailings currently in place will need to be excavated, leaving part of the remaining tailings without containment.

The proposed retaining structure at the QL-TSF is intended to ensure the stability of the overburden and tailing slope at this location. In addition, the structure will provide long-term containment and retention of the remaining tailings, thereby ensuring the continued integrity and safe management of the QL-TSF during and after pit expansion operations. The proposed retaining structure at QL-TSF is located in the central portion of the tailings storage area, as shown in Figure 1-8.




Figure 1-8: Plan View of the proposed Retaining Structure

As part of the open pit expansion, the construction of a dyke at Lortie Lake is being considered to allow the extraction of mineral resources located beneath a portion of the waterbody. This dyke is intended to maintain the water level in the retained section of the lake, notably to limit impacts on fish habitat, while ensuring safe conditions for mining operations. The dyke will be located in the northern portion of Lortie Lake, north of the projected pit as shown Figure 1-9.




Figure 1-9: Plan View of the proposed Lortie Lake dyke

For personal use only

For personal use only

1.14 Environmental Studies, Permitting and Social or Community Impact

The expansion projects are to proceed in stages to reflect the permitting requirements for each stage:

1. Permitting Stage 1.0 – reaching a 15-20% increase in the plant's capacity under the limit of 4,500 tpd, to be carried out in accordance with current regulations.

2. Permitting Stage 2.0 - increasing the plant's capacity to 6,500 tpd (''Milling capacity''). This includes infrastructure for Tailings Storage Facility TSF no.2.

3. Permitting Stage 3.0 - expansion of the mine pit for Phases 6 through 8. (''Pit expansion''). This includes tailings Storage facility TSF no. 3 and Waste Rock Pile HS no.4

Since the restart of operation in 2023, the site is staffed with a complete environmental team that ensures compliance with regulatory procedures and monitors social environmental activities at the site. The NAL project has existing environmental permits for mining operations including the disposal of waste rock, storage of tailings, water supply from open pit and tailings and final release of treated water to the environment. Permitting required for Stage 2.0 are currently in the application process and will be obtained in the coming months. For example, TSF-2 authorizations will soon be submitted to provincial authorities to obtain ministerial approval under section 22 of the Environment Quality Act (Q-2). Elevra received final approval for Waste Rock Pile #2 (HS) for several years of production.

Regarding the plant's capacity expansion, the project will be submitted in three main phases to the government authorities for permitting based on the addition of various equipment. It should be noted that the plant capacity expansion to 6500 tpd will be made within the current building's footprint. The Government of Quebec guidelines regarding permitting requirements for capacity increase are subject to the standard authorization process under Section 22 of the Environment Quality Act, as long as the plant's capacity increase does not exceed 50% and is limited to 6,500 tons per day. Regarding federal authorities, Elevra has also received confirmation that the increase in the plant's capacity is not subject to the environmental assessment process under the Physical Activities Regulations (SOR/2019-285), provided that the total infrastructure, including the plant's capacity, remains within a 50% increase.

The expansion of the mining pit will affect Lortie Lake by partially impacting the aquatic environment and fish habitat. The Regulation respecting the environmental impact assessment and review of certain projects (Q-2, r. 23.1) specifies in Section 2.2 of Schedule 2 that any project affecting an area greater than 15,000 m² of a lake or river must be submitted to the environmental assessment process, including a public hearing by the Bureau d'Audiences Publiques sur l'Environnement (BAPE). The pit expansion involves draining an area of several hectares of the lake, thereby triggering the provincial process for BAPE hearings. Accordingly, the Ministry of the Environment, Climate Change, Wildlife, and Parks (MELCCFP) has confirmed that the project will be subject to the provincial environmental impact assessment process. This assessment will require that the planned new mining infrastructure—TSF#3 and HS#4— be evaluated alongside the pit expansion.

For its part, the Department of Fisheries and Oceans Canada (DFO) will require that the impacts of mining activities on the fish habitat in Lortie Lake be offset by an approved habitat compensation project. Consultation will be undertaken with First Nations for the design of the compensation project(s). The new mining infrastructure (TSF & HS) could take place within a fish habitat, which would require registration under Appendix II of the Metal and Diamond Mining Effluent Regulations (SOR/2002-222). To do so, Elevra will need to demonstrate that the chosen solution was selected in accordance with the Guidelines for the Assessment of Alternatives for Mine Waste Disposal, as required by the Department of Fisheries and Oceans (DFO).

The extension of mineral resources under Lortie Lake will require the approval from the MRNF for the conversion of this lease area to a mining lease. The MRNF will require an update to the Closure and Rehabilitation Plan and the update of the approval by the MELCCFP. The BAPE process will provide the necessary decree to obtain the permits required for the conversion of the area to a mining lease.

For personal use only

1.15 Market Studies and Contracts

Global lithium supply is expected to increase materially in 2026, despite the pricing pressure seen through much of 2025. Supply is forecast to rise by around 250 kt LCE year-on-year, or approximately 15%, including recycling. Despite strong supply growth, the market is still expected to remain in deficit in 2026, as robust demand growth, particularly from electric vehicles and energy storage systems, continues to outpace new supply. By 2027, the surplus remains modest at less than 1% of total market size, pointing to a market that is close to balance. As a result, prices are forecast to experience upward pressure over 2026 and 2027. Figure 1-9 shows the market balance forecast between 2027 and 2040. Historical and base case forecast lithium product sale prices from the BMI Q1 2026 report are shown in Figure 1-10.




Figure 1-10: Lithium Market Balance Forecast 2027 – 2040




Figure 1-11: Lithium Product Historical and Forecast Pricing (Base Case)

The scoping study utilises BMI Q1 2026 base case price scenario. In the short-term, prices for 6% spodumene concentrate (SC6) are forecast to fluctuate between US$2,181/t (2026) and US$1,260/t (2031), with an average price of US$1,664 per tonne realized up to 2032. The long-term price after 2035 is US$2,430/t.

For personal use only

1.16 Capital Cost and Operating Cost Estimates

The total estimated initial capital cost for AACE Class 4 of the Expansion Project is estimated at $366.1 M. These costs are stated in constant dollars as of Q1 2026. A breakdown of the capital expenditures is shown in Table 1-5. All costs in Canadian dollar (CAD$, CAD or $).

Table 1-5: Capital Costs Summary ($M CAD)

Area	Stage 1 ($M CAD)	Stage 2 ($M CAD)	Stage 3 ($M CAD)	Total Cost ($M CAD)
Mechanical Direct	$14.3	$19.8	$22.9	$56.9
Other Disciplines Direct	$41.9	$38.9	$80.9	$161.8
Indirect Costs	$17.0	$22.2	$35.0	$74.1
Total Before Contingency	**$73.2**	**$80.9**	**$138.7**	**$292.8**
Contingency P_{50} (30%)	**$18.3**	**$20.2**	**$34.7**	**$73.2**
Total	**$91.5**	**$101.1**	**$173.4**	**$366.1**

Sustaining expenditures (SUSEX) for the base case and expansion project was estimated using current operational budgets and factors of direct plant cost. Tailings SUSEX costs were derived using previous estimates and quantities applied over preliminary facility designs. The Expansion case includes additional sustaining costs for additional equipment which are offset by the shorter mine life of this scenario.

The existing crushing circuit will be repurposed into an ore sorting facility following the Stage 2 expansion. This change increases sustaining capital compared to the previous scoping study.

Table 1-6: Sustaining Capital Summary

Area	Base $M CAD	Expansion $M CAD
Tailings	$357.7	$357.7
Stay in Business Capital (SIBC)	$105.4	$120.9
Mining	$22.9	$22.9
Compensation	$25.6	$25.6
Total	**$511.7**	**$527.1**

The operating expenditures (OPEX) was developed in accordance with the requirement of an Updated Scoping level study with a nominal accuracy range of ± 20%. The level of estimation is supported by actual operational information including salaries, consumables, maintenance costs and established contracts and therefore are more precise given this is a brownfield project.

The OPEX results represent annual steady state operations therefore no escalation or inflation is included within the estimate. A summary of the average LOM OPEX costs (all values in CAD$) and comparison between scenarios can be found in Table 1-7. OPEX costs are evaluated commencing as of Fiscal Year 2027.

Table 1-7: Total OPEX Summary

Item	Units	Base	Stage 1	Stage 2	Stage 3
LOM	Yrs	35		20	
Milling rate	Mt/yr	1.4	1.6	2.4	2.4
Mining Cost (ore and waste)	CAD$/t mined	8.6		7.9	
Processing cost	CAD$/t milled	42.6	38.7	37.5	34.2
G&A	CAD$/yr	23.6	24.6	28.3	29.9
Transport cost	CAD$/t dry conc.	142.4	133.8	118.6	118.6
Total OPEX	**CAD$M**	**7,086**		**5,949**	
C1 Cost Concentrate	**CAD$/t dry conc.**	**1,048**		**876**	

For personal use only

1.17 Economic Analysis

The main highlights of the Project's financial analysis are presented in Table 1-8 and Table 1-9. Financial Analysis was performed commencing as of Fiscal Year 2027.

Table 1-8: Main financial assumptions and results summary for the NAL Expansion Project

Parameters	Unit	Base	Expansion
Average Price 6% Li2O	USD$/t	$2,260	$2,137
Life of mine (from FY2027)	yrs	35	20
Total Waste	Mt	336	336
Total Ore	Mt	47	44
Strip Ratio	-	7.1	7.1
Average Annual ROM	Mt/y	1.36	2.41
Average Feed Grade	% Li_2O	1.12%	1.17%
LOM 5.4% Li_2O Produced	Mt	6.77	6.79
LOM Average Annual 5.4% Li_2O	kt/y	196	348
Average Annual 5.4% Li_2O production (post expansion)	kt/y	199	373

Notes:

- Total ore value for the expansion case is lower than the base case due to ore sorting.

Table 1-9: Project Economics

Project Economics	Unit	Base	Expansion
Exchange Rate	CAD/USD	1.35	1.35
Mining Cost (ore and waste)	C$/t mined	8.60	7.91
Process cost	C$/t milled	42.57	34.81
G&A	C$/t milled	17.31	13.05
Transport Cost	C$/t conc	142.37	119.81
Total OPEX	C$M	7,086	5,949
LOM C1 Cost Concentrate	C$/t conc	1,048	876
LOM AISC	C$/t conc	1,126	954
LOM C1 Cost of Concentrate (post expansion)	C$/t conc	1,045	851
LOM AISC (post expansion)	C$/t conc	1,112	918
Total SUSEX	C$M	512	527
Total initial CAPEX	C$M	-	366
Net Cash Flow (pre-tax)	C$M	10,297	10,822
$NPV_{8\%}$ (pre-tax)	C$M	3,193	4,655
$NPV_{8\%}$Expansion Only (pre-tax)	C$M	-	1,462
IRR Expansion (pre-tax)	%	-	58.3%
Payback (pre-tax)	Months	-	29
Net Cash Flow (post-tax)	C$M	7,471	7,307
$NPV_{8\%}$ (post-tax)	C$M	2,274	3,218
$NPV_{8\%}$ Expansion Only (post-tax)	C$M	-	943
IRR Expansion (post-tax)	%	-	49.9%
Payback (post-tax)	Month	-	34

Notes:

- All costs and sales are presented in constant 2026 CAD, with no inflation or escalation factors considered.
- $M = millions of dollars.
- The financial analysis was performed on existing Mineral Reserves as outlined in this report.
- The valuation calculations are unlevered.
- The average metallurgical recovery over the LOM is 71.2% for the expansion and 69.2% for the base case due to improvement in the flowsheet attributable to wet high-intensity magnetic separator (WHIMS) improvements.
- Plant availability is calculated at 90%.
- Tonnes of concentrate are presented as dry metric tonnes.
- An exchange rate of 1.35 CAD/USD was fixed over the LOM for the Project.
- The average 6% Li_2O concentrate (SC6) price is based on a market analysis from Benchmark Mineral Intelligence for Q1 2026 as described in the market section and varies over the LOM from US$1,260/t to US$2,430/t.

For personal use only

- Average LOM SC6 pricing may vary between the cases due to longer mine life at the long term US$2,430 price for the base case (2036 and beyond).
- A discount rate of 8% was used for the base case and expansion scenarios.
- Net Cash Flow and valuation calculations include investment tax credit on CAPEX.
- The numbers have been rounded. Any discrepancy in the totals is due to rounding effects.

The motivation of the revisions in this prefeasibility study from the previously published scoping study, is to reduce risk in the project execution by staging integration of new infrastructure, bring forward production increase and adjust the throughput. Indirectly the price of Spodumene is updated to ensure the pertinence of the study in the reality of the commodity price, the table below compares the previous scoping study expansion scenario to the current prefeasibility study (PFS).

Table 1-10: Expansion Scenarios - Previous Scoping Study and Present PFS

Parameters	Unit	Previous Scoping	Present PFS	Variance %
Exchange Rate	CAD/USD	1.35	1.35	-
LOM	Years	24	20	-16.7%
Average Price 6% Li_2O	USD$/t	1,392	2,137	53.5%
Mining Cost (ore and waste)	C$/t mined	7.60	7.91	4.1%
Process Cost	C$/t milled	35.4	34.8	-1.7%
G&A	C$/t milled	13.4	13.1	-2.2%
Transport Cost	C$/t conc	123.8	119.6	-3.4%
Total OPEX	C$M	6,062	5,949	-1.9%
LOM C1 Cost Concentrate	C$/t conc	877	876	-0.1%
LOM AISC	C$/t conc	952	954	0.2%
LOM C1 Cost of Concentrate (post expansion)	C$/t conc	851	851	0.0%
LOM AISC (post expansion)	C$/t conc	922	918	-0.4%
Total SUSEX	C$M	517	527	1.9%
Total Initial CAPEX	C$M	366	366	-
Net Cash Flow (pre-tax)	C$M	4,626	10,822	133.9%
$NPV_{8\%}$ (pre-tax)	C$M	1,798	4,655	158.9%
$NPV_{8\%}$ Expansion Only (pre-tax)	C$M	628	1,462	132.8%
IRR Expansion (pre-tax)	%	26.4%	58.3%	120.8%
Payback (pre-tax)	Months	36	29	-19.4%
Net Cash Flow (post-tax)	C$M	3,249	7,307	124.9%
$NPV_{8\%}$ (post-tax)	C$M	1,284	3,218	150.6%
$NPV_{8\%}$ Expansion Only (8%) (post-tax)	C$M	479	943	96.9%
IRR Expansion (post-tax)	%	26.4%	49.9%	89.0%
Payback (post-tax)	Month	46	34	-26.1%

To better understand the impact of staging improvements, the staging, operating cost and throughput increase is separated from the changes in price. Table 1-11 shows the contribution of each to the increase in $NPV_{8\%}$the expansion scenario.

Table 1-11: Expansion $NPV_{8\%}$ Contribution - Staging/Throughput and Price Li_2O.

Parameters	Unit	Staging / Throughput*	Price Li_2O	Total NPV increase
$NPV_{8\%}$Expansion Only (pre-tax)	C$M	409	425	834
$NPV_{8\%}$ Expansion Only (post-tax)	C$M	227	237	464

*Predominantly staging/throughput in addition to other assumption changes

From the table above, 51 % of the impact in $NPV_{8\%}$ post tax increase is predominantly a contribution of the staging and throughput increase while 49% is attributable to the increase in Li_2O price from the previous study.

1.18 Project Execution and Risk Assessment

The project schedule will be based on the project development sequence identified by Elevra. Engineering will continue following the Mineral Reserves PFS; Elevra plans to move directly to detailed engineering to advance Stage 1 and Stage 2 to advance the Project to construction. A preliminary project schedule was developed and is shown in Figure 1-12. Further development and detailed execution planning will be undertaken in the next project phases.




Figure 1-12: Indicative Timeline

A risk assessment workshop was performed during the Mineral Reserves PFS to identify the project risks, determine mitigations measures, and develop a risk register. The key residual risks after mitigation measures have been identified are listed below:

- Environmental impact of temporary crushing circuit due to excessive dust and noise emissions Significant increase in ROM pad traffic due to higher throughput requirements
- Damage to existing and new equipment during construction
- Increased chance of fire during construction due to hot work
- Safety and health concern from release of residue accumulated on equipment from operations during demolition
- Schedule risk due to difficulties sourcing equipment (same model as in-place, shipping location)
- Delay to start of detail engineering
- New permitting required for Increased dump/tailings capacity needed for the expansion
- Difficulties obtaining permit/approval to drain nearby lake (Lortie Lake)
- Difficulties obtaining social license in the Project footprint due to previous noise complaints from nearby Lac Legendre community
- Financing gap is longer than expected.
- Capital escalation

These risks will be tracked through the next project phases. The risk register will be updated as the project progresses. As the mitigations identified will be applied in subsequent phases, the likelihood of such risks will diminish or be removed.

For personal use only

For personal use only

There are several opportunities, including the potential for cost reduction opportunities, process recovery enhancements and design improvements.

- Opportunity to reuse the existing color ore sorters if washing can be implemented in both summer and winter effectively.
- Use of superstacks instead of stacksizers for ball mill classification. Reports by vendor indicate that superstacks are a viable alternative to stacksizers.
- Further plant capacity expansion in the future due to larger ball mill included in expansion case. This will permit a potential to increase capacity to 8400 tpd in the future without adding further communition capacity.
- Modularization of equipment packages to reduce costs and reduce reliance on local contractors.
- Use of prefabricated concrete as an opportunity for cost and schedule benefit.
- Federal and Provincial government incentives

These opportunities will be reevaluated in the subsequent phase of the project.

1.19 Interpretations and Conclusions

The Mineral Reserves PFS demonstrates the potential economic viability of an Expansion of the NAL Operation. The Mineral Reserves PFS expansion design follows the staged approach identified by Elevra to reach the following authorised mill throughputs:

- Stage 1: Increase to the limits of the current milling permit at 4,500 t/d average annual rate.
- Stage 2: Expansion to a new milling throughput limit of 6,500 t/d average annual rate.

The NAL Mineral Reserves have been estimated for a total of 47.2Mt of Proven and Probable Mineral Reserves at an average grade of 1.12% Li_2O, which is comprised of 0.2Mt of Proven Mineral Reserves at an average grade of 0.93% Li_2O and 47.0Mt of Probable Mineral Reserves at an average grade of 1.12% Li_2O. The Mineral Reserve estimate is underpinned by a detailed mine plan which includes pit phasing, a dilution model which ensures that potential ROM ore feed respects final product specifications, a detailed LOM schedule, which includes stockpiling, tailings disposal and haulage modelling, that results in a positive cash flow for the Project.

Construction of a dyke at Lortie Lake would allow the extraction of mineral resources located beneath a portion of the waterbody. The dyke would maintain the water level in the retained section of the lake, notably to limit impacts on fish habitat, while ensuring safe conditions for mining operations.

The tailings and water management are based on a strategy of placing conventional spodumene tailings in Tailings Storage Facility 1 (TSF-1) until mid-2029. Additional TSF-2 and TSF-3 are required and have been planned for as part of the Mineral Reserves PFS design. This planning includes site selection, integrated construction with waste rock storage, progressive embankment raises, capital and operating cost estimates. The WMP was updated to manage flows from the expansion scenario. Water management focuses on water diversion, where possible. Water management infrastructure will be phased in as required.

The total estimated initial capital cost for AACE Class 4 of the NAL Expansion Project is estimated at C$ 366,053,000. These costs are stated in constant dollars as of February 2026. Operating costs for the project have been calculated at C$1,048 per tonne of concentrate for base case and C$876 per tonne of concentrate for the expansion scenario.

Analysis of the financial model on the key economic assumptions indicates that the Project is robust in terms of CAPEX and OPEX. The Project is most sensitive to changes in commodity prices, exchange rates, and recoveries.

For personal use only

1.20 Recommendations

The study's results demonstrate that the Project is technically feasible and has the potential to be value accretive under the Mineral Reserves PFS case assumptions. Analysis of the results and findings from each major area investigated in this Mineral Reserves PFS suggests several recommendations for further studies.

Table 1-12: Mineral Reserves PFS Recommendations

Category	Recommendations
Geology and Resources	• Continue resource definition drilling within the conceptual resource pit shell to upgrade remaining Inferred resources to Indicated category and improve geological continuity. • Continue exploration drilling outside of the conceptual resource pit shell to assess the potential for additional Mineral Resources growth. • Complete additional bulk density measurements across pegmatite and waste rock to support the calculation of a density regression formula. Apply the regression formula to support more accurate Mineral Resource characterization. • Complete additional iron analyses for pegmatites and waste rock to support more accurate Mineral Resource characterization. • Continue detailed geological mapping of exposed pegmatite dykes in open pit faces and incorporate results in a future update of the geological model. • Regularly review and update Mineral Resource estimation methodology as new drilling data becomes available. Test sensitivity of estimated ore volumes and grades to different data preparation, domaining and Li_2O grade estimation methods. • Reconcile modelled pegmatite domain geometries, volumes and Li_2O grades against recent mine production data.
Mining and Reserves	• A fleet selection study should be completed with the results of this study used as the basis for the assessment. The fleet selection study must evaluate the potent mining costs savings which can be realised through the use of larger equipment, without negatively impacting loss and dilution of the ore. • Focus on the securing of approvals for all aspects of the life-of-mine plan, in particular the HS-4 waste storage area. Gaining of approvals to store waste in the HS-4 facility will provide operating economic benefits due to the closer proximity of HS-4 to the pit compared to other waste storage areas. • The benefit that backfilling of mined out voids provides should be thoroughly evaluated. Backfilling of mined out voids will provide lower operating costs, reduce the size of the final pit void and reduce the height or size of the out-of-pit dumps. This will only be an option if the surrounding host rock has been drilled sufficiently to ensure that no potentially recoverable ore is sterilised.
Metallurgy and Processing	• Optimisation testwork on the WHIMS to understand the limitations and set targets for plant operations.
Waste and Water Management	• Advance the detailed geotechnical and hydraulic design of TSF-2 and TSF-3, including centreline embankment configuration, seismic and dam safety criteria, and integration of waste rock into embankment construction, to support the next study phase and permitting. This includes the completion of a site-specific seismic hazard assessment. • Complete additional geotechnical and hydrogeological investigations, particularly for the TSF-3 footprint and new waste rock storage areas, to reduce key uncertainties and confirm foundation conditions and long-term performance for the expanded mine waste storage system. • Finalize the design of site water management infrastructure and the associated treatment scheme, ensuring adequate capacity under design storm and freshet events and compliance with applicable provincial and federal water quality requirements. • Refine the closure and monitoring framework for TSF-1, TSF-2, TSF-3 and waste rock storage areas, including beach reclamation, long-term drainage to spillways, and instrumentation and water quality monitoring programs from operations through post-closure, so that commitments are clearly reflected in the updated closure plan and regulatory approvals.

Several items mentioned in the previous chapters will reduce costs and improve the financial position of the deposit. The Mineral Reserves PFS CAPEX is on the level of an AACE Class 4, and a Definitive Feasibility Study phase is planned to increase the accuracy of the estimate to a Class 3 and further derisk the Project.

Elevra is planning on moving directly to Detailed Engineering for Stage 1 following the Mineral Reserves PFS to bring the engineering to a level appropriate to meet the construction timelines outlined in this Mineral Reserves PFS. It is recommended to proceed with the DFS and Detailed Engineering as described in the preliminary Project Schedule.

For personal use only

2 Introduction

2.1 Purpose of the Report

This Mineral Reserves Pre-Feasibility Study (PFS) National Instrument (NI 43-101) Technical Report (Report) was prepared at the request of Elevra Lithium Limited (Elevra). The purpose of this NI 43-101 Report is to provide a Mineral Reserves PFS for the expansion of the North American Lithium (NAL) mine. Elevra serves as the registrant of this NI 43-101 Report. The statement is based on information provided by Elevra and reviewed by various professionals and qualified persons (QP).

The information in this Report related to Mineral Resources is based on, and fairly represents, information compiled by the QPs as of the effective date of the Report. Qualified persons who contributed to the drafting of this Report meet the definition of QPs, consistent with the requirements of the NI 43-101 Code. All QPs are independent of the issuer.

This Report provides information from previous reports as context to support the expansion assessment against a base case scenario. The economic analysis presented in this Report is based on measured and indicated mineral resources only. Inferred mineral resources have not been considered in the analysis as these are considered too geologically speculative to have mining and economic considerations applied to them.

Sedgman Novopro Pty Ltd (Sedgman Novopro) was engaged by Elevra in Q1 2026 to complete multiple project study phases for major plant and infrastructure expansions to increase spodumene concentrate production at the NAL operation. Ahead of the Mineral Reserves PFS, an Updated Scoping Study was performed by Sedgman Novopro with the collaboration of Optimal Mining Solutions Pty Ltd (Optimal Mining) leading to the publication of a press release by Elevra. The Updated Scoping Study identified process optimizations to deliver the NAL expansion project according to the staging approach detailed by Elevra and provided AACE Class 5 cost estimates.

The Mineral Reserves PFS further develops the process design based on additional surveys conducted by NAL and improves on the accuracy of the cost estimates to AACE Class 4 from major equipment quotes obtained during a request for quotation (RFQ) cycle. This Mineral Reserves PFS Report was prepared as a collaborative effort between Sedgman Novopro, Optimal Mining Pty Ltd (Optimal Mining), BBA, Measured Group Pty Ltd (Measured Group), and Englobe Corp. (Englobe).

2.2 Context

The North American Lithium (“NAL”) mine site was established in 2012 and has operated during a number of campaigns based on fluctuating commodity pricing. The NAL property is wholly owned and operated by Sayona Québec Inc. (“Sayona Québec”), with Elevra owning 100% of Sayona Québec following the merger between Sayona Mining Limited (“Sayona”) and Piedmont Lithium Inc. The NAL property is considered material to Elevra.

The plant was most recently restarted in 2022 and following a period of ramp up and process optimisation, Elevra now proposes to increase production through a three-stage approach as follows:

- Stage 1: An initial 15-20% increase in annual spodumene concentrate production above current production levels commencing in mid-CY27 with an incremental reduction in unit operating costs. This increase is within the current limits of the milling permit set at 4,500 tpd.
- Stage 2: A subsequent expansion of downstream milling, flotation and filtration capacity to 6,500 tpd. The incremental feed material will be processed using a temporary mobile crushing circuit operating in conjunction with the existing crushing circuit. The further expanded production is expected to commence early CY28, with an additional incremental reduction in unit operating costs; and

For personal use only

- Stage 3: The replacement of the temporary mobile crushing circuit and the existing crushing circuit with a new crushing circuit capable of meeting feed requirements for a LOM average production of 373ktpa post-expansion. This final step will include additional ore sorting capacity and is expected to be completed in early CY29 delivering crushing cost efficiencies which are required to meet the anticipated LOM cost reduction.

2.3 Study Contributors and Report Responsibility

The following authors have contributed to the study:

- Sedgman Novopro Pty Ltd
- Optimal Mining Pty Ltd
- Measured Group Pty Ltd
- BBA
- Englobe Corp.

Table 2-1 presents the owners for each chapter of this Report. The authors of this Report are in good standing with the appropriate professional institutions. The authors have supervised the preparation of this Report and take responsibility for the contents of the Report as set out in Table 2-1. Each author has also contributed relevant figures, tables, and written information for Chapters 1 (Summary), 24 (Other Relevant Data and Information), 25 (Interpretation and Conclusions), 26 (Recommendations), and 27 (References).

Table 2-1: Chapters Responsibility

No.	Chapter Description	Owners
1	Summary	Chapter Owners
2	Introduction	Sedgman Novopro
3	Reliance on Other Experts	Sedgman Novopro
4	Property Description and Location	Sedgman Novopro / Elevra
5	Accessibility, Climate, Local Resources, Infrastructure and Physiography	Sedgman Novopro / Elevra
6	History	Sedgman Novopro / Elevra
7	Geology and Mineralization	Optimal Mining
8	Deposit Types	Optimal Mining
9	Exploration	Optimal Mining
10	Drilling	Optimal Mining
11	Sample Preparation, Analyses and Security	Optimal Mining
12	Data Verification	Optimal Mining
13	Mineral Processing and Metallurgical Testing	Sedgman Novopro
14	Mineral Resource Estimates	Optimal Mining
15	Mineral Reserve Estimates	Optimal Mining
16	Mining Methods	Optimal Mining
17	Recovery Methods	Sedgman Novopro
18	Project Infrastructure	Sedgman Novopro / Elevra / BBA / Englobe
19	Market Studies and Contracts	Optimal Mining / Elevra
20	Environmental Studies, Permitting and Social or Community Impact	Elevra
21	Capital and Operating Costs	Sedgman Novopro / Elevra
22	Economic Analysis	Sedgman Novopro / Elevra
23	Adjacent Properties	Elevra
24	Other Relevant Data and Information	Sedgman Novopro / Elevra
25	Interpretation and Conclusions	Chapter Owners
26	Recommendations	Chapter Owners
27	References	Chapter Owners

For personal use only

2.4 Site Visits

2.4.1 Sedgman Novopro Site Visit

A site visit was undertaken by Sedgman Novopro experts Benjamin Alliss and Minh Duc Vo from the 9th to the 11th of June 2026, during which time Sedgman Novopro met with key metallurgical and operations management personnel to review the process design developed for the Updated Scoping Study. The work undertaken during the site visit is summarised below:

- Attend the site over a three-day period.
- Review of the Process Flow Diagrams (PFDs) with key site personnel.
- Assess physical equipment constraints to further layout and 3D model development.

2.4.2 BBA Site Visit

A site visit was undertaken by BBA Tailings and Water Principal Engineers Gerladine Cosset and Eduardo Rodriguez on the 4th of May 2026, during which time BBA staff met with key environmental and operations management personnel after a site visit of existing TSF-1 and future TSF's location. The work undertaken during the investigation is summarised below:

- Attend the site over a one-day period.
- Complete a site visit of TSF-1 and associated water infrastructures and future location of TSF-2 and TSF-3.
- Hold an afternoon workshop with key site personnel to understand current operational challenges and review proposed design.

2.4.3 Previous Site Visits

2.4.3.1 Sedgman Novopro Site Visit

A site visit was undertaken by Sedgman Novopro experts Benjamin Alliss, Robert Simmons and Abbas Mahmoodi from the 29th to the 30th of January 2026, during which time Sedgman Novopro staff met with key metallurgical and operations management personnel before assessing the plant and equipment in operation. The work undertaken during the investigation is summarised below:

- Attend the site over a two-day period.
- Hold workshops with key site personnel to understand current concerns and operational shortcomings.
- Review operating data and reports.
- Assess plant configuration and operation to identify any physical processing constraints and opportunities for improvements, both short term and long term.
- Review the current proposed optimization/expansion projects to ensure they are suitably addressing the issues at hand.

2.4.3.2 Optimal Mining Site Visit

Tony O'Connell of Optimal Mining, QP for several of the chapters, visited the Project and its existing installations between September 10th and 12th 2024 inclusive. The site visit included a field tour of the current operating open pit's phase 1 operations (Figure 2-1), phase 2 operations (Figure 2-2) and phase 3 operations (Figure 2-3). Extensive discussions were held with management, geologists and engineers of Sayona Quebec during the site visit.



Figure 2-1: View of the Phase 1 Open Pit Operations



Figure 2-2: View of the Phase 2 Open Pit Operations



Figure 2-3: View of the Phase 3 Open Pit Operations

For personal use only

2.4.3.3 *Other Site Visits*

A site visit was also completed on May 27th, 2025, by other consultants engaged in the preparation of the Mineral Resource estimate. The site visit included a field tour of the main geological features visible in the current open pit, a tour of the core storage facility, visual inspections of drill cores, and discussions with on-site geologists and engineers of Elevra Québec.

Selected drillhole collars in the field were also validated. The site visit also included a review of the sampling and assay procedures, QA/QC program, downhole survey methodologies, and the descriptions of lithologies, alteration and structures. The outcomes of this site visit are discussed in greater detail in Section 12.2.2 – Drilling and Sampling Procedure Validation.

2.5 Sources of Information

The following documentation were used to support the preparation of this Report:

- Reference documents from C101 – Scoping Study (Wave International, 2025)
- Reference documents from C102 – DFS Study (BBA, 2023)

Additional information was sought from Elevra and NAL personnel as required. Sections from reports authored by other consultants may have been directly quoted or summarized in this report and are so indicated where appropriate.

The report has been completed using the aforementioned sources of information as well as information contained in, but not limited to, the following reports, documents, and discussions:

- Technical discussions with NAL and Elevra personnel.
- QP site visits.
- Technical and financial information provided by NAL and Elevra personnel.
- Internal unpublished reports received from NAL.
- Additional information from public domain sources.

2.6 Units of Measure and Glossary of Terms

Unless otherwise specified or noted, this Report uses the following assumptions and units:

- All measurements are in metric units.
- Currency is in Canadian dollars (CAD, C$ or $).
- Metal prices are expressed in Canadian dollars, selling prices are in USD.

A list of the abbreviations and units of measurement used in this Report are provided Table 2-2. This Report includes technical information that required subsequent calculations to derive subtotals, totals, and weighted averages. Such calculations inherently involve a degree of rounding and consequently introduce a margin of error. Where these occur, the authors consider them immaterial.

For personal use only

For personal use only

Table 2-2: List of Abbreviations and Units of Measurement

Abbreviation	Description
3D	Three dimensional
AACE	Association for the Advancement of Cost Engineering
ActLabs	Techni-Lab SGB
Ag	Silver
AGAT	AGAT Laboratories Ltd.
Ai	Abrasion index
AISC	All-in sustaining cost
ALS	ALS Laboratory Group
AMC	AMC Mining Consultants (Canada) Ltd.
ARD	Acid Rock Drainage
ASX	Australian Securities Exchange Ltd.
BAPE	Bureau d'audiences publique en Environnement (Public Hearings Office on the Environment)
BBA	BBA Engineering Inc.
BFA	Bench face angles
Bi	Bismuth
BM	Block model
BMI	Benchmark Minerals Intelligence
BO3	Borate
BWi	Ball mill work index
CAD	Canadian Dollar
CAGR	Compound annual growth rate
C-ALS	Cavity autoscanning laser system
Cambior	Cambior Inc.
Capex	Capital Cost Estimate
CDA	Canadian Dam Association
CDPNQ	Centre de Données sur le Patrimoine Naturel du Québec
CEAA	Canadian Environmental Assessment Agency
CIM	Canadian Institute of Mining, Metallurgy and Petroleum
CLC	Canada Lithium Corp.
CN-	Cyanide
CN	Canadian National
COG	Cut-off grade
CRM	Certified reference materials
Cs	Cesium
CV	Coefficient of variation
CWI	Crushing work index
DCF	Discounted cash flow
DDH	Diamond drillhole
DFO	Department of Fisheries and Oceans of Canada
DFS	Definitive Feasibility Study
DIL	Diluvio deposit
DMS	Dense media separation
DTM	Digital terrain model
EBITDA	Earnings Before Interest, Taxes, Depreciation, and Amortization
EDF	Environmental Design Flood
EFE	Exceptional forest ecosystem
EGM	Engineering geology model
Elevra	Elevra Lithium Limited
EOY	End of year
EPCM	Engineering, procurement and construction management
EQA	Environment Quality Act
ESIA	Environmental and Social Impact Assessment
ESR	Excellence in Social Responsibility

For personal use only

Abbreviation	Description
ESS	Energy storage systems
EVs	Electric vehicles
Fe	Iron
FEL	Front-end loader
FOB	Freight-on-board
FOS	Factor of safety
FS	Feasibility Study
FY	Fiscal year
G&A	General and Administration
Geo Labs	Geoscience Laboratories
GET	Ground engaging tools
GHG	Greenhouse gas
Golder	Golder Associates
GSC	Geological Survey of Canada
Hbl	Hornblende
HDPE	High-density polyethylene
H_2O	Water
HLS	Heavy-liquid separation
HS	Waste Rock Stockpile
IBA	Impact Benefit Agreement
ICP-AES	Inductively coupled plasma – atomic emission spectroscopy
ICP-OES	Inductively coupled plasma – optical emission spectrometry
ID	Inverse distance
ID2	Inverse distance squared
ID3	Inverse distance cubed
InnovExplo	InnovExplo Inc.
IRA	Inter-ramp angles
IRR	Internal rate of return
IW	Independent witness
JBNQA	James Bay and Northern Quebec Agreement
JV	Joint venture
KE	Kriging efficiency
KNA	Kriging neighbourhood analysis
KPI	Key production indicator
kt LCE	thousand tonnes lithium carbonate equivalent
LAN	Lithium Amérique du Nord
LCE	Lithium carbonate equivalent
LCT	Li-Cs-Ta (Lithium, cesium, tantalum)
LG	Low grade
Li	Lithium
LIMS	Low-intensity magnetic separator
Li_2O	Lithium oxide
LiOH.H2O	Lithium hydroxide monohydrate
LLDPE	Linear low-density polyethylene
LOM	Life of mine
LSB	Loi sur la sécurité des barrages (The Dam Safety Law applied in Québec)
LV	Low voltage
m.a.s.l.	Metres above sea level
MDMER	Metal and Diamond Mining Effluent Regulations
MELCC	Ministère de l'Environnement, et de la Lutte contre les changements climatiques, (now MELCCFP)
MELCCFP	Ministère de l'Environnement, de la Lutte contre les changements climatiques, de la Faune et des Parcs (formerly MELCC)
MFFP	Ministry of Forest, Fauna and Parks
MIBC	Methyl isobutyl carbinol

For personal use only

Abbreviation	Description
ML	Metals leaching
Mo	Molybdenum
MRC	Municipalité Régionale de Comté
MRE	Mineral resource estimate
MRNF	Ministère des Resources naturelles et des Forêts (formerly MERN)
MSO	Mine stope optimisation
MSSO	MineSight Schedule Optimizer
MTOs	Material take-offs
MV	Medium voltage
Na_2CO_3	Soda ash
NAD	North American Datum
NAG	Non-acid Generating
NAL	North American Lithium
NaOH	Sodium hydroxide
Nb-Y-F (or NYF)	Niobium-yttrium-fluorine
NCF	Net cash flow
NI 43-101	National Instrument 43-101
NIR	Near infrared
NN	Nearest neighbour
$NPV_{8\%}$	Net present value with 8% discount rate applied
NSR	Net smelter return
OBP-2	Overburden pile 2
OK	Ordinary kriging
Opex	Operating Cost Estimate
PCBs	Polychlorinated biphenyls
PEA	Preliminary economic assessment
PFS	Pre-feasibility study
PGA	Potential gravity acceleration
PMF	Probable maximum flood
PO4	Phosphate ion
POV	Pre-operational verification
PwC	PricewaterhouseCoopers
Q1	First quarter
Q2	Second quarter
Q3	Third quarter
Q4	Fourth quarter
QA/QC	Quality Assurance / Quality Control
QLC	Quebec Lithium Corporation
QP	Qualified Person
Rb	Rubidium
REE	Rare earth elements
RNC	Royal Nickel Corporation
RNC Media	Radio Nord Communications Inc.
ROM	Run of mine
ROMPad	Run of Mine pad
RPA	Roscoe, Postle and Associates
RPEEE	Reasonable Prospects for Eventual Economic Extraction,
RQD	Rock quality designation
RSB	Règlement sur la sécurité des barrages (Dam Safety Regulation, applied in Quebec)
RTK	Real time kinematic
SAD	Abitibi RCM's territory development and activities plan
Sayona	Sayona Québec / Sayona Mining Limited
SD	Standard deviation
SEC	Study of the environmental character

Abbreviation	Description
SG	Specific gravity
SGS	SGS Lakefield
SN	Sedgman Novopro
Sn	Tin
Spd	Spodumene
SNC	Surveyor, Nenniger et Chênevert Inc.
std	Standard
ST-H	High-grade standard
ST-L	Low-grade standard
tpa	Tonnes per Annum
tpd	Tonnes per Day
TSF	Tailings Storage Facility
TSF-1	Tailings Storage Facility 1
TSF-2	Tailings Storage Facility 2
TSF-3	Tailings Storage Facility 3
TSS	Total suspended solids
UFCF	Unlevered free cash flow
U/G	Underground
URSTM	Unité de Recherche et de Service en Technologie Minérales
USD	United States dollar
WBS	Work breakdown structure
WHIMS	Wet high-intensity magnetic separation
WMP	Water Management Plan
XRD	X-ray diffraction

For personal use only

3 Reliance on Other Experts

3.1 General

The authors of this Report have relied on information provided by experts who were not authors of the Report. The authors of the various chapters of the Report believe that it is reasonable to rely upon these experts, based on the assertion that the experts have the necessary education, professional designation, and related experience on matters relevant to the technical report.

The authors have assumed, and relied on the fact, that all the information and existing technical documents listed in Chapter 27– References of this Report are accurate and complete in all material aspects. While the authors reviewed all the available information presented, we cannot guarantee its accuracy and completeness. The authors reserve the right, but will not be obligated, to revise the Report and conclusions, if additional information becomes known after publication of this Report.

The statements and opinions expressed in this document are given in good faith and in the belief that such statements and opinions are neither false, nor misleading at the date of this Report. A draft copy of the Report has been reviewed for factual errors by Elevra. Any changes made because of these reviews did not involve any alteration to the conclusions made.

3.2 Mineral Claims and Surface Rights

The authors have not independently reviewed ownership of the Project area and any underlying property agreements, mineral claims, surface rights or royalties. The authors have fully relied upon information derived from Elevra. Refer to 4 – Property Description and Location for further information on property ownership and agreements.

3.3 Environmental and Social

The authors have relied upon information provided from Elevra regarding environmental, permitting and social. The authors have reviewed the information and consider it adequate and of a reasonable basis for the Mineral Reserves PFS.

3.4 Taxation

The Project is subject to three levels of taxation: federal corporate income tax, provincial corporate income tax, and provincial mining taxes. NAL compiled the taxation calculations for the Project with assistance from third-party taxation experts; this information has been relied upon by the authors.

For personal use only

For personal use only

4 Property Description and Location

This chapter describes the NAL Property location. This chapter contains information that was previously published by Sayona in a NI 43-101 Technical Report titled “Definitive Feasibility Study Report for the North American Lithium Project”, dated April 14th, 2023 (BBA, 2023).

4.1 Property Location, Country, Regional and Government Setting

The Property is situated in the Province of Québec, Canada (Figure 4-1).



Figure 4-1: Property Overview Map

Canada is a North American country with its centre of government in Ottawa located in the Province of Ontario. Canada is a constitutional monarchy which forms part of the British Commonwealth, and it is ruled by a parliamentary democratic government. The Crown assumes the roles of the executive, as the Crown-in-Council; the legislative, as the Crown-in-Parliament; and the judicial, as the Crown-on-the-Bench. The country is politically stable, comprised of ten provinces and three territories, of which Québec is one.

The site is located in the western Quebec region of Abitibi-Témiscamingue (Figure 4-2). The site is approximately 550 km north of Montréal, 700 km north-west of Québec City, and is serviced by road, rail, and air.



Figure 4-2: NAL Regional Property Location

At the local level, the Property is situated in La Corne Township approximately 38 km southeast of Amos, 15 km west of Barraute and 60 km north of Val-d'Or. The Property is centred near coordinates 292,500 m E and 5,365,600 m N (48°24'24"N, 77°49'50W,), Zone 18N as located on the NTS map sheet 32C05 (Figure 4-3).

As of March 30, 2026, the North American Lithium Property consists of a contiguous group of 59 mineral titles including 1 mining lease covering an area of 116.4 ha and 58 claims, covering an area 2,287.9 ha.

For personal use only

For personal use only




Figure 4-3: NAL Property Location

For personal use only

4.2 Mineral Tenure, Agreement and Royalties

4.2.1 Surface Rights

In the Province of Québec, the Mining Act governs the management of mineral resources and the granting of exploration rights for mineral substances during the exploration phase. It also deals with the granting of rights pertaining to the use of these substances during the mining phase. Finally, the act establishes the rights and obligations of the holders of mining rights to ensure maximum development of Québec's mineral resources.

On August 26, 2021, Sayona Québec, a joint venture of subsidiary company of Sayona Mining Limited (75%) and Piedmont Lithium Inc. (25%) Ltd., acquired NAL. At the time, all claims (19) were registered in the name of NAL for a total area of 583.51 ha. The mining lease (BM1005) is also under NAL's name and covers an area of 116.4 Ha. The mining lease was granted to Québec Lithium on May 29, 2012, based on a PFS pit filed at the time in support of the application to be granted such a lease. The mining lease has an initial term of 20 years, expiring on May 28, 2032.

On August 30, 2025, Sayona Mining Limited and Piedmont Lithium Inc. merged to form the new entity owning Sayona Québec Inc. under the name of Elevra Lithium Limited. Since the acquisition of the Project, NAL acquired 20 claims spanning roughly 750 ha from Resources Jourdan Inc. and two claims with a total area of 42.3 ha from Lise Daigle. NAL also acquired 17 mineral claims by designation in February 2026, for a total of 911.7 ha.

Claim status was verified using GESTIM, the Québec government's online claim management system. As of March 30, 2026, the NAL Property consists of a contiguous group of 59 mineral titles including 58 claims and 1 mining lease (Figure 4-4, Table 4-1) covering a total area of 2,404.3 ha. The author has not verified the legal titles to the Property or any underlying agreement(s) that may exist concerning the licenses or other agreement(s) between third parties.




Figure 4-4: NAL Mineral Titles

For personal use only

Table 4-1: Mining Titles List and Details

Claim Name	Status	Issue Date	Expiry Date	Area (Ha)	Owner
BM 1005	Active	May 29, 2012	May 28, 2026	116.39	Lithium Amérique du Nord (100%)
CDC 2145325	Active	March 17, 2008	November 24, 2026	31.25	Lithium Amérique du Nord (100%)
CDC 2145326	Active	March 17, 2008	November 24, 2026	32.12	Lithium Amérique du Nord (100%)
CDC 2145327	Active	March 17, 2008	November 24, 2026	42.85	Lithium Amérique du Nord (100%)
CDC 2145328	Active	March 17, 2008	November 24, 2026	41.64	Lithium Amérique du Nord (100%)
CDC 2145329	Active	March 17, 2008	November 24, 2026	16.76	Lithium Amérique du Nord (100%)
CDC 2145330	Active	March 17, 2008	November 24, 2026	23.81	Lithium Amérique du Nord (100%)
CDC 2145331	Active	March 17, 2008	November 24, 2026	15.29	Lithium Amérique du Nord (100%)
CDC 2145332	Active	March 17, 2008	November 24, 2026	22.75	Lithium Amérique du Nord (100%)
CDC 2145333	Active	March 17, 2008	November 24, 2026	46.94	Lithium Amérique du Nord (100%)
CDC 2145334	Active	March 17, 2008	November 24, 2026	17.59	Lithium Amérique du Nord (100%)
CDC 2145335	Active	March 17, 2008	November 24, 2026	1.53	Lithium Amérique du Nord (100%)
CDC 2145336	Active	March 17, 2008	November 24, 2026	35.92	Lithium Amérique du Nord (100%)
CDC 2154760	Active	May 26, 2008	May 25, 2027	41.71	Lithium Amérique du Nord (100%)
CDC 2154761	Active	May 26, 2008	May 25, 2027	41.64	Lithium Amérique du Nord (100%)
CDC 2154987	Active	May 26, 2008	February 2, 2027	42.15	Lithium Amérique du Nord (100%)
CDC 2154988	Active	May 26, 2008	February 2, 2027	42.15	Lithium Amérique du Nord (100%)
CDC 2154989	Active	May 26, 2008	February 2, 2027	42.68	Lithium Amérique du Nord (100%)
CDC 2154990	Active	May 26, 2008	February 2, 2027	42.65	Lithium Amérique du Nord (100%)
CDC 2154991	Active	May 26, 2008	February 2, 2027	42.67	Lithium Amérique du Nord (100%)
CDC 2154992	Active	May 26, 2008	February 2, 2027	21.45	Lithium Amérique du Nord (100%)
CDC 2154993	Active	May 26, 2008	February 2, 2027	21.31	Lithium Amérique du Nord (100%)
CDC 2167933	Active	July 28, 2008	July 27, 2027	43.07	Lithium Amérique du Nord (100%)
CDC 2167934	Active	July 28, 2008	July 27, 2027	42.63	Lithium Amérique du Nord (100%)
CDC 2167935	Active	July 28, 2008	July 27, 2027	42.67	Lithium Amérique du Nord (100%)
CDC 2167936	Active	July 28, 2008	July 27, 2027	42.71	Lithium Amérique du Nord (100%)
CDC 2167937	Active	July 28, 2008	July 27, 2027	42.71	Lithium Amérique du Nord (100%)
CDC 2167938	Active	July 28, 2008	July 27, 2027	42.71	Lithium Amérique du Nord (100%)
CDC 2444462	Active	May 11, 2016	May 10, 2027	21.66	Lithium Amérique du Nord (100%)
CDC 2444463	Active	May 11, 2016	May 10, 2027	13.53	Lithium Amérique du Nord (100%)
CDC 2490652	Active	April 25, 2017	April 24, 2026	4.21	Lithium Amérique du Nord (100%)
CDC 2490653	Active	April 25, 2017	April 24, 2026	10.67	Lithium Amérique du Nord (100%)
CDC 2490654	Active	April 25, 2017	April 24, 2026	37.72	Lithium Amérique du Nord (100%)
CDC 2490655	Active	April 25, 2017	April 24, 2026	26.50	Lithium Amérique du Nord (100%)
CDC 2490656	Active	April 25, 2017	April 24, 2026	44.59	Lithium Amérique du Nord (100%)
CDC 2520959	Active	July 19, 2018	July 18, 2027	42.99	Lithium Amérique du Nord (100%)
CDC 2521244	Active	July 20, 2018	July 19, 2027	57.20	Lithium Amérique du Nord (100%)
CDC 2521245	Active	July 20, 2018	July 19, 2027	57.20	Lithium Amérique du Nord (100%)
CDC 2521246	Active	July 20, 2018	July 19, 2027	57.20	Lithium Amérique du Nord (100%)
CDC 2521247	Active	July 20, 2018	July 19, 2027	37.03	Lithium Amérique du Nord (100%)
CDC 2569722	Active	June 23, 2020	June 22, 2027	20.53	Lithium Amérique du Nord (100%)
CDC 2569723	Active	June 23, 2020	June 22, 2027	21.78	Lithium Amérique du Nord (100%)
CDC 2870149	Active	February 17, 2026	February 16, 2029	57.25	Lithium Amérique du Nord (100%)
CDC 2870150	Active	February 17, 2026	February 16, 2029	57.24	Lithium Amérique du Nord (100%)
CDC 2870151	Active	February 17, 2026	February 16, 2029	57.24	Lithium Amérique du Nord (100%)
CDC 2870152	Active	February 17, 2026	February 16, 2029	57.24	Lithium Amérique du Nord (100%)
CDC 2870153	Active	February 17, 2026	February 16, 2029	57.24	Lithium Amérique du Nord (100%)
CDC 2870154	Active	February 17, 2026	February 16, 2029	45.23	Lithium Amérique du Nord (100%)
CDC 2870155	Active	February 17, 2026	February 16, 2029	7.85	Lithium Amérique du Nord (100%)
CDC 2870688	Active	February 24, 2026	February 23, 2029	57.25	Lithium Amérique du Nord (100%)
CDC 2870689	Active	February 24, 2026	February 23, 2029	57.25	Lithium Amérique du Nord (100%)
CDC 2870690	Active	February 24, 2026	February 23, 2029	57.25	Lithium Amérique du Nord (100%)
CDC 2870691	Active	February 24, 2026	February 23, 2029	57.25	Lithium Amérique du Nord (100%)
CDC 2870692	Active	February 24, 2026	February 23, 2029	57.25	Lithium Amérique du Nord (100%)
CDC 2870693	Active	February 24, 2026	February 23, 2029	57.25	Lithium Amérique du Nord (100%)

Claim Name	Status	Issue Date	Expiry Date	Area (Ha)	Owner
CDC 2870694	Active	February 24, 2026	February 23, 2029	57.24	Lithium Amérique du Nord (100%)
CDC 2870695	Active	February 24, 2026	February 23, 2029	57.24	Lithium Amérique du Nord (100%)
CDC 2870696	Active	February 24, 2026	February 23, 2029	57.24	Lithium Amérique du Nord (100%)
CDC 2870697	Active	February 24, 2026	February 23, 2029	57.23	Lithium Amérique du Nord (100%)
Total				**2404.30**	

4.2.2 Mineral Rights and Permitting

Permits are required for any exploration program that involves tree cutting (to create access roads or drill pads or, in preparation for mechanical outcrop stripping, for example). Permits are issued by the Ministère des Resources Naturelles et des Forêts (MRNF). Permitting timelines are typically three to four weeks. Additional permitting requirements are needed when drilling on the historical tailings sites. Permits are also necessary for the exploitation of the mine.

NAL operations have obtained all necessary permits from government agencies to allow for surface drilling on the NAL Property. All necessary regulatory permits required for the operation of the NAL mine since its construction are listed below.

Major existing permits and authorizations include:

- Ore treatment plant (concentrator) and refinery.
- Construction of tailings accumulation areas.
- Overburden stockpile #1 and 2.
- Operation of a spodumene surface mine in La Corne.
- Operation of the concentrator and the refinery.
- Wastewater treatment system.
- Open pit mining.

A complete list of permits and authorizations for the Project can be found in Chapter 20 – Environmental Studies, Permitting and Social or Community Impact.

4.2.3 Agreements and Royalties

There are no royalties applicable to any mineral substances extracted from the lands subject to the NAL mining titles. The author did not verify the legality or terms of any underlying agreement(s) that may exist concerning the Project ownership, permits, offtake agreements, license agreements, royalties, or other agreement(s) between NAL / Sayona Québec and any third parties.

4.3 Environmental Liabilities and Other Permitting Requirements

The author is not aware of any environmental liabilities, other than those mentioned here, to which the Property is subject, other than the normal licensing and permitting requirements that must be made prior to undertaking certain operations and environmental restrictions as set forth in the Provincial Mining Act and Regulations.

There were no outstanding liabilities on the old mining site prior to the resumption of operations in 2013 as a previous owner of the claims, Cambior Inc., had completed the full rehabilitation to the satisfaction of the MRNF and in conformity with provincial safety standards, as well as received confirmation from the authorities for the completion of the work. Such rehabilitation of the mine site

For personal use only

For personal use only

included the complete removal of all underground and surface plant and equipment, the mine's head frame, the railway spur connecting to the Canadian National (CN) railway line, and all office buildings and other structures, which was completed from 1975 through 2001. The crown pillar was fenced off and all openings sealed.

Old tailings were stored within two dams located to the north of the mine area in a west-east trending valley between Lortie Lake and Lac Roy. There is an estimated 700,000-750,000 t of material stored there, mostly quartz and feldspar sand (Karpoff, Évaluation Technique de la Propriété Minière Québec Lithium, 1993). Rehabilitation included covering the tailings with soil and vegetation.

In 2009, a Study of the Environmental Character (SEC) of the Property was initiated by Genivar Inc. of Amos, Québec, which was then pursued and completed by Project personnel prior to resuming production mid-2013. The objective of the SEC was to outline all environmental concerns and constraints for the proposed development of an open-pit mining operation.

An environmental baseline study for the Project, begun in October 2009, was incorporated into the final SEC report. This was the first step towards obtaining the permits and authorizations from regulatory authorities to permit the construction of new infrastructure and pre-stripping of the deposit in 2012. New office buildings, sheds, warehouse, and a processing plant, all located about 1 km west of the mining pit area, were permitted and constructed prior to launching open-pit operations in mid-2013.

TSF-1 has been raised to 415 m as part of the completed Phase 1C works, providing a total residue storage capacity of 5.6 Mm^3. Detailed engineering for Phase 1D is largely complete and includes a +3 m raise, increasing total capacity to 7.2 Mm^3. TSF-1 is ultimately planned for a total capacity of 8.8 mm^3 reached in 2028. This notwithstanding a second TSF will be required in the short- to medium-term for the storage of LOM concentrator tailings followed by a third TSF to carry to the remaining LOM.

NAL also has two planned waste rock storage areas, currently located 1.5 km and 2.5 km from the pit. Waste rock storage 3 is authorized, and waste rock storage 2, including its final west-side expansion phase, has also received authorization. NAL therefore holds all required permits for waste rock deposition until the end of Phase 5. These two waste rock piles have been designed to reach the final required capacity as previously published by Sayona in a NI 43-101 Technical Report titled "Definitive Feasibility Study Report for the North American Lithium Project", dated April 14th, 2023. (BBA, 2023)

The only current environmental liabilities are known contaminated soils. The other infrastructures are covered by the restoration plan and the financial guarantee deposited with the MRNF.

4.4 Mineral and Surface Purchase Agreements

In addition to the mining rights described above, NAL holds five surface leases on lands of the domain of the State (referred to below as Public Land Leases), which it rents or plans to rent from the MRNF for the utilization and rights shown in Table 4-2. NAL has received an extension of the leases for the waste stockpile 2 and the waste stockpile 3 from MRNF.

NAL has federal authorization for TSF-2, with an authorization request planned to be made at the provincial level in mid-2026 for TSF-2.

Table 4-2: NAL Public Land Leases

MRNF Lease #	Land Lease Description	Area (Ha)
82373700	Public Land Lease – Surface Infrastructures	43.2
824391/41818908	Public Land Lease – Waste Stockpile 3	146,3
82439000	Public Land Lease – Overburden stockpile	30.8

MRNF Lease #	Land Lease Description	Area (Ha)
82439400	Public Land Lease – Waste Stockpile 2	90.6
82439200	Public Land Lease – TSF-1	117.5
82438600	Public Land Lease – Lortie Lake North well (OW-11-03)	1.0
Total		394.8

4.5 Other Significant Factors and Risks

To the author's knowledge, there are no significant factors, risks or legal issues that may affect access, title, the right, or ability to perform work on the Property.

For personal use only

For personal use only

5 Accessibility, Climate, Local Resources, Infrastructure and Physiography

This chapter describes the NAL Property accessibility, climate, local resources, infrastructure and physiography. This chapter contains information that was previously published by Sayona in a NI 43-101 Technical Report titled “Definitive Feasibility Study Report for the North American Lithium Project”, dated April 14th, 2023. (BBA, 2023)

5.1 Accessibility

The Property is located approximately 60 km north of Val-d’Or, Québec, and 38 km southeast of Amos, Québec, and is accessible by provincial Highway 111, connecting Val-d’Or and Amos, or alternatively by provincial Highway 397, connecting Val-d’Or and Barraute (Figure 4-3).

An all-weather secondary road, known as Route du Lithium, connecting the site to the Val-d’Or – Amos highway, which was used to traverse the Property and factually caused constraint to the pit operations, has now been relocated to avoid the mining area. The site is also accessible from Mont-Vidéo, through an all-weather road that connects further east to the Val-d’Or – Barraute highway.

Val-d’Or and Rouyn-Noranda are serviced daily by regional air carriers, while small craft landing areas are also located in these towns and nearby Amos. The closest all-weather landing strip and helipad is located at Amos now that the small aircraft landing strip, once located at Mont-Vidéo to the east of the Property, was converted into the new all-weather gravel road circumventing the mine site.

5.2 Topography, Elevation, Vegetation and Climate

5.2.1 Physiography

The Property contains small hills and is located at a mean elevation of 400 m above sea level, but the topography is generally flat with swamps, sand plains and an esker along its edge.

Granitic intrusions, which are part of the La Corne pluton, underlie nearly all of the hilly area. The volcanic rocks adjacent to this pluton have been altered to hornblende (Hbl) schists, which are very resistant to weathering and now form the highest hills. In the early 1950s, the hills were covered with dense forest growth consisting mainly of hardwoods. Most of the outcrops of spodumene-bearing (Spd) pegmatite occur on the top of a ridge that rises to an elevation of approximately 150 ft (~45 m) above Lortie Lake. This ridge can be traced for approximately 2,000 ft (~610 m) in an east-west direction.

The region's landscape typically features mixed forest to the south, while boreal forest covers the northern section, notably along the Amos – La Sarre corridor. Wholesale timber logging activities took place locally during the ‘50s and ‘60s, until the ‘80s, when reforestation was undertaken. As the mine is a recently reclaimed site and also because all timber had been cut earlier, vegetation is limited to spruce with jack pine and alders in regrowth near the site.

Figure 5-1 shows the main existing and planned site infrastructure for the Project. The highlighted features include the fully developed open pit, the existing and expanded tailings management facilities, plant facilities, the waste storage areas, and overburden piles, as well as various other pads associated with the life of mine (LOM) pit plan.

For personal use only




Figure 5-1: General Arrangement of Existing and Planned Infrastructure at the Mine Site

5.2.2 Vegetation

The regional study zone is located within the western balsam fir-yellow birch bioclimatic domain. The forest landscape is dominated by stands of pine and white spruce, intermingling with white birch trees. The regional study zone includes several open environments, e.g., farmer's fields, non-forest wetlands, recent logging areas, etc., but is nonetheless primarily comprised of forest. Conifer stands predominate, followed by mixed stands. Hardwood or deciduous stands are less frequent and consist almost solely of young stands or trees undergoing regeneration. The numerous disturbances of the late '70s, e.g., epidemics, logging, plantations, and windfall, all resulted in major occurrences of these types of stands.

According to the Centre de Données sur le Patrimoine Naturel du Québec (CDPNQ), the sector concerned by the Project does not include any plant species designated as threatened, vulnerable or likely to be thus designated. Any special-status species have been observed in the ESIA previous baseline studies and those conducted in 2025. The sector contains no Exceptional Forest Ecosystems (EFEs), forest stands with a phytosociological interest or biological refuges. Furthermore, the past few years have seen considerable logging activity.

Figure 5-2 and Figure 5-3 show the relief and vegetation of the property adjacent to the mine site, as well as the location of the mine and tailings facility in relation to the processing plant.



Figure 5-2: View Looking North-Westerly Across the Plant and Mine Site

For personal use only

For personal use only



Figure 5-3: View Looking South-Easterly Showing the Plant Facilities in the Foreground of the Tailings Impoundment Area

For personal use only

5.2.3 Climate

The Val-d'Or area experiences a subarctic continental sub-humid climate, characterized by short, cool summers and long, cold winters. The nearest weather monitoring station with data on climate normals maintained by Environment Canada (climat.meteo.gc.ca) is the Val D'or station, approximately 60 km south of the Property. According to the available data collected at this weather station from 1991-2020, the average daily temperature for January was -16.3 °C and the daily average temperature in July was 17.7 °C. The record low during this period was -42.7 °C, and the record high was 36.1 °C. Figure 5-4 summarizes the weather normal for Val D'Or between 1991 and 2020.




Figure 5-4: Val D'or Weather Normals (Source: climat.meteo.gc.ca)

Data collected from the Val D'or weather station from 1991 to 2020 indicates that the total annual precipitation was 868 mm, with peak rainfall occurring during September (102 mm average), July (101 mm average) and August (93 mm average). Snowfall is light to moderate from October to April, with an annual average of 228 cm.

The climatic conditions at the Property do not significantly impede the Project or hinder exploration or mining activities, beyond seasonal consideration for certain works (e.g., drilling muskeg swamps during winter freeze).

5.3 Local Infrastructure and Resources

5.3.1 Airports, Rail Terminals, and Bus Services

The town of Val-d'Or, with a population of approximately 32,750 residents (Canadian Census, 2021), is located 60 km south of the Property, along the provincial Highway 111. Since Val-d'Or was founded in the 1920s, it has been a mining service centre. Val-d'Or is one of the largest communities in the Abitibi region and has all major services, including an airport with scheduled service from Montréal. A CN railway line is about 49 km east of the Property, connecting east through to Montréal and west to the North American rail network. Val-d'Or is a 6-hour drive from Montréal, and there are daily bus services between Montréal and the other cities and towns in the Abitibi region.

The town of Amos, with a population of roughly 12,675 residents (Canadian Census, 2021), is located roughly 40 km northwest of the NAL site. Amos is served by highways 109, 111, and 395 and the Amos/Magny airport.

5.3.2 Local Workforce

According to the 2021 census prepared by Statistics Canada, the population of the MRC of La Vallée-de-l'Or was 43,347 people, with 63% of the residents aged 15-64, and an average of 42 years old. Male population accounts for 51% of the population, 49% is female, and 8.7% is Aboriginal. In 2021, 64.2% of the population participated in the labour force, with 15.2% of the labour force employed in the "mining, quarrying, and oil and gas extraction" category. This portion of the workforce is experienced in mining operations, as they are currently employed at exploration and gold mines located elsewhere in the Abitibi region. Local resources also include commercial laboratories, drilling companies, exploration service companies, engineering consultants, construction contractors and equipment suppliers.

5.3.3 Additional Support Services

Additional services within the town of Val-d'Or include the Val-d'Or Hospital, grocery stores, fuel stations, financial institutions, and hotels. Val-d'Or has a Canada Post office and additional shipping/freight services by several providers. Landline telephone, mobile service, high-speed internet, and satellite internet are available in town and the vicinity.

A high-voltage power line (120 kV) passes approximately 2 km to the west of the Property and a 25 kV electric line, running along the Route du Lithium, services the Mont-Vidéo ski and recreation area.

For personal use only

For personal use only

6 History

This chapter describes the NAL Property history. This chapter contains information that was previously published by Sayona in a NI 43-101 Technical Report titled “Definitive Feasibility Study Report for the North American Lithium Project, dated April 14th, 2023.

6.1 General History

There is a large amount of historical information relating to the exploration and mining activities on the Property, which has been summarized in the following reports:

- Stone, M. and Selway, J., Technical Report of December 2009. (Stone & Selway, 2009)
- Stone, M. and Ilieva, T., Technical Report of April 2010. (Stone & Ilieva, 2010)
- Lavery, M.E. and Stone, M., Technical Report of November 2010. (Lavery & Stone, 2010)
- Hardy, C.A. and al., Technical Report of August 2017 (unpublished). (Hardy, 2017)

The compilation work was assisted by published reports, internal reports, drill logs and available assessment files from the MRNF. Historic annual mine reports are missing for the period of 1958 to 1962. Drilling information for all historic underground and some surface holes are incomplete or missing.

Table 6-1 summarizes ownership and historic exploration completed on the Property. The author has not done sufficient work to classify the historical estimates or to verify their accuracy.

Table 6-1: Summary of Ownership and Historic Activities

Year	Company ownership	Main Activity/Event	Main Result
1942	Sullivan	Prospecting.	Discovery of spodumene pegmatite.
1942-1943	Dumont	Diamond drilling.	17 holes (3,598.9 ft).
1946	Nepheline Products Ltd. and Great Lakes Carbon Corporation	Prospecting, trenching, diamond drilling bulk sampling.	Sufficient material discovered for mining, 6 holes (2,088 ft) - results encouraging.
1947	La Corne Lithium Mines Ltd.	Company was established.	
1950	Lakefield Research Ltd.	Nepheline Products Ltd. Changed name to Lakefield Research Ltd.	
1952-1953	La Corne Lithium Mines Ltd.	Diamond drilling.	+30,000 ft drilled; several spodumene pegmatites intersected.
1954	Québec Lithium Corp.	Acquires the Property, surface diamond drilling, shaft sinking mine and mill development.	
1955	Québec Lithium Corp.	Mine and mill development.	Shaft completed to 560 ft depth.
1955	Québec Lithium Corp.	Three underground levels (150 ft, 275 ft and 400 ft).	
1955	Québec Lithium Corp.	Underground drilling.	118 drillholes (+22,000 ft).
1956	Québec Lithium Corp.	Mining, underground drilling.	1,100 tons/d (~1,000 tpd); 325 drillholes totalling +53,000 ft (+16,150 m).
1957	Québec Lithium Corp.	Mining, surface diamond drilling totalling 58,920 ft.	1,250 tons/d (1,135 tpd), total 513,403 tons (465,750 t).
1959	Québec Lithium Corp.	Construction of lithium refinery commences.	
1960	Québec Lithium Corp.	Refinery operational.	
1963	Québec Lithium Corp.	Production of lithium hydroxide begins.	

For personal use only

Year	Company ownership	Main Activity/Event	Main Result
1963-1964	Québec Lithium Corp.	Mining and refining.	76,856 tons (69,722 t) of ore hoisted; year-end reserves of broken ore were 198,998 tons (180,528 t).
1965-1966	Québec Lithium Corp.	Mining and refining.	62,479 tons (56,680 t) of ore hoisted; year-end reserves of broken ore were 249,842 tons (226,653 t).
1974	Sullivan Mining Group	FS on the re-opening of the Québec Lithium mine prepared, mining, processing, historic resource estimate.	LOM is 2 1/2 years at 1,000 tpd, 2,100 ft (640 m) of cross-cutting and 3,500 ft (1,067 m) of drifting, 17,347,000 t of ore estimated at 1.14% Li_2O.
1977	Sullivan Mining Group	1974 resource confirmed.	
1979	Sullivan Mining Group	Diamond drilling.	7 holes (5,320 ft (1,621 m).
1985	Sullivan Mining Group	Diamond drilling.	2 holes (504 ft (154 m).
1987	Cambior	Acquired the Property.	
1990-1991	Cambior	Mining facilities sold.	Site rehabilitated.
1993	Cambior	Report summarizing historic mining activities (Karpoff, 1993).	
2000	Cambior	Report approving the rehabilitation.	
2001	Cambior	Grab samples.	
2008	Canada Lithium Corp.	Metallurgical testwork to produce battery grade lithium carbonate. Drilling 8 holes.	Metallurgical testing results encouraging.
2009	Canada Lithium Corp.	Mine data digitally compiled, diamond drilling program, twinning and infill.	A first in-house resources estimate from historical compilation; 30-40 Mt at 1.1-1.2% Li_2O. Twinning and infill; 38 drillholes (9,648 m).
2010	Canada Lithium Corp.	New resource estimate by Caracle Creek, diamond drilling program.	Metallurgical testwork; 67 drillholes (1,010 m); Infill and extension drilling 45 drillholes (6,938 m); A new resource model and estimate is announced (CCIC): measured and indicated: 46.6 Mt at 1.19% Li2O.
2011	Canada Lithium Corp.	PFS, diamond drilling program, RPA conduct independent review of the resources.	RPA downgrades the resources estimate; Infill and extension drilling 63 drillholes (12,003 m); AMC report updated resource estimate: measured and indicated: 32.24 Mt at 1.19% Li2O.
2012	Canada Lithium Corp.	FS completed, construction of mine and plant commences. Production launched late 2012.	Production: 20,600t at 1.07% Li_2O mined; 1,316t milled.
2013	Canada Lithium Corp.	Commissioning and ramp up in production.	Production: 303,200 t at 0.99% Li_2O mined; 259,834 t milled.
2014	Canada Lithium Corp. (Restructured)	Project delivery delays and financial difficulties; Ownership change: CLQ is restructured and becomes Québec Lithium Corp. (QLI); placed on care and maintenance.	Production: 349,000 t at 0.99% Li_2O mined and 278,922 t milled; halts production in September 2014.
2015	Québec Lithium Corp. (Restructured)	Ownership change; company restructuring; engineering studies.	Property placed in receivership; Interim production plan: Two years start-up pit plan; Project scheduling.
2016	North American Lithium Corp.	New ownership and Project management; Infill drilling launched; engineering studies; mill recommissioning.	Interim in-house resources estimate from new model and data; M+I: 34.4 Mt at 1.22% Li_2O. Additional infill drilling: 46 (+4 re-drill) drillholes (8,910.5 m).
2017	North American Lithium Corp.	Recommissioning of concentrator; engineering	Phase 1 hot commissioning and ramp-up started June 2, 2017. 22 geotechnical drillholes (956 m).

Year	Company ownership	Main Activity/Event	Main Result
		studies; Geotechnical drilling campaign.	
2019	North American Lithium Corp.	Drilling, exploration work and production shutdown.	42 drillholes (11,487 m) to define Phase 2 of the pit; Shutdown of production on February 19, 2019; Stripping work in summer 2019 permitted surface mapping of the dykes.
2021	**Sayona Québec**	**Ownership change: Sayona Québec acquires North American Lithium Inc. on August 26, 2021.**	**Updated resources were published on March 1, 2022.**

6.2 Historical Ownership & Activities

The original discovery of spodumene-bearing pegmatite on the Property was made in 1942, when three main spodumene dykes were intersected, along with several thinner ones. The owner at that time was Sullivan Mining Group and the Property went through several owners before being acquired by Québec Lithium Corporation (QLC) in 1954. QLC put the operation into production in 1955, after sinking a three-compartment shaft and establishing three working levels at 150 ft, 275 ft, and 400 ft. At the end of 1955, two stopes were in operation, which contained approximately 136,000 tons of ore grading 1.2% Li_2O.

In mid-1959, the contract for the sale of spodumene concentrate by QLC to Lithium Corporation of America Inc. was terminated. A refinery capable of producing lithium carbonate, lithium hydroxide monohydrate, and lithium chloride was constructed in Barraute and was operational by 1960. Production of lithium hydroxide monohydrate ($LiOH.H_2O$) began in June 1963.

In October 1965, operations were suspended on account of a strike and due to unfavourable market conditions. Altogether, from 1955 until 1965, a total of 938,292 t of ore were milled from 1,084,738 t mined from underground operations at the site. The production profile for the mine is presented in Section 6.3.

In 1974, the Sullivan Mining Group acquired the Property and contracted Surveyor, Nenniger et Chênevert Inc. (SNC), an engineering consulting firm, to table a feasibility report on the rehabilitation of the Québec Lithium mine (SNC, 1974). They investigated market conditions, alternative mining methods and metallurgical processes. They also recalculated the mining and property Li_2O reserves.

In October 1987, Cambior Inc. (Cambior) acquired all assets of QLC. In 1990-1991, the mining facilities were sold, infrastructures were demolished, and the site was completely levelled and rehabilitated (Karpoff, Évaluation Technique de la Propriété Minière Québec Lithium, 1993).

In May 2008, Canada Lithium Corp. (CLC) acquired the Property and began a metallurgical testing program to produce spodumene concentrate and battery-grade lithium carbonate. In 2009, the historic mine data was digitally compiled and a 29-30 Mt exploration target for lithium, with a grade range of 1.1% to 1.2% Li_2O, was estimated. This potential tonnage was verified and expanded upon through a number of drill programs completed in 2009 and 2010. In October 2010, the mineral resource was updated to a measured and indicated resource of 46.6 Mt at 1.19% Li_2O.

In April 2010, CLC completed a PFS for the development of a battery-grade lithium carbonate mining and processing operation that would produce approximately 19,000tpa of lithium carbonate equivalent (LCE) over a 15-year mine life. The feasibility study was completed in December 2010.

On February 28, 2011, CLC announced the appointment of Roscoe, Postle and Associates (RPA) to undertake an independent review of the mineral resource estimate of October 2010, following an internal review that indicated a material reduction in the resources. In March 2011, CLC announced that RPA had confirmed that there were significant issues with the geological modelling that had

For personal use only

For personal use only

produced the mineral resource estimate announced on October 28, 2010. CLC then appointed AMC Mining Consultants (Canada) Ltd. (AMC) to independently conduct a resource estimate of the Project and expeditiously prepare a new technical report in accordance with NI 43-101. AMC completed the first updated resource estimate in May 2011, filed on SEDAR on June 8, 2011 (Shannon, Nussipakynova, & Pitman, 2011).

Between June and August 2011, a 63-hole infill drilling program was carried out at the Project under CLQ, comprising 12,003 m of diamond core drilling. AMC subsequently carried out an updated mineral resource estimate using a rebuilt mineralized domain model, which incorporated the latest drilling data, in addition to data from CLQ's 2009 and 2010 drill programs, which included a certain amount of historical data. This updated resource estimate, dated December 5, 2011, reported a measured and indicated resource of 33.24 Mt at 1.19% Li_2O, on which BBA estimated a pit reserve of 17.1 Mt at 0.94% Li_2O (Shannon, Nussipakynova, & Pitman, 2011).

CLC completed a Feasibility Study in January 2011 (Hardie, et al., 2011) and commenced construction of the Project in September 2011 and its successor, Quebec Lithium Corp. (QLI), went on to operate the mine from late 2012 until September 30, 2014, extracting 676,800 t at 0.99% Li_2O from the pit. The concentrator processed some 551,695 t of ore at 1.03% Li_2O. Under CLC, the Project faced commissioning issues and mounting financial difficulties; it finally closed in November 2014 and went into receivership in January 2014.

The Project remained under care and maintenance until July 2016, when it was acquired by North American Lithium Inc., which proceeded to carry out additional infill diamond drilling and produced internal studies to recommission the Project. Plant upgrades were undertaken, and the mine and concentrator resumed operation in 2017. During 2018, the concentrator produced roughly 114,000 t of spodumene concentrate that averaged roughly 5.6% Li_2O. Due to financial difficulties, the mine and concentrator ceased operations in April 2019. The concentrator was put into care and maintenance.

6.3 Historical Production

Historical underground mine production lasted 10 years from 1955 to 1965 and peaked at 247,000 t hoisted in 1957; however, production was intermittent after 1959, when the contract for the sale of spodumene concentrate to Lithium Corporation of America Inc. was terminated.

Mine production statistics can be seen in Table 6-2.

Table 6-2: Mine Production Statistics

Year	Tonnes of Ore Hoisted	Tonnes of Ore Milled
1955	10,537	9,570
1956	240,732	216,190
1957	246,946	205,816
1958	170,739	142,511
1959	183,769	150,858
1960	4,765	3,351
1961	21,237	23,013
1962	16,566	12,825
1963	63,044	60,710
1964	69,723	63,614
1965	56,680	49,834
Total	**1,084,738**	**938,292**

While it is not known if there were some tonnage reconciliation adjustments contributing to the numbers above, it is noted that hand sorting activities were employed to remove non-dyke material and upgrade the mill feed during the course of historical operations. The total figures above suggest a difference of 13.5%, but it is postulated that sorting removed about 10% of the hoisted material.

For personal use only

6.3.1 2012 – 2014 Production

Open pit mining operations (Figure 6-1) took place from late 2012 until September 30, 2014, extracting 676,800 t at 0.99% Li_2O from the pit, while processing some 551,695 t at 1.03% Li_2O through the concentrator. Planned reserves that were mined were 540,072 t at 1.0% Li_2O while the concentrator reported 551,695 t at 1.03% Li_2O. Mine operational staff were mindful of grade and quality control, but overall dilution was relatively high at 28%.

CLC officially started concentrator production in November 2012, ramping-up from a modest 20,600 t in late 2012 to 349,000 t in 2014, until September 30, 2014. The process plant never reached nameplate capacity. The concentrator struggled to meet concentrate specification and typically produced concentrate grading between 3% and 4% Li_2O with iron typically ranging from 2% to 3%.

The conversion plant operated intermittently and in batch mode during 2014 and produced a total of roughly 100 t of lithium carbonate. Based on the 2012-2014 operation, major challenges included:

- Higher-than-planned dilution in run-of-mine ore.
- Mining costs were higher than anticipated due to the narrow vein nature of the deposit.
- High levels of dilution led to processing issues and production of low-quality concentrate.
- Competition for skilled labour with other mines in the Abitibi-Témiscamingue region.



Figure 6-1: Québec Lithium Project Open Pit Mine Operations at Peak in 2014

6.3.2 2017 – 2019 Operations

Plant upgrades were undertaken prior to restarting the mining and concentrator operation in 2017. Major plant upgrades included installation of a second ore sorter, modifications to the crushed ore silo, and addition of a wet high-intensity magnetic separator.

Efforts were made to improve operational procedures to better understand and manage dilution in the run-of-mine ore. Mining and processing worked closely together to establish upper specification limits on iron content in the feed to the mill. Geology, mining, and process teams worked in collaboration both on understanding sources of dilution and on aligning key production indicator (KPI) for operations.

The NAL mine and concentrator operated from June 2017 to March 2019. The aim was to maintain host rock dilution below 20%. During operation, roughly 1.5 Mt of ore was fed to the plant. The concentrator produced roughly 166,000 t of spodumene concentrate, typically ranging in grade from 5.5% to 6.0% Li_2O and 0.9% to 1.6% Fe. The plant never achieved nameplate capacity (3,800 tpd) and due to depressed spodumene concentrate prices, the plant was put into care and maintenance in April 2019.

6.4 2021 Acquisition to Present

Sayona Québec acquired the NAL project in August 2021. A PFS was completed in May 2022 for the restart of mining and concentrator operations. Significant process plant upgrades were implemented to ensure production of high-quality chemical-grade spodumene concentrate at nameplate capacity. Operation of the concentrator commenced in March 2023, with first spodumene concentrate sold in August 2023. The mine is a currently operating spodumene producer.

For personal use only

For personal use only

7 Geology and Mineralization

This chapter describes the NAL Property geological setting and mineralization. Information contained in this chapter was previously published by Sayona in an ASX Press Release and JORC (2012), dated August 27th, 2025, and in a NI 43-101 Technical Report titled “Definitive Feasibility Study Report for the North American Lithium Project, dated April 14th, 2023.

7.1 Regional Geology

The Archean Preissac-La Corne batholith is a syn- to post-tectonic intrusion that was emplaced in the Southern Volcanic Zone of the Abitibi Greenstone Belt of the Superior Province of Québec. The batholith intruded along the La Pause anticline into the ultramafic to mafic lavas of the Kinojevis (2,718 Ma; Corfu 1993) and Malartic groups, and biotite schist of the Kewagama Group. The batholith is bound to the north by the Manneville fault and to the south by the Cadillac fault and the eastward extension of the Porcupine-Destor fault.

The batholith is a composite body comprising early metaluminous gabbro, diorite, monzonite, and granodiorite (ca. 2,650-2,760 Ma: Steiger and Wasserburg 1969, Feng and Kerrich 1991) and four late peraluminous monzogranitic plutons (Preissac, Moly Hill, La Motte and La Corne) and associated pegmatites and quartz veins (ca. 2,621-2,655 Ma: Gariépy and Allègre 1985, Feng and Kerrich 1991). The final intrusive activity in the area was the Proterozoic diabase dykes. The regional metamorphic grade is greenschist facies and close to the batholith is hornblende hornfels facies contact metamorphism.

7.2 Local Geology

The geology of La Corne and Fiedmont Townships is described in reports by Tremblay 1950, Dawson 1966 and Mulja et al., 1995 and is shown on the Geological Survey of Canada (GSC) map 999A (Tremblay, 1950) and GSC map 1179A (Dawson, 1966). Local geological units are summarized in Table 7-1.

Table 7-1: Geological Units

Geologic Unit	Description
Basaltic Lavas Malartic and Kinojevis Groups 2.718 Ma	Volcanic rocks are generally fine-grained and medium to dark green on fresh surfaces. The units are massive or locally exhibit structures such as pillows, flow breccia or amygdule. Under the microscope, the volcanic rocks are mainly green hornblende, plagioclase with minor amounts of quartz, epidote, biotite, and chlorite. Accessory minerals include titanite, apatite, magnetite, pyrite and an alteration product of ilmenite, leucoxene. The abundant green hornblende shows incipient alteration to chlorite or partial replacement by holmquistite.
Biotite Schist Kewagama Group	The biotite schists are conformably interbedded with the basaltic lavas. The schists are mainly sedimentary in origin, derived from greywacke, sandstone, and conglomerate. The biotite schist beds are up to 40 cm thick, fine-grained and are grey to black on fresh surfaces. They are foliated with the foliation parallel with either the contact or the foliation in the outcrops of the Preissac-La Corne batholith. Under the microscope, the biotite schist consists mainly of quartz, plagioclase, and biotite. Hornblende and chlorite are major components in a few beds. The common accessory minerals are apatite, epidote, tourmaline, pyrite, and magnetite.
Metaperidotite	The metaperidotite is interbedded with basaltic lavas and, less commonly, with biotite schists. Metaperidotite is fine-grained and black or dark green in colour. The weathered surface is typically brown and exhibits a variety of textures, including polygonal fracture systems, pseudo-pillow structures and a platy structure, which is likely komatiite. The metaperidotite consists mainly of felted aggregates of chlorite flakes, acicular to prismatic actinolite, fibrous serpentine and talc flakes with accessory magnetite, carbonate, and pyrite. The platy structure consists of planar concentrations of chlorite and serpentine, alternating with similarly shaped concentrations of actinolite and magnetite. Primary olivine and/or pyroxene relicts are pseudomorphed by aggregates of chlorite, serpentine, talc, magnetite, and carbonate.

Geologic Unit	Description
Granodiorite La Corne Pluton 2,621-2,655 Ma	The La Corne pluton has been described by Mulja et al. (1995a). It is dominated by biotite monzogranite, which gives way inward to two-mica and muscovite monzogranite. The geology of the La Corne pluton is similar to that of the rest of the Preissac-La Corne batholith.
Gabbro/Diabase Dykes Proterozoic age	**There are post-batholithic gabbro/diabase dykes that outcrop in the batholith and nearby as tabular bodies up to 60 m wide and several kilometres long, striking either N25º E or N40º E and dipping vertically. The gabbro is fine- to medium-grained and tends to be ophitic.**

Local geological units comprise (from oldest to youngest): basaltic lavas (Malartic and Kinojevis Groups), biotite schist (Kewagama Group), metaperidotite and monzogranite (La Corne pluton).

Local stratigraphy and local geology are shown in Figure 7-1 and Figure 7-2.

The Manneville fault, a major strike fault, is occasionally exposed in the basaltic lava outcrops along the north side of the batholith. As a result of the strike of N80º W, the distance between the fault and the batholith varies from approximately 3.2 km north of Preissac to less than 1.6 km at Lac Roy. It contains some base metal sulphides, locally. Many of the lithium-bearing dykes occur within 2.5 km SW and roughly parallel with the Manneville fault.




Figure 7-1: Stratigraphy of NAL Property

For personal use only




Figure 7-2: Local Geology of NAL Property

For personal use only

7.3 Property Geology

Figure 7-3 shows the Property geology including an interpreted surface projection of spodumene-bearing pegmatite dykes.




Figure 7-3: Geology of NAL Property, Centred on the Currently Interpreted Mineralized System

For personal use only

For personal use only

Figure 7-4 presents a representative geological cross-section of the Property. Property-scale geological units comprising volcanics, gabbro, granodiorite and pegmatite dykes are described below.




Figure 7-4: NE – SW Geological Cross-Section of Mineralized System

7.3.1 Volcanics

Volcanic rocks are represented by dark green mafic metavolcanics and medium grey silicified intermediate volcanics. The mafic metavolcanics range from medium grey to dark grey-green and are cryptocrystalline to very fine-grained. While these rocks are mostly massive, they occasionally display compositional banding with slightly coarser-grained amphibole. Some of the mafic volcanic rocks exhibit weak to moderate foliation, featuring minor dark green amphibole-rich bands and irregular patches that generally follow the foliation. Overall, these mafic volcanic rocks are quite hard and sometimes magnetic.

Both mafic and intermediate volcanic rocks show moderate to strong pervasive silicification, with minor chloritization and varying degrees of lithium alteration. Green hornblende alteration is observed near the spodumene-bearing pegmatite dykes. Additionally, there are fine-grained, weakly foliated, dark green amphibolites. Locally, a salt-and-pepper appearance is present where plagioclase is more prominent, making the amphibolite difficult to scratch. These amphibolites undergo strong pervasive potassic alteration, which is evident as biotisation and widespread or patchy lithium alteration.

7.3.2 Granodiorite

The granodiorite is massive, coarse-grained to porphyritic, medium grey to greenish grey in colour and exhibits a salt-and-pepper appearance. Granodiorite locally contains fragments of the same composition or that are slightly enriched in muscovite.

The main mineral constituents of granodiorite are light grey to greenish white plagioclase (40-45 vol%), dark green to black amphibole, most likely hornblende (15-20 vol%), mica (20 vol%),

represented by biotite and muscovite, grey quartz (10-15 vol%) and minor epidote, chlorite and disseminated sulphides. The grain size ranges from 0.5 mm to 5 mm. Granodiorite has patchy to pervasive lithium and/or chlorite alteration, weak epidote alteration, and locally pervasive potassic alteration.

7.3.3 Pegmatite Dykes

Three different types of pegmatite dykes have been identified based on mineralogy and textures: PEG1, PEG2 and PEG3. These are described in Table 7-2 and Figure 7-5, Figure 7-6 and Figure 7-7. PEG1 textural characteristics are described in Table 7-3.

The main differences between the three types of pegmatite dykes are the amount of spodumene, feldspar and quartz, the texture of the pegmatite and the presence or absence of zoning. Spodumene grain size can be highly variable within a zone and overall, through entire intersections.

Table 7-2: Pegmatite Types in the Property

Pegamatite Type	Description
PEG1	PEG1 dykes are zoned and contain five mineralogical/textural zones described in Figure 7-5Table 7-3.
PEG2	PEG2 dykes are not zoned and contain coarse- to medium-grained, light grey and with pale yellowish-green crystals of spodumene (5-15 vol%), grey quartz (35-40 vol%), white megacrystals of plagioclase and K-feldspar (40-50 vol% and, most likely, albite and orthoclase), occasional millimetre-sized garnets, light coloured mica that is possibly lepidolite, flakes of biotite, specks of molybdenite, very rare chalcopyrite surrounded by brownish anhedral mineral with resinous lustre that is possibly sphalerite. The spodumene mineralization occurs from contact to contact with no apparent zonation; concentration varies from 2-3 vol% to approximately 20 vol%. Spodumene crystals can be both tabular and needle-shaped within the same intersection. Euhedral crystals are common, while preferred orientations are exhibited by some spodumene crystals and can form both the matrix or fill the interstices between larger quartz, plagioclase, and K-feldspar grains, as observed in the 2016 drilling program and shown in Figure 7-5. In Figure 7-6, spodumene megacrystals in PEG2 are shown oriented perpendicular to the contact in drillhole QL-S09-026. Observed locally, Figure 7-7 shows a preferential orientation for spodumene crystalline clusters.
PEG3	**PEG3 dykes are quartz dominant and contain less than 1% spodumene. They are medium- to coarse-grained, light pink-grey to medium grey creamy pink colour, with black or grey patches of mica, i.e., biotite and muscovite. Megacrystals of mica form up to 40% of the rock. PEG3 dykes are variable in width from 0.4 m to 8.0 m, contain small vugs and very hard to scratch and cut.**

Table 7-3: Mineralogical Zoning of PEG1 Type Pegmatites (as Intersected in Core from Top to Bottom)

Pegamatite Type	Description
Quartz core	5 cm to 50 cm zone of massive, medium- to coarse-grained grey quartz, with very rare plagioclase or spodumene crystals. Spodumene near the quartz core is white, elongated, and crystals up to 10 cm long and 1 cm wide were observed in the outcrop.
Spodumene zone	Medium- to coarse-grained pegmatite, 35-40 vol% quartz, 40-50 vol% plagioclase, with white euhedral and pale yellowish green interstitial crystals of spodumene (5-20 vol%) and rare aggregates of mica (biotite). The size of the spodumene crystals varies from 0.2 cm to 14 cm.
Border zone	1 cm to 10 cm fine-grained aplitic zone. Distinct change in grain size and colour. The pegmatite becomes fine-grained and uniformly grey, mainly composed of quartz-plagioclase-K-feldspar.

For personal use only




Figure 7-5: Coarse-Grained Pegmatite Dyke in Hole NAL-16-16




Figure 7-6: Spodumene Megacrystals Perpendicular to PEG2 Contact Zone in Hole QL-S09-026



Figure 7-7: Preferential Orientation of Spodumene Crystals in Hole NAL-16-024

For personal use only

7.4 Mineralization

Results of past mineral exploration, resource evaluation and mining demonstrate that NAL is an extensively mineralised lithium system. The primary metal is lithium and it is mainly associated with spodumene, a lithium bearing pyroxene.

A total of 117 spodumene-bearing pegmatite dykes each with thicknesses more than 2 m have been identified in the NAL geological model.

Pegmatite mineralisation occurs as a swarm of pegmatite dykes spanning at least 3,500 m along strike in a northwest direction and 1,300 m in width. Pegmatite dykes are generally dipping subvertical to 50 degrees southwest. Pegmatite dykes have been drilled to a depth of approximately 800 m vertical, and they remain largely open at depth. A subset of pegmatite dykes strikes east-west, obliquely to the main northwest orientation. Some pegmatite dykes can be traced more than 700 m along strike in surface exposures and 70 m vertically down pit walls (Figure 7-8). Pegmatite dykes have variable widths up to 70 m.

Pegmatite dykes intrude granodiorite and mafic volcanics. They contain steeply dipping splays, splits and bends that can be mapped between benches within the open pit. Pegmatite dykes vary in width from tens of centimetres up to 90 m. Most of the pegmatite dykes greater than 3 m in width are spodumene-bearing.

Spodumene crystals are widely and variably spread throughout the dykes, displaying faint greenish shades and sometimes locally displaying centimetric to decametric crystal gradations (Figure 7-9). Pegmatite dykes display internal zoning (Figure 7-10).




Figure 7-8: Multiple Exposure of Pegmatite Dykes in the pit (Face Looking West)

For personal use only



Figure 7-9: Coarse to Fine-Grained Spodumene Mineralization in Hole NAL-16-024




Figure 7-10: Pegmatite Dyke Zoning and Alteration in Hole NAL-16-036

For personal use only

For personal use only

8 Deposit Types

8.1 Rare-Element Pegmatites of the Superior Province

Rare-element Li-Cs-Ta ("LCT") pegmatites may host several types of minerals with potential economic significance, such as columbite-tantalite (tantalum and niobium minerals), tin (Sn) (cassiterite), lithium (Li) (ceramic-grade spodumene and petalite), rubidium (Rb) (lepidolite and K-feldspar), and cesium (Cs) (pollucite), collectively known as rare elements, strategic and energetic metals (Selway et al., 2005). Two families of rare-element pegmatites are common in the Superior Province:

- LCT enriched, and niobium-yttrium-fluorine ("Nb-Y-F" or "NYF") enriched. LCT pegmatites are associated with S-type, peraluminous (aluminium-rich), quartz-rich granites referred to as two-mica granites. S-type granites crystallize from a magma produced by partial melting of pre-existing sedimentary source rock. They are characterized by the presence of biotite and muscovite, and the absence of hornblende.
- NYF pegmatites are enriched in rare earth elements ("REE"), uranium and thorium, in addition to Nb, Y, and F, and are associated with A-type, subaluminous to metaluminous (aluminium-poor), quartz-poor granites or syenites (Černý, 1991).

Figure 8-1 summarizes the postulated chemical evolution of lithium-rich pegmatites with distance from the granitic source (London, 2008).





Figure 8-1: Chemical Evolution of Lithium-Rich Pegmatites

8.2 La Corne Pluton Rare-Element Pegmatites

Rare-element pegmatites associated with the La Corne pluton are LCT pegmatites, because they are enriched in Li and Ta, and they are associated with the S-type La Corne pluton, i.e., biotite to two-mica to muscovite monzogranite. The La Corne pluton is the fertile parental granite from which the pegmatites were derived. The presence of garnet, molybdenite, columbite-tantalite and sphalerite in the muscovite monzogranite indicates that the La Corne pluton is fertile granite rather than barren granite (Mulja et al. 1995a).

Figure 8-2 describes the geological evolution of the La Corne pluton and its role in the emplacement of spodumene-bearing pegmatite dykes. Rare-earth pegmatites are regionally zoned from the La Corne pluton outwards: beryl pegmatites to spodumene-beryl pegmatites, spodumene-bearing pegmatites to molybdenite-bearing albitite to molybdenite-quartz veins.



The geology of the La Corne pluton is similar to the rest of the Preissac-La Corne batholith. The geological evolution of the pluton comprises:

(A) Early side-wall crystallization produces marginal biotite monzogranite and less dense crystal-layer melts, which ascend

(B) to the roof of the magma chamber; (B) Fractional crystallization continues to form successive two-mica and muscovite monzogranite layers from more differentiated melts; (

(C) Expulsion of pegmatite-forming, volatile-rich magma from the chamber due to fluid overpressure, results in the emplacement of the beryl pegmatite in the overlying monzogranite; and

(D) Later contraction of the pluton on cooling reactivates fractures in the country rock and produces new fractures, into which the more evolved melts are intruded. This gives rise to the spodumene-beryl and spodumene pegmatites.

Figure 8-2: History of La Motte and La Corne Plutons

For personal use only

Rare-element pegmatites share characteristics with other pegmatites in the Superior Province:

- They are located within the Abitibi Greenstone Belt, near the contact with the Pontiac sub province. Many pegmatites are less than 2.5 km SW of the Manneville fault zone.
- They are genetically related to the fertile La Corne pluton.
- They are hosted within basaltic lavas of the Kinojevis group.
- Basaltic lavas have undergone metasomatism, resulting in the formation of holmquistite (lithium amphibole) at the contact with the La Corne pluton.
- Spodumene is the main lithium-bearing mineral. Columbite-tantalite is the main tantalum-bearing mineral. Cesium-bearing minerals have not been identified in pegmatites.
- Columbite-tantalite crystals are found within the albite.

For personal use only

9 Exploration

Elevra has not conducted any exploration work other than diamond core drilling as covered in Chapter 10 – Drilling on the Project as of the effective date of this technical report.

For personal use only

For personal use only

10 Drilling

10.1 Drilling History

Diamond core drilling is the only means of exploration employed at NAL Project for the purpose of the Mineral Resource estimate. Exploration drilling programs completed by historical companies (1942 - 1985), Canada Lithium Corp. ("CLC") (2009 – 2011) and North American Lithium Corp. (2016 – 2019) and Sayona (2023 – 2024) are summarized in the sections below.

The Project database used in the Mineral Resource estimate contains information for:

- Diamond drillholes completed in 2009, 2010, 2011, 2016 and 2019 programs.
- Diamond drill core resampling completed in 2022 by Sayona.
- Diamond drillholes completed in 2023 and 2024 programs.

Figure 10-1 shows the location of drillholes incorporated within the Mineral Resource estimate.

10.1.1 Historical (1942 – 1985)

Drilling programs were completed from surface and underground by various operators between 1942 and 1985. In total, 873 holes were drilled, totalling 60,862 m. These historic drillholes have not been assayed and their location is uncertain. They are therefore excluded from the Mineral Resource estimate.

10.1.2 Canada Lithium Corp. (2009 – 2011)

CLC completed exploration, metallurgical and geotechnical drilling programs in 2009, 2010 and 2011. Drilling programs are summarized in Table 10-1.

Table 10-1: Summary of CLC Drillholes

Year	Period	No. of Holes	Meters	Comments
2008	June	8	Unknown	Metallurgical samples
2009	October-December	38	9,646	Twinning and infill
2009-10	December-January	67	1,010	Metallurgical samples and geotechnical
2010	April-June	45	6,938	Infill and extension
2011	June-August	63	12,003	Infill and extension
Total		221	29,597	

The 2009 drilling program comprised 38 NQ-sized (47.6 mm core diameter) diamond drillholes and one wedge (9,646 m). Nine holes were abandoned and redrilled (470 m) because of technical difficulties. Holes were drilled on eight sections intersecting spodumene-bearing pegmatite dykes perpendicular to strike.

The 2010 drilling program comprised 45 NQ-sized diamond drillholes (6,938 m). Eight geotechnical drillholes were also completed. Holes were drilled on 15 sections intersecting pegmatite dykes perpendicular to their strike.

The 2011 drilling program comprised 63 NQ-sized diamond drillholes (12,003 m). Holes were drilled on 14 sections intersecting pegmatite dykes perpendicular to strike.

For personal use only




Figure 10-1: Property Map Showing Location of Drillholes Incorporated Within the Mineral Resource Estimate

10.1.3 North American Lithium Corp. (2016 – 2019)

North American Lithium Corp. completed exploration and resource definition drilling programs in 2016 and 2019 (Table 10-2).

Table 10-2: Summary of North American Lithium Corp Holes

Year	Period	No. of Holes	Meters	Comments
2016	October-December	46	8,911	Infill and extension
2019	May-July	42	11,487	Infill and extension
Total		88	20,398	

The 2016 drilling program comprised 46 NQ-sized diamond drillholes, including four redrills (8,911 m). The holes were drilled on nine sections targeting the Naud pegmatite dyke, a new body of mineralization first encountered during pit excavations in 2012-2014, and on thirteen sections targeting pegmatite dyke extensions on the eastern margin of the deposit (Figure 10-2). The holes were drilled on bearings of 45°, perpendicular to the strike of pegmatite dykes.

The 2019 drilling program comprised 42 NQ-sized diamond drillholes (11,487 m). A total of 3,976 samples totalling 4,471 m, were collected, but only 308 samples were analysed due to financial constraints.



Figure 10-2: Infill and Extension Drilling Program (Late 2016)

10.1.4 Sayona (2022)

Sayona completed no exploration drilling in 2022. Sayona completed a program of historical drill core sampling in 2022 with objectives to:

- Sample core intervals where they intersect modelled pegmatite dykes. In most instances the core was previously described as pegmatite but had not been sampled.
- Sample pegmatite, granodiorite, volcanics and gabbro lithologies to collate a valid Fe content database.

For personal use only

- Sample pegmatite, granodiorite, volcanics and gabbro lithologies to collate a valid density database.

A total of 574 core samples were collected from 129 drillholes for Li_2O % and Fe % analysis. A total of 600 core samples were collected from 97 drillholes for density measurements.

10.1.5 Sayona (2023 – 2024)

Sayona completed two major resource definition and exploration drilling programs in 2023 and 2024 (Table 10-3). The 2023 drilling program comprised 172 NQ-sized diamond drillholes (48,076 m). The 2024 drilling program comprised 153 NQ-sized diamond drillholes (53,444 m). A subset of 8 holes, totalling 305 m were not surveyed and ignored for the purpose of Mineral Resource estimation.

The 2023 and 2024 drilling programs mainly comprised definition drilling at reduced spacing in order to improve confidence in the location, width, and grade of the pegmatite dykes, and to upgrade Inferred resources to the Indicated category. The drilling also provided the opportunity to investigate the areas between historical stopes and existing mining infrastructure. Exploration drilling was completed to the northwest, north, southeast and west of the NAL open cut pit.

The 2023 and 2024 drilling campaigns programs were successful to improve confidence in the geological model and enhance the understanding of mineralisation within and outside of the current pit shell. Results of the 2023 and 2024 Programs are incorporated in the Mineral Resource estimate.

Table 10-3: Summary of Sayona Drillholes Completed in 2023 and 2024

Year	Period	No. of Holes	Meters
2023	1 January -31 December	172	48,076
2024	1 January – 31 December	153*	53,444
Total		325	101,520

**Note: Includes drilling of drill hole extensions for two of the 2023 holes during 2024.*

10.2 Drilling Procedures

Diamond drill cores are NQ diameter (47.6 mm) and HQ diameter (63.5 mm). Core recovery for all drilling programs is reported to be excellent, typically exceeding 95%. There is no correlation or bias observed between the Li_2O grades obtained and core recovery. No twinned holes have been drilled on the Property.

10.2.1 Collar Surveys

CLC (2009 – 2011) and North American Lithium Corp. (2016 – 2019) employed similar methods for all drill collar surveys. Casings were left in place and capped to support future downhole testing or drill extensions.

GPS coordinates for all drill collar locations were positioned by mine-site personnel using a Trimble TSC3 precision GPS instrument and incorporated into the exploration grid.

All drillhole collars were precisely surveyed by J.L Corriveau, a local surveying contractor. The topography used is a combination of three Lidar surveys dated from September 2024 to April 1st, 2025. The grid system employed is UTM NAD 83 Zone 18.

For personal use only

For personal use only

10.2.2 Downhole Surveys

From 2009 to 2016, CLC and North American Lithium Corp. employed similar methods for downhole surveying.

In 2009, Major Drilling used a Reflex EZ-Shot and Orbit utilized a Flexit single shot. In 2010 to 2012, all drilling contractors employed a Reflex EZ-Shot.

In 2016 and 2019, drilling contractors employed Flexit testing instrument with downhole measurements every 15 m whilst drilling. Multishot tests were performed every 3 m along the hole upon closure.

In 2023 and 2024, drillhole deviation was regularly measured by the drill operator, approximately every 10 m using three instruments (EZ-Trac, SPRINT-IQ and DEVI-GYRO) and using the instrument Reflex Sprint-IQ. Multishot tests were recorded every 3 m along the hole upon closure.

Recorded measurements included depth, azimuth (magnetic north), inclination, magnetic tool face angle, magnetic field strength and temperature.

10.3 Core Logging Procedures

10.3.1 Historical (1942 – 1985)

Historical records 1942-1985 contain no information concerning drill core logging practices.

10.3.2 Canada Lithium Corp. (2009 – 2011)

Core logging procedures employed by CLC are summarized in Table 10-4.

Table 10-4: Summary of Canadian Lithium Corp. Core Logging Procedures

Year	Description
2009	Sample security and chain of custody commenced with removal of core from the core tube and boxing of drill core at the drill site. Core was placed in wooden boxes, sealed with lids, and secured with plastic straps. Core was transported from the drill site to CLQ's core facility in Val-d'Or, either by the drill contractor or CLQ personnel. At the core facility, core was washed, photographed, and logged before sampling. Core logging was performed by consulting geologists, including one responsible for overseeing the 2009 on-site drilling program. Geological and geotechnical data were recorded directly into Coreview v.5.0.0 software (Visidata Pty Ltd.), with nightly exports and backups to a secure data server.
2010	CLC established a new core facility in Val-d'Or, relocating all logging, sawing, and storage equipment to that location. Logging and sampling process was overseen by a senior geologist, with two other geologists handling the logging. Logging followed protocols of the 2009 program.
2011	The core shack in Val-d'Or was used for the 2011 program, with all logging conducted at that facility. Core from the 2011 program, previously stored with earlier samples at the C-Lab core storage in Val-d'Or, was moved to NAL's core storage facilities at the mine site. Logging was supervised by M.E. Lavery, P. Geo., and logging was completed by two independent contract geologists. Logging followed protocols of the 2009 and 2011 programs.

10.3.3 North American Lithium Corp. (2016 – 2019)

Core logging procedures employed by North American Lithium Corp. are summarized in Table 10-5. Figure 10-3 and Figure 10-4 show core logging and storage facilities.

Table 10-5: Summary of North American Lithium Corp. Core Logging Procedures

Year	Description
2016	North American Lithium Corp. rented well-equipped core logging and sampling facilities from Royal Nickel Corporation (RNC), a local company with a regional base of operations. Core samples were placed in wooden boxes, respecting the drilling sequence, with wooden markers indicating depth. Once filled, lids were sealed on the boxes, which contractors then delivered to North American Lithium Corp. personnel for transportation to the core shack located at Amos. The RNC core shack in Amos was utilized during the 2016 drilling program, and all logging and sawing of core was completed at this facility. All core from the 2016 program is now stored at the mine site, along with core from previous years that was brought back from the C-Lab core storage facility located in Val-d'Or. The 2016 logging was supervised by the chief geologist for North American Lithium Corp. Logging was completed by two independent contract geologists using the Geotic data recording software. Protocols for the logging used in 2016 were consistent with the 2009, 2010 and 2011 programs but they were more systematic and uniform, having adopted MERN geological rock coding. Photographs of the core were taken systematically after core boxes were opened and laid out on the platform and, prior to any marking or cutting taking place, Rock quality designation (RQD) measurements were generally taken at regular intervals of 6 m, with the fracturing and recovery data being recorded. Once geologists had logged and sampled the drill core, boxes were brought back to the mine site for long-term storage on sheltered racks.
2019	Core samples were placed in wooden boxes, respecting the drilling sequence, with wooden markers indicating depth. Once filled, lids were sealed on the boxes, which contractors then delivered to North American Lithium Corp. personnel. Logging was supervised by the chief geologist for North American Lithium Corp. Logging was completed by independent contract geologists using the Geotic data recording software. Photographs of the core were taken systematically after core boxes were opened and laid out on the platform and prior to any marking or cutting, RQD measurements were generally taken at regular intervals of 6 m, with the fracturing and recovery data being recorded. Geologists logged core on benches set up outside at mines' core storage area. Once geologists had logged and sampled core, boxes were placed on sheltered racks. Logging protocols were consistent overall with the 2016 program.

10.3.4 Sayona (2022 – 2024)

Core logging procedures employed by Sayona are summarized in Table 10-6.

Table 10-6: Summary of Sayona Core Logging Procedures

Year	Description
2022 to 2024	Drill core was placed in wooden boxes, respecting the drilling sequence, with wooden markers indicating depth. Once filled, lids were sealed on the boxes, and NAL personnel transported the core to the core shack located in the nearby town, Val-d'Or. Upon delivery to the core shack, the drill core was taken care of by the company's team of technicians and geologists. All sampling is supervised by a geologist. Exploration drill core was logged geologically. Photographs of wet core were taken systematically after core boxes were opened and laid out on the platform and, prior to any marking or cutting taking place. Geological logging recorded qualitative descriptions of lithology, alteration, mineralization, veining and structure. Logging also includes measurement of core recovery and RQD. Geological logging of recovered drill core visually identified as pegmatites and its constituent mineralogy in lithium to determine the intervals for sampling. Samples were clearly identified in their respective bags without risk of contamination.

For personal use only



Figure 10-3: Core Logging Facilities at RNC Exploration Office in Amos (35 km from Site)



Figure 10-4: Core Storage Sheds and Facilities at the NAL Mine Site

10.4 Qualified Person's Opinion

It is the QP's opinion that the drilling and core logging procedures put in place by Canada Lithium Corp., North American Lithium Corp., and Sayona met acceptable standards at the time of completion and provide sufficiently reliable results for use in the Project database and Mineral Resource estimate.

For personal use only

For personal use only

11 Sample Preparation, Analyses and Security

This section outlines the sample preparation, analyses and security procedures pertaining to preparation of the Mineral Resource estimate.

11.1 Sample Preparation Methods

11.1.1 Historical (1942 – 1985)

Historical records 1942-1985 contain no information concerning the sampling methods employed for drill core sampling, nor the analytical techniques used to determine Li_2O content.

A review of historical drill logs indicates that sample intervals varied from around 3 cm to 31 m, with an average interval of about 2.4 m. Assay values for $\%Li_2O$ are noted either typed or handwritten on the drill logs, but no original assay certificates are available to verify these grades. A total of 806 assays were reported for 61 surface drillholes, with some grade values possibly representing composites. Information on grades for the underground drilling is not available. Historical data was excluded from the Mineral Resource estimate.

11.1.2 Canada Lithium Corp. (2009 – 2011)

Sample preparation procedures employed by CLC are summarized in Table 11-1.

Table 11-1: Summary of CLC Sample Preparation Methods

Year	Description
2009	A total of 2,342 core samples were collected from 38 drillholes. Core samples were sawn in half; one half of the sampled interval was submitted for analysis, and the remainder was retained in the core box for reference and future testing and/or verification. The nominal sample interval was 1 m, or less, if the pegmatite was less than 1 m in width. Lengths were adjusted as necessary to reflect geological and/or mineralization contacts. Pegmatite veins that were 0.4 m to 1 m in thickness were also sampled if spodumene was visible. Longer sample lengths were taken of strongly sheared core or sections with poor core recoveries. After cutting, the core samples were sealed with a plastic cable tie in labelled plastic bags with their corresponding sample tag. The plastic sample bags were placed in large rice sacks and secured with tape and a plastic cable tie for shipping to the laboratory. The drillhole and sample numbers were also labelled on the outside of each rice sack and checked against the contents, prior to sealing the sacks. Standards and blanks were inserted into the sample sequence prior to shipping. Samples from individual holes constitute individual batches of samples sent to the laboratory.
2010	A total of 1,454 core samples were collected from 41 drillholes. Core samples were sawn in half. One half of the sampled interval was submitted for lithium analysis. The nominal sample interval was 1 m with more than 99.7% of the samples being 1 m or less. Lengths were adjusted as necessary to reflect geological and/or mineralization contacts. After cutting, the core samples were sealed with a plastic cable tie in labelled plastic bags with their corresponding sample tag. The plastic sample bags were placed in large rice sacks and secured with tape and a plastic cable tie for shipping to the laboratory. The drillhole and sample numbers were also labelled on the outside of each rice sack and checked against the contents, prior to sealing the sacks. Standards and blanks were inserted into the sample sequence prior to shipping. Samples from individual holes constitute individual batches of samples sent to the laboratory. In 2010, due to a change of primary laboratory, samples were delivered by CLC to the ALS Laboratory Group (ALS) preparation facility in Val-d'Or.

Year	Description
2011	A total of 3,167 core samples were collected from 53 drillholes. The core shack in Val-d'Or was utilized during the 2011 program, and all the sawing of core was completed at this facility. All the core from the 2011 program that was stored with the previous years' core at the C-Lab core storage facility in Val-d'Or has now been transferred to NAL's core storage facilities at the mine site. The 2011 sampling was supervised by M.E. Lavery, P. Geo., and sampling was completed by two independent contract geologists. The same protocols for core cutting and sampling used in the 2009 and 2010 drill programs were used in 2011. Core samples were sawn in half. One half of the sampled interval was submitted for lithium analysis. The nominal sample interval was 1 m with more than 93% of the samples being 1 m or less. Lengths were adjusted as necessary to reflect geological and/or mineralization contacts, which created samples of less than 1 m in length. In 2011, samples were delivered by CLC personnel to the ALS facility in Val-d'Or and the samples were then shipped to ALS facilities in either Timmins or Thunder Bay for preparation. Prepared samples were shipped to Vancouver, British Columbia, for analysis.

11.1.3 North American Lithium Corp. (2016 – 2019)

Sample preparation procedures employed by North American Lithium Corp. are summarized in Table 11-2.

Table 11-2: Summary of North American Lithium Corp. Sample Preparation Methods

Year	Description
2016	A total of 2,367 core samples were collected from 46 completed drillholes. The 2016 sampling was supervised by the chief geologist for North American Lithium Corp. Sampling was completed by two independent contract geologists. Protocols for core cutting and sampling were consistent with 2009 and 2010 programs. Chosen core samples were always sawn in half, with one half of the sample interval submitted for lithium analysis and the remainder kept for future testing and/or reference. The nominal sample interval was 1 m. Lengths were adjusted as necessary to reflect geological and/or mineralization contacts, which created the samples of less than 1 m length. Sample tags were fixed to core boxes. To better quantify the background values, samples of the host rocks that were immediately adjacent to the contact with pegmatite dykes were collected systematically, as samples separate from the pegmatite. Samples were delivered by North American Lithium Corp. personnel to the Techni-Lab SGB (ActLabs) laboratory facility in Sainte-Germaine-Boulé, Québec, for sample preparation and primary analysis. Coarse rejects were returned to the mine site for storage and reference, while the ALS Laboratory Group of Vancouver, British Columbia, was contracted for duplicate analyses of chosen pulp and rejects.
2019	A total of 3,976 core samples were collected from 37 drillholes. Protocols for the core cutting and sampling that were used in 2019 were consistent with the 2016 drill program. Sampling was completed by independent contract geologists. Chosen core samples were always sawn in half, with one half of the sample interval submitted for lithium analysis and the remainder kept for future testing and/or reference. The nominal sample interval was 1 m. Lengths were adjusted as necessary to reflect geological and/or mineralization contacts, which created the samples of less than 1 m length. Samples were delivered by North American Lithium Corp. personnel to the ActLabs laboratory facility in Sainte-Germaine-Boulé, Québec, for sample preparation and primary analysis. Coarse rejects were returned to the mine site for storage and reference. ALS of Vancouver, British Columbia, was contracted for duplicate analyses of chosen pulp and rejects. Due to financial constraints, not all pegmatite intervals were sampled in 2019. These samples were sampled in 2022 (see section below).

For personal use only

11.1.4 Sayona (2022-2024)

Sample preparation procedures employed by Sayona are summarized in Table 11-3.

Table 11-3: Summary of Sayona Sample Preparation Methods

Year	Description
2022	A total of 574 core samples were collected from 129 drillholes for Li_2O % and Fe % analysis. A total of 600 core samples were collected from 97 drillholes for density measurements. After logging, core was marked by a geologist with sample intervals. Selected core samples were always split in half, with one half of the sample interval submitted for lithium, iron and density analysis, and the remainder kept for future testing and/or reference. Lengths were adjusted as necessary to reflect geological and/or mineralization contacts. Sample sizes were considered to be appropriate for the style of mineralisation. Samples were delivered by Sayona personnel to SGS Canada Inc. laboratories, for sample preparation and primary analysis. Coarse rejects were returned to the mine site for storage and reference.
2023	A total of 24,318 core samples were collected from 172 drillholes. Protocols for core cutting and sampling were consistent with the 2022 program. Samples were delivered to ALS Canada for preparation and analysis using the ME-MS89L analytical method define as the Lowest Detection limit (DL) Multi-Element Super Trace method utilizing Sodium peroxide fusion (Na2O2) and HCl leach digest on 0.2 g aliquot.
2024	A total of 33,399 core samples were collected from 153 drillholes. Protocols for core cutting and sampling were consistent with the 2022 program. ALS Canada continued to provide the analytical services. Same analytical method as 2023.

11.2 Analytical Laboratory Procedures

11.2.1 Canada Lithium Corp. (2009 – 2011)

In 2009, the core samples were prepared and analysed either in Lakefield or in Toronto, Ontario, SGS Canada Inc. laboratories using a sodium peroxide fusion with atomic absorption spectrometry, method 9‐8‐40, to determine the %Li content. Check samples were prepared for selected samples from a split from the remaining pulps after primary analysis. The samples were packaged by SGS Canada Inc. Lakefield and sent by couriers to the ALS Vancouver laboratory.

In 2010 and 2011, The primary laboratory was ALS and the check laboratory was AGAT Laboratories Ltd. Samples were prepared at ALS Val d’Or and assayed in Vancouver using four‐acid digestion with ICP‐AES finish, method Li‐OG63, to determine the %Li content.

11.2.2 North American Lithium Corp. (2016 – 2019)

In 2016, the primary laboratory was Techni‐Lab. The samples were prepared and assayed using a four‐acid digestion with ICP‐AES finish, method ICP‐OES, to determine the %Li content. The check laboratory for 2016 was ALS Vancouver.

In 2019, a mobile SGS Canada Inc. lab was set‐up directly on site. The sample were prepared and assayed by SGS Canada Inc. to determine the %Li content of the core samples.

For personal use only

11.2.3 Sayona (2022 – 2024)

In 2022, SGS Canada Inc. was responsible for analysing the samples collected by Sayona. Preparation of samples was performed at the Lakefield site, Ontario. Samples were sent to Burnaby site, British Columbia for assaying.

Samples were analysed using a four-acid digestion with ICP-AES finish, Na_2O_2 Fusion and HNO_3 to determine %Li and Fe% content of the pulverized core samples. Coarse rejects and pulps were returned to the NAL mine site for storage and reference.

Sample density measurements were also performed at SGS Canada Inc. laboratories. Specific gravity measurements were determined by the water immersion method. Samples were weighed in air and then placed in a basket suspended in water and weighed again. The samples were not waxed or sealed; however, the natural voids were not considered to be a significant issue with respect to density determination.

In 2023 and 2024, ALS performed the analytical for the Exploration and delineation drill program. The method used was ME-MS89L Super Trace Multi-Element Analysis by Sodium Peroxide Fusion and ICP-MS. A prepared sub-sample (0.2 g) is added to sodium peroxide flux, mixed well and then fused at 670 °C. The resulting melt is cooled and then dissolved in 30% hydrochloric acid. The resulting solution is analysed by a combination of inductively coupled plasma-atomic emission spectrometry (ICP-AES) and inductively coupled plasma-mass spectrometry (“ICP-MS”), with results corrected for spectral or isotopic interference.

11.3 QA/QC (Analytical) Procedures

11.3.1 Canada Lithium Corp. (2009 – 2011)

Standards and blanks were reported to have been inserted into the sample sequence prior to shipping. Documentation of specific QA / QC procedures was not available for review here.

11.3.2 North American Lithium Corp. (2016 – 2019)

In 2016, the quality of the analysis was monitored using blanks (one for approximately every 20 samples), and standards (one for approximately every 20 samples). Site technical personnel created customised lithium standards, i.e. low-grade (ST - L) and high-grade (ST), by the dilution of spodumene concentrate from the Tanco pegmatite mine in Manitoba with pulverised quartz. The spodumene concentrate was sent to Geoscience Laboratories for dilution, pulverisation to < 200 mesh and homogenisation. Additionally, several pulps were sent to a secondary laboratory as a check.

In 2016, three standards were created using pulps from the 2013 and 2014 production drillholes.

In 2016, BBA further investigated NAL’s QA/QC protocol and data produced. Sterile material labelled as “blank” was inserted in the sample stream to control contamination and sample handling errors. Customised reference materials labelled as standards A, B and C, representing low grade (0.336% Li_2O), average cutoff grade (0.878% Li_2O) and high grade (1.567% Li_2O) material, respectively were also inserted into the sample stream. Each sample batch included insertion of one blank sample and insertion of three standard samples (A, B and C). Total QA/QC sample inserts accounted for 5 to 10% of the total material submitted.

For personal use only

11.3.3 Sayona (2022)

In 2022, a total of five low-grade (A), five medium grade (B), five high-grade (C) and five very high-grade (D) standards were submitted during the sampling program as part of the QA/QC procedure. Results are summarized below.

Using the determined standard A low value of 0.488% Li_2O, with an SD of 0.009% Li_2O, all samples were within the tolerance specification. A control chart was not generated, as five samples do not constitute a large enough sample population to accurately chart the statistics.

The determined standard B medium value of 1.03% Li_2O, with an SD of 0.003% Li_2O was used. A control chart was not generated, as five samples do not constitute a large enough sample population to accurately chart the statistics.

The determined standard C high-grade value of 1.52% Li_2O, with a standard deviation of 0.016% Li_2O was used. A control chart was not generated, as five samples do not constitute a large enough sample population to accurately chart the statistics.

The determined standard D very high-grade value of 2.21% Li_2O, with a standard deviation of 0.034% Li_2O was used. A control chart was not generated, as five samples do not constitute a large enough sample population to accurately chart the statistics.

Additionally, a total of twelve blank samples were dispersed throughout the sample stream during the sampling program. All samples returned values at or below detection limit. A control chart was not generated, as five samples do not constitute a large enough sample population to accurately chart the statistics.

11.3.4 Sayona (2023 – 2024)

In 2023 and 2024, four different lithium standard types supplied by Core Lithium's Finnis Lithium Project, located in the Northern Territory in Australia, were used during the drilling campaigns.

Certified reference material ("CRM") was produced by Ore Research & Exploration Pty. Ltd. ("OREAS"), a globally recognized supplier of CRM for mining and geochemistry. The selected OREAS lithium certified reference materials offered a systematic progression in lithium grades to support Sayona's quality assurance and quality control programs. OREAS 750 is certified at 0.496 % Li_2O (low grade), OREAS 751 at 1.01 % Li_2O (low to medium grade), OREAS 752 at 1.52 % Li_2O (medium grade), and OREAS 753 at 2.19 % Li_2O (high grade). This series was specifically designed to bracket the range of lithium concentrations typically reported at NAL, thereby ensuring robust method validation and quality control across a spectrum of ore grades.

QA/QC procedures also involved inserting sterile material, labelled as "blank," into the sample stream to monitor contamination and handling errors. A total of 1100 blank samples were inserted in 2023, and a total of 2025 blank samples were inserted during the 2024 drilling program.

11.4 Qualified Person's Opinion

In the Qualified Person's opinion, the methods used for sample preparation and analysis provide sufficiently reliable results for use in the Project database and Mineral Resource estimate.

For personal use only

12 Data Verification

This section describes the data verification process for NAL Property.

12.1 Previous Audits and Reviews

In 2009, data for drill holes completed in that year was audited by Ms. Stone, P.Geo. CCIC. The audit included review of assay certificates, down hole deviation, hard copy records of the down hole survey results, logging codes for pegmatites and checks for data logged, sampled or measured. The 2009 drill hole database was considered to be acceptable for use in resource estimation.

In 2011, Roscoe, Postle and Associates completed an independent review of the Mineral Resource estimate. AMC subsequently completed an independent Mineral Resource estimate in compliance with NI 43 ‑ 101 guidelines. Upon completion of infill drilling in 2011, AMC completed validation work leading to an updated Mineral Resource estimate.

In 2016, SGS Canada Inc. audited the drilling data collected in that year.

In 2016, InnovExplo performed a due diligence review of NAL drilling, core handling, sampling and QA/QC protocols.

In 2016, BBA further investigated NAL's QA/QC protocol and data produced.

In 2021, BBA audited the drilling data and the geological model completed by NAL in 2019.

In 2022, BBA as previous QPs completed a site visit to NAL mine. The site visit included a field tour of the main geological features visible in the current open pit, a tour of the core storage facility, visual inspections of drill cores and discussions with geologists and engineers of Sayona. Selected drillhole collars in the field were also validated. The site visit also included a review of the sampling and assay procedures, QA/QC program, downhole survey methodologies, and the descriptions of lithologies, alteration and structures.

12.2 Site Visits

Optimal Mining's QP visited the Project and its existing installations between September 10th and 12th, 2024 inclusive. The 2024 site visit included a field tour of the current operating open pit's Phase 1 operations, Phase 2 operations and Phase 3 operations (Figure 12-1 to Figure 12-3). Extensive discussions were held with management, geologists and engineers of Sayona Québec during the site visit.

A site visit was also completed on May 27th, 2025, by other consultants engaged in the preparation of the Mineral Resource estimate.

The site visit included a field tour of the main geological features visible in the current open pit (Figure 12-1), a tour of the core storage facility (Figure 12-2), visual inspections of drill cores (Figure 12-3), and discussions with on-site geologists and engineers of Elevra Québec.

Selected drillhole collars in the field were also validated. The site visit also included a review of the sampling and assay procedures, QA/QC program, downhole survey methodologies, and the descriptions of lithologies, alteration and structures (Figure 12-3).

For personal use only

12.2.1 Field Collar Validation

Some drill collars were surveyed by a Garmin Rino 755t handheld global positioning system (GPS) unit. These collar readings compared to the recorded collar locations in the Project database; deviations between these two readings were within the expected resolution of the handheld units.

12.2.2 Drilling and Sampling Procedure Validation

Drill core inspection and discussions were completed with on-site geologists to confirm that drilling and sampling procedures were generally well applied.

Several sections of mineralized core were reviewed while visiting the Project. All core boxes were labelled and properly stored outside. Sample tags were present in the boxes. It was possible to validate sample numbers, confirm the presence of mineralization in core trays and witness half-core samples from the mineralized zones (Figure 12-3).

Drilling was not underway during the site visit; it was however possible to follow the entire path of drill core from drill rig to logging and sampling to the laboratory to Project database by reviewing historical reports.



Figure 12-1: View of the Open Pit Visited During the Site Tour

For personal use only



Figure 12-2: Core Storage Facility at the Project Site

For personal use only




Figure 12-3: Core Review at the Core Storage Facility

For personal use only

12.2.3 Log and Core Box Validation

During the site visit, visual inspections of drill core were completed for four discrete geological intervals in drillholes completed during the 2024 drilling campaign (Table 12-1). Core boxes were withdrawn from the core rack and laid on the ground to review the selected intervals.

Table 12-1: Geological Intervals Inspected During Site Visit

BHID	Depth (m)	
	From	To
LAN-24-170	297	337
LAN-24-179	29	50
LAN-24-262	265	306
LAN-24-270a	302	343

12.2.4 Validation Of Sample Preparation, Analytical, QA/QC and Security Procedures

Discussions were held with on-site personnel to confirm that the sample preparation, analytical, QA / QC and sample security procedures are adequately applied.

A visual inspection of several sections of core boxes confirmed that all core boxes were labelled and properly stored. Sample tags were present in the boxes, and it was possible to validate sample numbers and visually confirm the presence of spodumene mineralization in the remaining half-core.

12.3 Database Validation

All sampling and assay information are stored in a secure GeoticLog database located on the Sayona Québec server at the NAL site and containing restricted access. The server is backed up daily, and backups are stored in a different building at the NAL site. Assay results from the laboratory with corresponding sample identification are loaded directly into the GeoticLog database.

The digital drill hole database was audited by personnel engaged in the preparation of the Mineral Resource estimate using validation tools for: collar location, azimuth, dip, hole length, survey data and analytical values. There were no relevant errors or discrepancies noted during the validation.

A representative number of assays contained in the Project database were validated against the laboratory certificates. No discrepancies were noted.

12.4 Qualified Person's Opinion

It is the QP's opinion that the drilling, sampling and assaying protocols in place are adequate. The Project database provided by Elevra is of acceptable quality and is suitable for use in the Mineral Resource estimate.

For personal use only

For personal use only

13 Mineral Processing and Metallurgical Testing

This chapter summarizes testwork results, plant operating data, and other relevant information that has led to the identification of process improvement opportunities and form the basis for process design for the NAL spodumene concentrator. Information contained in this chapter was previously published by Sayona in a NI 43-101 Technical Report titled “Definitive Feasibility Study Report for the North American Lithium Project”, dated April 14th, 2023.

In recent history, the NAL concentrator operated from March 2013 to September 2014 (Québec Lithium Inc.), and June 2017 to March 2019 (North American Lithium Inc.). The concentrator was restarted in March 2023 (Sayona Quebec Inc.) and is currently operational (Elevra Lithium Limited).

Extensive metallurgical testwork has been undertaken on ore from the NAL deposit since 2008 including:

- 2008 – A development program involving grindability tests, DMS separation, flotation, locked cycle tests and pilot scale testwork.
- 2011 – Ore Sorting.
- 2014 – WHIMS.
- 2016 – Restart Testwork involving hardness characterisation, WHIMS testwork and flotation tests.
- A comprehensive program was undertaken in between 2019 and 2022 looking at the metallurgical performance and characteristics of blends of NAL and Authier material.

Extensive metallurgical testwork has also been undertaken for the Authier Project including historical testwork since 1969 and has focused on flotation including historical testwork in 1969, 1991, 1997, 1999 and 2012. More recent modern testwork commenced in 2018 by Sayona Quebec involved hardness characterisation, bench and pilot scale flotation.

Operational data was also reviewed as part of the Mineral Reserves PFS to inform mass balances, recoveries and forward works program.

13.1 North American Lithium – Historical Process Plant Operations

13.1.1 Québec Lithium Concentrator Operations (2013 – 2014)

The Québec Lithium Project operated from March 2013 until September 2014. The concentrator never reached nameplate capacity and was unable to produce chemical grade spodumene concentrate. The major issue encountered during operation was higher than expected dilution from the mine. The waste rock contained iron-bearing silicate minerals that could not be adequately rejected in the concentrator flowsheet. The result was the production of low-grade spodumene concentrate (ca. 3% to 4% Li_2O) with high iron concentrations (ca. 2% to 3% Fe).

Process plant design was based on testwork operated on samples with little to no dilution. During operation, typical levels of dilution in run of mine (ROM) ore were roughly 20%.

Major process plant deficiencies that limited throughput and concentrate quality included:

- Higher than anticipated dilution in ROM ore.
- Design flaws in the crushing circuit (e.g., materials handling issues, material freezing, inadequate dust collection).
- Limited buffer capacity in the crushed ore silo.

- Inadequate iron-bearing mineral rejection in the flowsheet.
- Inadequate high-intensity conditioning ahead of flotation.

13.1.2 North American Lithium Concentrator Operations (2017 – 2019)

Prior to NAL concentrator restart in 2017, several plant upgrades were implemented including:

- Installation of a secondary optical near-infrared (NIR) ore sorter.
- Modifications to the crushed ore silo.
- Installation of a wet high-intensity magnetic separator (WHIMS) ahead of the flotation circuit.
- Modifications to the high-intensity conditioning tank.

The NAL concentrator operated from June 2017 until March 2019. The concentrator never reached nameplate capacity and typically produced spodumene concentrate ranging in grade from 5.5% to 6.0% Li_2O.

Figure 13-1 shows monthly spodumene concentrate production. During 2018 and 2019, monthly production ranged from roughly 4,500 t to 13,250 t. At the time, nameplate capacity was roughly 15,900 t of 5.8% Li_2O concentrate.




Figure 13-1: Monthly Spodumene Concentrate Production

Figure 13-2 shows monthly averages of spodumene concentrate lithia (Li_2O) and iron grades and lithium recovery. After initial plant start-up in 2017, concentrate grades ranged from 5.4% to 6.0% Li_2O and from 0.9% to 1.6% Fe. Lithium recovery ranged from roughly 55% to 70% for the same period.

For personal use only




Figure 13-2: Concentrate Grade and Lithium Recovery (Monthly Averages)

Several plant improvement projects were identified which would be required to reach plant nameplate capacity and ensure production of chemical grade spodumene concentrate:

- Modifications to the primary crusher dump hopper and feeder.
- Improvements in the crushing circuit (e.g., materials handling, dust collection).
- Increased crushed ore buffer capacity.
- Installation of a third ore sorter (in parallel to the existing secondary sorter); Increased screening capacity in the ball mill circuit.
- Improved magnetic separation (installation of a LIMS and a second WHIMS).
- Installation of a new high-intensity conditioning tank ahead of flotation.
- Increase spodumene concentrate filter capacity.

13.1.3 Sayona Quebec Concentrator Operations (2023 – Present)

Concentrator operations restarted in March 2023 and is processing lithium-bearing pegmatite ore from the NAL mine. The concentrator underwent a period of commissioning and then ramp up following start-up. For Q3 2025, the concentrator operated with a higher-grade feed of 1.2 to 1.4% Li_2O, to produce a lithium concentrate of 5.1 to 5.2% Li_2O and at a lithium recovery of 72%. Year to date concentrate was 5.2% Li_2O at a Li recovery of 70.8%

Recent testwork has been focused on the metallurgical behaviour of an Authier and NAL blended feed samples, determine the impact of granodiorite, gabbro, and volcanics waste rock dilution on metallurgical performance and mimic the NAL flowsheet on the proposed blends.

For personal use only

For personal use only

13.2 North American Lithium Testwork Program

13.2.1 North American Lithium Testwork Review Summary

A large number of metallurgical studies have been undertaken on samples from the NAL deposit since 2008. In 2008, SGS Canada Inc., in Lakefield, Ontario operated a development testwork program which included a flotation pilot plant. Variability testwork was undertaken to evaluate the impact of head grades on performance. The testwork was used to produce engineering data for plant design and produce marketing samples.

Two composite samples were used for a series of grindability tests. Dense media separation (DMS) and batch flotation tests were undertaken. During the initial feasibility study, further batch-scale optimization tests were carried out as well as locked-cycle flotation tests and pilot-scale tests. Testwork results are documented in the NI 43-101 Prefeasibility Technical Report (Hardie, et al., 2011) and the updated Feasibility Technical Report (Blanchet, et al., 2011) . The process flowsheet was developed based on projected recoveries that were determined from the testwork program and a plant throughput of 3,800 tpd (rod mill feed).

It should be noted that all tests carried out during the previous prefeasibility and feasibility studies were conducted on relatively clean pegmatite ore with little ore dilution. There were indications in early testing that ore dilution may negatively impact flotation performance; however, the extent of ore dilution was not well defined, and its impact was not thoroughly tested. The use of optical ore sorting to remove waste material in the crushing circuit was investigated during the feasibility study but was not tested and was not included in the final feasibility study flowsheet.

Optical ore sorting was tested during detailed engineering, and an optical ore sorter was installed after plant start-up to sort +3” material after primary crushing and screening. The ore sorter did not operate in the winter months and only operated for a short period before the plant was put on care and maintenance in 2014. A second ore sorter was installed prior to plant restart in 2017.

WHIMS tests were carried out on the final flotation concentrate during prefeasibility and feasibility study testwork. WHIMS was performed to lower iron content of the final concentrate to meet concentrate specifications. During testing, relatively clean pegmatite ore (low levels of dilution) was tested. As such, iron was present in the spodumene crystal structure and WHIMS was not effective. As a result, WHIMS was not included in the original flowsheet.

The NAL pegmatite dykes are hosted in two host rock types: granodiorite or volcanics. The two host rock types have differences in terms of mineralogy, specifically related to presence of iron-bearing silicate minerals. Table 13-1 and Table 13-2 show examples host rock mineralogy and elemental composition from testwork undertaken in 2022.

Table 13-1: Example Mineralogy of NAL Host Rock Types

Mineral	Granodiorite (Wt %)	Volcanics (Wt %)
Albite	50.8	23.8
Magnesio-hornblende	11.4	53.2
Quartz	14.4	1.0
Microcline	9.6	0.9
Chlorite	1.6	2.6
Muscovite	3.4	4.5
Holmquistite	4.3	5.6
Biotite	2.7	1.7
Diopside	1.7	6.2
Rutile	0.1	0.5
Total	100	100

Table 13-2: Example Assays of NAL Host Rock Types

Component	Granodiorite (Wt %)	Volcanics (Wt %)
Li	0.1	0.1
Li_2O	0.2	0.2
Al	8.7	5.8
Ca	3.3	7.3
Fe	2.9	9.7
Na	3.4	1.9
K	2.0	0.6
Mg	1.4	4.9
Mn	1.4	0.2
Si	29.7	23.7

The analyses show magnesio-hornblende concentrations to be significantly higher in the basalt sample (53.2%) as compared to the granodiorite sample (11.4%). Iron concentration in the volcanics sample was 9.72% as compared to 2.87% in the granodiorite sample.

Two process plant upgrades have been executed to reject iron-bearing silicate minerals in the flowsheet. The first is the installation of a third ore sorter in the crushing circuit to reject host rock dilution. Work is ongoing to improve the efficacy of the ore sorting system. The second is the installation of a second WHIMS in the flowsheet to further reject iron-bearing silicate minerals prior to flotation. A LIMS was also installed ahead of the WHIMS units to remove abraded steel from the mills, which has a negative impact on WHIMS performance. The metallurgical testing focused on controlling iron in the flowsheet using WHIMS and the effect of the quantity and type of host rock dilution.

13.2.2 Optical Ore Sorting Testwork (2011)

In 2011, during detailed engineering, optical sorting tests were undertaken at the TOMRA (previously Commodas Ultrasort GmbH) test facility in Wedel, Germany, using commercial-scale optical sorting units. The material provided for the test program was a mixture of pegmatite, granodiorite, and basalt. Figure 13-3 shows example images of the three rock types tested.

The material provided was screened into four size fractions: -60 mm / + 40 mm, -40 mm / +20 mm, -20 mm / +12 mm, and -12 mm / +8 mm. Each size fraction was tested with 20% and 40% waste of either granodiorite or basalt and was tested with a range of sorting parameters. The sorting parameters can be set to minimize loss of lithium or maximize rejection of waste. These tests demonstrated waste rejection rates as high as 95% with corresponding lithium loss of 6% or less. Example images of sorted products from the testwork are shown in Figure 13-4.

For personal use only

For personal use only




Figure 13-3: Ore Sorting Test Program Material (Pegmatite Upper Left, Granodiorite Upper Right, Basalt Lower)



Figure 13-4: Example Images of Sorted Products

13.2.3 WHIMS Testwork (2014)

Initially, WHIMS testing was carried out at the process plant using lab scale equipment (Eriez model L-20 WHIMS). Tests were carried out on the de-sliming cyclone underflow feeding the flotation circuit and on the spodumene concentrate product. The objective was to remove amphiboles (hornblende) either from the flotation feed or the concentrate. Figure 13-5 shows the magnetic and non-magnetic fractions when the WHIMS unit was operated at 8,000 gauss (G) on the de-sliming cyclone underflow.




Figure 13-5: Magnetic and Non-Magnetic Fractions from Test Conducted at 8,000 Gauss

The tests were also run on a range of magnetic intensities. Visually, the best results on the cyclone underflow appeared to be at about 12,000 G. Vendor testing was subsequently undertaken. A WHIMS (Eriez WHIMS SSS-I-3000 1.0-1.3 T) was installed in the NAL process plant in 2016-17. The WHIMS is located ahead of spodumene conditioning in the flowsheet.

13.2.4 NAL Re-Start Metallurgical Testing (2016)

In 2016, a testwork program was undertaken at SGS Canada Inc. in Lakefield, Ontario. The program included:

- Hardness characterization of pegmatite, granodiorite, basalt, and composite samples.
- WHIMS testing on pegmatite samples with varying levels of dilution containing granodiorite or basalt host rock.
- Flotation tests on samples processed through the WHIMS unit.

The results of the grindability tests showed that the Bond work indices of the sample mixtures and in-situ samples were all below the work indices used in the 2012 design criteria for sizing of the rod and ball mills. Therefore, the presence of mine dilution should not negatively impact the mill throughput capacity.

For the WHIMS testing, the magnetic intensity was varied between 5,000 G and 15,000 G for various mixtures of pegmatite ore with granodiorite or basalt. Results indicated that the ideal magnetic intensity to reject iron, while minimizing lithium loss, was in the range of 10,000 G to 13,000 G.

Figure 13-6 shows iron rejection and lithium loss to the magnetic concentrate at various magnetic intensities for an ore sample containing 10% granodiorite (left) and 10% basalt (right). Related to the host rock composition and mineralogy, magnetic separation performance is quite different in the two samples. At 12,000 G, both samples show roughly 4.8% lithium loss with the granodiorite sample showing 47% iron rejection and the basalt sample showing 80% rejection. The feed grades of the granodiorite and basalt samples were 1.16% Li_2O and 0.95% Fe_2O_3, and 1.20% Li_2O and 1.74% Fe_2O_3, respectively.

For personal use only




Figure 13-6: Iron Rejection and Li Loss to Magnetic Concentrate for Pegmatite with 10% Granodiorite (Left) and 10% Basalt (Right)

Batch flotation tests were undertaken on the non-magnetic fractions after magnetic separation at 15,000 G. Figure 13-7 shows the grade-recovery curves for the optimized conditions for test F3 (pegmatite with 10% basalt) and test F4 (pegmatite with 10% granodiorite). Spodumene flotation was operated at pH 8.5 using 675 g/t of FA-2 collector with a rougher-scavenger and three stages of cleaning. The final spodumene concentrates assayed between 1.05% and 1.10% Fe_2O_3. Lithium recovery at 6% Li_2O ranged from roughly 80% to 83% (interpolated).




Figure 13-7: Optimized Flotation Test Results

For personal use only

For personal use only

13.3 Blended Ore (NAL and Authier) Testwork Program

13.3.1 Preliminary Testwork (2019)

Initial testwork on blended NAL and Authier samples was undertaken in 2019 at SGS Canada Inc. in Lakefield, Ontario. The Authier sample tested was material from the 2018 pilot plant and was a blend of Composite 1 and Composite 2 material. The NAL samples (pegmatite, granodiorite and volcanics) were hand-picked from ROM stockpiles located at the NAL site in November 2019.

The blend ratio tested in the 2019 Preliminary Testwork was 75% NAL ore and 25% Authier ore. Based on historical data, dilution in the NAL mine plan was expected to be roughly 18%. By contrast, and due to the nature of the deposit and the mining strategy, the Authier mine plan was expected to include less than 5% dilution in ROM ore.

Assays of the various feed samples are shown in Table 13-3. The Authier pegmatite sample had a grade of 1.05% Li_2O. The NAL pegmatite sample was high-grade at 1.57% Li_2O. The NAL granodiorite (4.1% Fe_2O_3) and the volcanics samples (13.1% Fe_2O_3) had relatively high iron content as compared to the pegmatite samples (0.82% and 0.49%, respectively). Table 13-4 shows the composition of the feed blends tested.

Table 13-3: Assays of Ore Samples Tested

Analysis	Authier	NAL		
	Composite	Pegmatite	Granodiorite	Volcanics
Li	0.49	0.73	0.14	0.09
Li_2O	1.05	1.57	0.30	0.19
SiO_2	73.50	74.00	62.70	48.90
Al_2O_3	15.60	15.70	16.70	8.95
Fe_2O_3	0.82	0.49	4.10	13.10
MgO	0.26	0.02	2.30	11.80
CaO	0.21	0.24	4.59	10.50
Na_2O	4.75	3.39	4.48	1.46
K_2O	2.80	2.33	2.24	1.23

Table 13-4: Overview of Feed Samples Tested

Analysis	Authier	NAL		
	Composite	Pegmatite	Granodiorite	Volcanics
	Composition %			
F3	25	67.5	-	7.5
F4	25	67.5	7.5	-
F5	-	100.0	-	-
F6	25	75.0	-	-

Test procedures included: crushing, grinding, de-sliming, WHIMS and spodumene flotation. Reagent dosages were chosen based on historical testwork and NAL operating experience.

Figure 13-8 shows the grade-recovery curves for the four tests. Figure 13-9 shows the relationship between $Fe_2O_3$and Li_2O concentrations in the concentrates.

For personal use only




Figure 13-8: Grade – Recovery Curves




Figure 13-9: Fe_2O_3 vs. Li_2O in the Concentrate

For personal use only

For test F3, the concentrate produced from the blended sample containing basalt was unable to achieve 6% Li_2O (5.87% Li_2O at 80% recovery). The final concentrate also contained a relatively high level of iron (1.96% Fe_2O_3).

Results for test F4 showed that the concentrate produced from the blended sample containing granodiorite achieved 6% Li_2O at 85% recovery. Iron levels in the final concentrate were slightly high at 1.33% Fe_2O_3.

Test F5 on NAL pegmatite (no dilution) performed well, achieving 6% Li_2O at roughly 90% recovery. Iron in the 6% Li_2O concentrate was roughly 1.2% Fe_2O_3.

Test F6 on a blend of Authier and NAL pegmatite (no dilution) performed well, achieving 6% Li_2O at roughly 90% recovery. Iron in the 6% Li_2O concentrate was roughly 1.2% Fe_2O_3.

The pegmatite sample tested from NAL was relatively high-grade compared to the expected life-of-mine average. All samples tested produced concentrate with Fe_2O_3 concentrations exceeding 1%. The sample tested containing basalt produced a concentrate of 5.87% Li_2O (slightly below 6%), which contained a relatively high concentration of iron (1.96% Fe_2O_3). The results are shown in Table 13-5.

Table 13-5: Final Spodumene Concentrate Grade (3-Stages of Cleaning)

Test	Li_2O	Fe_2O_3
F3	5.87	1.96
F4	6.05	1.33
F5	6.54	1.29
F6	6.24	1.18

13.3.2 Prefeasibility Study Testwork (2021 – 2022)

Testwork on blended NAL and Authier ore was undertaken in 2021-22 at SGS Canada Inc. in Lakefield, Ontario. Both samples were selected from drill core. The objectives of the testwork were:

- Test a blended feed sample of 64% NAL and 36% Authier (Compared to 75% NAL and 25% Authier blend from 2019 Preliminary Testwork).
- Test the impact of basalt waste rock dilution on performance.
- Examine the impact of two-stages of WHIMS on concentrate quality.

Pegmatite and host rock samples were analysed separately. Table 13-6 and Table 13-7 show assays and mineralogy of the components.

Table 13-6: Assays of the Pegmatite and Host Rock Samples

Component	NAL			Authier	
	Pegmatite	Basalt	Granodiorite	Pegmatite	Basalt
	Composition, Wt %				
Li	0.67	0.08	0.11	0.68	0.10
Li_2O	1.44	0.17	0.24	1.46	0.22
Al	8.42	5.77	8.73	8.42	9.21
Ca	0.23	7.29	3.32	0.12	3.51
Fe	0.15	9.72	2.87	0.26	7.76
Na	3.32	1.92	3.41	3.23	3.30
K	2.16	0.62	2.00	2.40	0.59
Mg	0.02	4.94	1.39	0.04	5.62
Mn	0.10	0.16	0.05	0.09	0.22
Si	34.20	23.70	29.70	34.50	22.20

For personal use only

Table 13-7: Mineralogy of the Pegmatite and Host Rock Samples

Component	NAL			Authier	
	Pegmatite	Basalt	Granodiorite	Pegmatite	Basalt
	Composition, Wt %				
Albite	39.50	23.80	50.80	37.40	40.00
Magnesio-hornblende	-	53.20	11.40	-	36.80
Quartz	25.10	1.00	14.40	26.70	-
Microcline	12.40	0.90	9.60	11.50	-
Chlorite	-	2.60	1.60	-	15.90
Muscovite	3.00	4.50	3.40	4.50	4.10
Holmquistite	-	5.60	4.30	-	-
Biotite	0.80	1.70	2.70	0.90	0.90
Diopside	-	6.20	1.70	-	0.40
Rutile	-	0.50	0.10	-	0.30
Calcite	0.50	-	-	0.50	-
Beryl	0.20	-	-	0.20	-
Total	100	100	100	100	100

Based on previous studies and NAL operational data, the NAL testwork feed sample comprised 10% basalt dilution (to simulate feed to the mill after ore sorting). The feed samples were blended at a ratio of 64% NAL ore and 36% Authier ore (to simulate rod mill feed). Table 10-8 shows the assays of the blended ore sample. The feed grade of the blended sample was 1.14% Li_2O and 1.56% Fe_2O_3.

Table 13-8: Blended Ore Assays

Component	NAL/Authier Blend
	Composition
Li	0.53
Li_2O	1.14
Al2O3	15.40
CaO	0.98
Fe_2O_3	1.56
Na2O	4.40
K2O	2.51
MgO	0.73
MnO	0.15
SiO2	72.50

The samples were stage-crushed and stage-ground to a target P80 of 200 µm. The samples were scrubbed and de-slimed, underwent WHIMS, de-slimed and conditioned prior to spodumene rougher and scavenger flotation followed by three stages of cleaning. The testwork was designed to mimic the NAL flowsheet. Table 13-9 shows reagent dosages for the optimized tests. For the optimized tests, FA-2 fatty acid collector dosage ranged from 780 g/t to 1,080 g/t.

Table 13-9: Reagent Dosages for Optimized Tests

Test	P100 (µm)	Dosage (g/t)				
		Na2CO3	NaOH	F100	F220	FA-2
F6	300	225	75	250	-	780
F9	300	225	75	250	-	1,080
F16	300	201	75	-	250	780

Figure 13-10 shows the grade-recovery curves for the three optimized tests. Final spodumene concentrate grades in the three tests were roughly 6% Li_2O. Lithium recovery ranged from 60% to 66%.




Figure 13-10: Grade – Recovery Curves

Table 13-10 shows the final concentrate grades which ranged from 6.01% to 6.05% Li_2O and 0.78% to 1.05% Fe_2O_3.

Table 13-10: Final Spodumene Concentrate Assays

Test	Li2O %	Fe2O3 %
F6	6.01	1.05
F9	6.01	0.98
F16	6.05	0.78

Figure 13-11 compares the performance of the WHIMS when processing ore containing basalt versus granodiorite host rock (10% dilution in all tests shown). The data points are taken from several testwork programs on NAL ore and blended ore. The results show higher mass pulls, iron rejection and lithium losses for the basalt tests. This is due to the higher concentrations of iron-bearing silicate minerals in the basalt samples.

For personal use only




Figure 13-11: Comparison of WHIMS Performance with Basalt vs. Granodiorite Host Rock

13.3.2.1 Tailings Filtration Tests

In 2022, ten pressure filtration tests were conducted by Pocock Laboratories on combined tailings samples. Two pressure filtration methods were tested:

- Air blowing only.
- Membrane squeeze with air blow.

With respect to Tailings Filtration, the target moisture content that forms the basis of assessment and filter sizing was 15%. During the test program, the effects of cake thickness and drying time on filter cake moisture and the production rate were examined.

The design conditions simulated the filtration of tailings with an average 56% solids feed density. The pressure for all ten air blow procedures was maintained at 552 kPa. However, combined tailings material in four out of ten tests were subjected to an additional pressure of 690 kPa for the initial membrane squeeze procedure, which was raised to 1,600 kPa for the final 30 seconds of air blow. The test results and the simulations yielded the production of a tailings cake with satisfactory discharge as well as stacking properties reaching their target values in a cycle time that would require one operating and one stand-by pressure filter configuration, the specifications for which are provided in Chapter 14.

13.3.3 Feasibility Study Testwork Program (2022 – 2023)

Testwork on blended NAL and Authier ore was undertaken in 2022-23 at SGS Canada Inc. in Lakefield, Ontario. Two composite and five variability samples were tested. The main objectives of the testwork were to:

- Test blended feed samples (64% NAL and 36% Authier).
- Test the impact of granodiorite, gabbro, and volcanics waste rock dilution on metallurgical performance.
- Mimic the NAL flowsheet.

13.3.3.1 Composite Samples

The NAL pegmatite sample was collected in 2022 by operations geologists from run-of-mine ore remaining in the pit from previous mining operations in 2019. The material was selected to represent average-grade material. The NAL volcanics and granodiorite samples used were material remaining from the PFS testwork program. The Authier pegmatite sample was taken from a test pit onsite. The Authier host rock (ultramafic) sample was from the PFS testwork program.

For personal use only

For personal use only

Pegmatite and host rock samples were analysed separately. Table 13-11 and Table 13-12 show assays and mineralogy of the components. The NAL and Authier pegmatite samples graded 1.12% and 1.05% Li_2O, respectively. The host rock samples contained low levels of lithium, ranging from 0.17% to 0.24% Li_2O. A major difference between the host rock samples was the varying iron concentrations which ranged from 4.10% to 13.9% Fe_2O_3.

Table 13-11: Composite Sample Assays of the Pegmatite and Host Rock Samples

Component	NAL			Authier	
	Pegmatite	Volcanics	Granodiorite	Pegmatite	Ultramafic
	Composition, Wt %				
Li	0.52	0.08	0.11	0.49	0.10
Li_2O	1.12	0.17	0.24	1.05	0.22
Al_2O_3	15.60	10.90	16.49	15.60	17.40
CaO	0.37	10.20	4.65	0.14	4.91
Fe_2O_3	0.32	13.90	4.10	0.42	11.10
Na_2O	4.57	2.59	4.60	4.42	4.45
K_2O	2.61	0.75	2.41	2.86	0.71
MgO	0.05	8.19	2.31	0.05	9.32
MnO	0.10	0.21	0.06	0.13	0.28
SiO_2	74.30	50.10	63.50	74.40	47.50

The NAL and Authier pegmatite samples contained 14.7% and 12,9% spodumene. The major difference between the host rock types was the varying amounts of magnesio-hornblende which ranged from 11.4% to 53.2%. The volcanics and granodiorite samples contained holmquistite which correlates with the presence of lithium in the samples.

Table 13-12: Mineralogy of the Pegmatite and Host Rock Samples

Component	NAL			Authier	
	Pegmatite	Volcanics	Granodiorite	Pegmatite	Ultramafic
	Composition, Wt %				
Spodumene	14.7	-	-	12.9	-
Albite	38.8	23.8	50.8	38.5	40.0
Magnesio-hornblende	-	53.2	11.4	-	36.8
Quartz	27.9	1.0	14.4	29.3	-
Microcline	15.8	0.9	9.6	15.2	-
Chlorite	-	2.6	1.6	-	15.9
Muscovite	2.2	4.5	3.4	3.6	4.1
Holmquistite	-	5.6	4.3	-	-
Biotite	-	1.7	2.7	-	0.9
Diopside	-	6.2	1.7	-	0.4
Rutile	-	0.5	0.1	-	0.3
Petalite	0.4	-	-	0.5	-
Total	100	100	100	100	100

The samples were blended at a ratio of 64% NAL ore and 36% Authier ore (to simulate rod mill feed composition). Based on previous studies, mine plans, and NAL operational data, the NAL testwork feed samples comprised 9% dilution (medium dilution). The Authier portion of the sample contained 1.7% dilution. Two samples were prepared, one containing volcanics and one containing granodiorite. Table 13-13 shows the assays of the blended composite samples. The feed grade of composite 1 (volcanics) was 1.12% Li_2O and 1.29% Fe_2O_3, and composite 2 (granodiorite) was 1.12% Li_2O and 0.68% Fe_2O_3.

For personal use only

Table 13-13: Blended Feed Assays

Component	Composite 1 (Volcanics) %	Composite 2 (Granodiorite) %
Li	0.5	0.5
Li_2O	1.1	1.1
Al2O3	15.2	15.7
CaO	0.9	0.6
Fe_2O_3	1.3	0.7
Na2O	4.4	4.6
K2O	2.6	2.8
MgO	0.6	0.3
MnO	0.6	0.3
SiO2	72.5	73.4

13.3.3.2 Variability Samples

Five variability samples were selected from NAL drill core samples (quarter core). The samples were selected to represent early years of production (years 1-10) and to include each major type of host rock (i.e., granodiorite, gabbro and volcanics). Table 13-14 gives a brief description of each of the five variability samples. Pegmatite and host rock samples from each drillhole were grouped separately. Pegmatite and host rock sample composites were analysed for chemical composition and mineralogy.

Table 13-14: Variability Sample Description

Variability Sample	Years of Production	Host Rock Type	Hole ID	Dykes
1.0	Years 1-2	Volcanics / Granodiorite	NAL-19-008	B
			NAL-19-008	N
			NAL-19-019	B
			NAL-19-023	B2
2.0	Years 1-2	Granodiorite	NAL-16-005	CT_S-K
			NAL-16-012	CT_S-K
			NAL-16-028	CT_K
			NAL-19-010	B2
3.0	Years 3-5	Volcanics / Granodiorite	NAL-16-035	P
			NAL-16-036	N
			NAL-19-020	B
			NAL-19-026	B
4.0	Years 3-5	Gabbro	NAL-19-011	CT_V2
			NAL-19-031	N2
			NAL-19-034	CT_V2
			NAL-19-036	CT_S-K
5.0	Years 5-10	Gabbro / Granodiorite	NAL-19-021	A
			NAL-19-024	B
			NAL-19-036	CT_V

Table 13-15 shows the chemical composition of the pegmatite and host rock for each variability sample. Pegmatite grades ranged from 0.88% to 1.25% Li_2O and from 0.15% to 0.79% Fe_2O_3. Host rock sample grades ranged from 0.19% to 0.47% Li_2O and from 4.1% to 12.1% Fe_2O_3.

Spodumene content of the pegmatite samples ranged from 10.8% to 15.4%. Muscovite content ranged from 2.0% to 4.5%. Low levels of spodumene are seen in the host rock samples (1.1% to 2.4%). Holmquistite is present in all host rock samples ranging from 2.0% to 6.8%. Large variations in magnesio-hornblende content (3.3% to 63.2%) can be seen in the various host rock types.

Similar to the composite samples, NAL variability testwork feed samples comprised 9% dilution while the Authier portion (composite samples) contained 1.7% dilution. The samples were blended at a ratio of 64% NAL ore and 36% Authier ore (to simulate rod mill feed composition).

For personal use only

Table 13-15: NAL Variability Sample Assays: Pegmatite and Host Rock

Component	Pegmatite Composition, wt%					Host Rock, Composition, wt%				
	Var 1	Var 2	Var 3	Var 4	Var 5	Var 1	Var 2	Var 3	Var 4	Var 5
Li	0.57	0.41	0.57	0.50	0.58	0.14	0.10	0.22	0.09	0.15
Li_2O	1.23	0.88	1.23	1.08	1.25	0.30	0.21	0.47	0.19	0.32
Al_2O_3	15.50	15.80	15.70	14.90	15.30	15.30	16.40	14.00	8.80	8.90
CaO	0.38	0.86	0.48	0.39	0.36	8.40	4.41	7.67	12.10	11.80
Fe_2O_3	0.15	0.79	0.28	0.26	0.23	8.24	4.11	9.70	11.90	11.20
Na_2O	4.79	4.85	4.79	4.50	4.38	2.54	4.45	2.99	1.51	1.62
K_2O	1.95	2.70	2.22	2.49	2.45	1.07	2.36	1.44	0.72	0.65
MgO	0.04	0.40	0.12	0.11	0.10	5.49	2.32	6.50	9.89	9.69
MnO	0.15	0.10	0.16	0.16	0.16	0.17	0.08	0.17	0.20	0.19
SiO_2	74.90	72.60	73.40	75.60	75.40	55.50	62.70	53.90	52.10	52.70

Table 13-16: NAL Variability Sample Mineralogy: Pegmatite and Host Rock

Mineral	Pegmatite Composition, wt %					Host Rock, Composition, wt%				
	Var 1	Var 2	Var 3	Var 4	Var 5	Var 1	Var 2	Var 3	Var 4	Var 5
Spodumene	14.7	10.8	15.4	13.5	14.9	2.1	1.1	2.4	1.3	2.4
Quartz	29.3	24.1	27.6	30.4	30.3	10.0	13.4	4.5	5.2	6.1
Plagioclase	42.3	45.7	43.3	40.8	39.2	36.5	47.7	36.6	14.1	19.8
Magnesio-hornblende	-	0.8	-	-	-	24.5	3.3	26.3	63.2	47.3
K-feldspar	10.4	11.9	10.4	13.1	13.1	1.5	10.5	2.4	1.8	2.0
Phlogopite	-	-	-	-	-	7.5	6.6	9.1	3.4	3.5
Epidote	-	-	-	-	-	4.9	4.7	4.8	3.3	5.9
Holmquistite	-	0.7	-	-	-	3.8	3.9	6.8	2.0	4.5
Muscovite	2.0	4.5	3.3	2.2	2.4	-	-	-	-	-
Diopside	-	-	-	-	-	4.2	2.9	2.5	2.7	3.3
Clinochlore	-	1.3	-	-	-	1.7	3.0	1.9	0.8	1.3
Schorl	1.3	-	-	-	-	1.9	1.9	0.9	1.0	1.3
Other	-	0.2	-	-	-	1.0	0.4	1.0	1.0	1.9
Total	100	100	100	100	100	100	100	100	100	100

Table 13-17: NAL Blended Variability Sample Assays

Component	Composition				
	Var 1	Var 2	Var 3	Var 4	Var 5
Li	0.52	0.46	0.52	0.48	0.53
Li_2O	1.12	0.99	1.12	1.03	1.14
Al_2O_3	15.60	15.70	15.60	14.00	15.60
CaO	0.81	0.84	0.83	0.97	0.68
Fe_2O_3	0.81	0.93	1.05	1.13	0.95
Na_2O	4.51	4.67	4.56	4.32	4.54
K_2O	2.20	2.73	2.39	2.41	2.67
MgO	0.43	0.46	0.52	0.65	0.36
MnO	0.15	0.10	0.15	0.15	0.16
SiO_2	73.70	72.20	72.30	69.60	73.40

13.3.3.3 Composite Sample Testwork Results

The composite samples were stage-crushed and stage-ground to P100 values between 212 µm and 300 µm. The samples were scrubbed and de-slimed, underwent two stages of magnetic separation (WHIMS), de-slimed and conditioned prior to batch spodumene rougher and scavenger flotation followed by three stages of cleaning. The batch tests were designed to mimic the NAL flowsheet with recent 2023 circuit modifications.

Initial testwork examined the impact of grind size on flotation performance. Samples were stage-ground and screened. Tests were operated on each composite at -300 µm (tests F2 and F5) and -250 µm (tests F7 and F8) as shown in Figure 13-12. The finer grind (-250 µm) showed improved performance. Based on the results, all further testing was undertaken at a grind size of -250 µm. Tests were operated with a 250 g/t dosage of F220 dispersant and total dosage of FA-2 collector of 780 g/t.




Figure 13-12: Composite Samples – Effect of Grind Size

Tests were undertaken to examine the effect of collector dosage of flotation performance. Figure 13-13 shows an example for composite 1. Tests were undertaken using 680 g/t, 780 g/t and 980 g/t of FA-2 collector. There was a slight improvement in performance at the highest collector dosage.

For personal use only

For personal use only




Figure 13-13: Effect of Collector (FA-2) Dosage on Flotation Performance

Tests were undertaken to examine the impact of host rock dilution on flotation performance. The amount of NAL volcanics (host rock) included in the feed sample was varied: low (4.5%), medium (9%), and high (11%). Figure 13-14 shows grade-recovery curves for the three batch flotation tests. The low dilution sample showed the best performance which was largely attributed to lower lithium losses during magnetic separation (5.8% lithium loss as compared to 8.5% and 8.6% for the medium and high dilution samples, respectively).




Figure 13-14: Example of the Impact of Dilution on Flotation Performance

Table 13-18 shows final spodumene concentrate assays for the tests. The low dilution sample showed the highest lithia grade and lowest iron content.

Table 13-18: Spodumene Concentrate Assays

Test	Li_2O %	Fe_2O_3 %
F22 (Low Dilution)	5.58	1.26
F11 (Medium Dilution)	5.27	1.76
F23 (High Dilution)	5.30	1.43

13.3.3.4 *Variability Sample Testwork Results*

The variability samples were tested using the same flowsheet (mimicking the NAL flowsheet) as the composite samples. All variability tests were operated under the same conditions as shown in Table 13-19.

Table 13-19: Variability Conditions

Test	P100 (µm)	Dosage (g/t)			
		Na_2CO_3	NaOH	F220	FA-2
Variability	250	88	200	250	780




Figure 13-15: Example of the Impact of Dilution on Flotation Performance

Table 13-20 shows final concentrate assays for each test. For variability samples 1, 3, 4, and 5 grades ranged from 5.47% to 6.03% Li_2O, and from 0.92% to 1.19% Fe_2O_3. Final lithium recovery for these samples ranged from 77.6% to 82.3%. Variability sample 2 performed poorly and only achieved 4.80% Li_2O and 1.87% Fe_2O_3 with lithium recovery of 72.2%.

For personal use only

Further testing is planned for variability sample 2 to investigate the impact of finer grind size and varying collector dosage.

Table 13-20: Final Spodumene Concentrate Assays

Variability Sample	Li_2O %	Fe_2O_3 %
1 (grano. /volcanics)	5.47	1.19
2 (grano.)	4.80	1.87
3 (grano. /volcanics)	5.60	0.98
4 (gabbro)	5.73	1.05
5 (gabbro)	6.03	0.92

13.3.3.5 Testwork Analysis

Optimized testwork data was selected and analysed to support the process mass balance. The majority of the tests selected to be used in the analysis were from the DFS testwork program (one test from the PFS testwork program was included). All tests analysed were from testing on composite samples.

Figure 13-16 outlines the testwork conditions for the optimized tests. Two fatty acid collectors were tests: Sylfat FA-2 and Arrmaz Custofloat 7080. Custofloat 7080 was employed at the NAL concentrator but the collector has been changed since the restart.




Figure 13-16: Testwork Analysis: Grade-Recovery Correlation

All tests were operated with two stages of wet high-intensity magnetic separation at 13,000 gauss. Table 13-21 shows the grade-recovery data point for the selected tests. The red curve is the correlation through all the datapoints which was used to support the recovery assumptions in the process mass balance.

For personal use only

For personal use only

Table 13-21: Testwork Conditions

Test	P100 (µm)	Dosage (g/t)					
		Na_2CO_3	NaOH	F100	F220	FA-2	CF 7080
F7 (DFS)	250	250	NM	0	250	780	0
F8 (DFS)	250	200	NM	0	250	780	0
F18 (DFS)	250	200	88	0	250	0	780
F19 (DFS)	250	200	88	0	250	0	780
F21 (DFS)	250	200	88	0	250	780	0
F22 (DFS)	250	200	88	0	250	780	0
F23 (DFS)	250	188	88	0	250	780	0
F24 (DFS)	250	225	100	0	250	0	780
F9 (PFS)	300	225	75	250	0	1,080	0

**Note: NM = Not Measured.*

13.4 Testwork Analysis

Optimised testwork data was selected and analysed to support the process mass balance. The majority of the tests selected to be used were from the 2023 DFS testwork program. The 2023 DFS testwork assessed NAL/Authier ore feed blends and the figure below summarises the spodumene concentrate grade vs testwork recovery curve (DFS, 2023).




Figure 13-17: 2023 DFS Testwork Grade-Recovery Curve

A comparison of the global Li_2O recovery comparing the testwork recovery curve (without any industrial derating) against the NAL operational quarterly performance data (from Q3 FY24 to Q4 FY25) is presented below. The recent quarterly performance (Q4 FY25) with a spodumene concentrate grade of 5.2% Li_2O at 73% global recovery is also shown. The expansion forecast recovery curve also includes the datapoint of 71.2% recovery at 5.4% Li_2O concentrate grade.




Figure 13-18: Li_2O Grade Recovery Curve including NAL Quarterly Performance

Historical metallurgical testwork from the above-described previous phases, along with current operational performance has been used as the basis for the NAL expansion FS.

Based on the previous laboratory testwork and current operational performance, an average global recovery of 71.2% at a spodumene concentrate grade of 5.4% Li_2O has been applied for the Expansion Scenario for the purposes of the PFS.

The impact of ore sorters was analysed through statistical methods for impact on recovery from operating data. A recovery increase of 2% above the base case is included in the above 71.2% with additional ore sorting performance testing underway.

13.5 Current Testwork

Historical metallurgical testwork from the above previous phases, along with current operational performance has been used as the basis for the NAL expansion FS. Geometallurgy testwork and further metallurgy optimisation testwork is currently underway to increase understanding of the metallurgical performance and spodumene recovery across the NAL mineral resource and Mine Plan, in addition to identifying potential spodumene recovery improvement opportunities. The following programs are nearing completion:

- Geometallurgical program based on Life of mine sample selection to provide additional data on ore behaviour throughout the mine life.
- XRT ore sorting testwork.

The author is of the opinion that the previous feasibility-level testwork, current operating metallurgical data and methodologies applied are relevant and of adequate nature for the treatment of NAL ore at the NAL treatment plant.

For personal use only

14 Mineral Resource Estimate

This chapter describes the process and results of the Mineral Resource estimate for the NAL Property. Information contained in this chapter was previously published by Sayona in an ASX Press Release and JORC (2012) Mineral Resource Estimate dated August 27th, 2025, in a NI 43-101 Technical Report titled “Definitive Feasibility Study Report for the North American Lithium Project, dated April 14th, 2023 and from the announcement entitled “2026 Annual Report” published on the ASX on August 28th, 2026

14.1 Methodology

The Mineral Resource estimate occupies an area spanning 3,550 m along strike, 1,300 m in width and 800 m depth (Figure 14-1).




Figure 14-1: Area of Mineral Resource Estimate, Showing Mineralized Zone Locations at Elevation 350m

Three-dimensional geological wireframes, mineralized intercepts, composites, block modelling, interpolation, classification and reporting were all constructed using Seequent Leapfrog Geo™ (“Leapfrog Geo”) and Leapfrog Edge™ version 2024.1 (“Leapfrog Edge”). Statistical studies were undertaken using Excel and Snowden Supervisor version 9.1 (“Supervisor”). Deswik version 2025.1.2156 was used for the pit shell optimization and Deswik.SO 5.1.3878 for the definition of potentially mineable underground stopes.

For personal use only

For personal use only

14.2 Database

The Project database contains data for 1,575 diamond drillholes, including 923 surface-collared and 652 underground-collared drillholes with a cumulative length of 221,404 m (Figure 14-2).

Table 14-1 shows available drilling data and the drilling data subsequently included in the Mineral Resource estimate. A subset of 562 surface-collared drillholes completed between 2009 and the end of 2024 with a cumulative length of 153,047 m was included in the Mineral Resource estimate. The last drillhole contained in the Project database is hole LAN-24-289.

The average drill spacing is approximately 100 m x 100 m in the area of the deposit, with local definition up to 50 m x 50 m, mostly within the conceptual pit shell. The majority of holes completed between 2009 and 2024 were drilled with an azimuth of N045, which is perpendicular to most of the pegmatite dykes. Holes were typically angled at -45 to -60 degrees to cut as closely as possible to the interpreted true width of each dyke.

Table 14-1: Drilling Data used in the Geological Model and Mineral Resource Estimate

Available Data	Number of Holes	Data Used in the New Model	Grade Interpolation
Drilling Type		Program	
Underground	652	Historical	0
Surface	21	Historical Jourdan	0
	81	Historical (LV)	0
	119	Historical (SB-LB-E-CL-S)	0
	53	2009 - Environment and GT	11
	39	2009	39
	51	2010	50
	63	2011	63
	50	2016	46
	22	2017 - Geotech	0
	59	2018 - Pit limits	0
	42	2019	38
	172	2023	164
	151	2024	151
Total	1,575		562

14.3 Geological Interpretation and Domaining

The geological model employed for the Mineral Resource estimate is based on drillholes, open pit mapping and historical underground mapping and voids. A three-dimensional interpretation of pegmatite dykes was developed using Leapfrog Geo, employing lithology information contained in the Project database (Figure 14-3). A total of 117 pegmatite wireframes (“pegmatite domains”) were created. Other lithology wireframes were developed for granodiorite, volcanic rocks and gabbro (Figure 14-4).

Historical mining voids from past production work are included in the model (Figure 14-5). The location, dimensions and content of some of the historical void shapes are not sufficiently precise, therefore their location and volume were adapted and slightly modified to fit the pegmatite domains.




Figure 14-2: Plan View Showing Pegmatite Dykes and Drillhole Locations

For personal use only




Figure 14-3: Three-Dimensional Interpretation of Pegmatite Domains

For personal use only




Figure 14-4: Lithology Model for Volcanics, Granodiorite and Gabbro

For personal use only




Figure 14-5: Historical Mining Voids Adjusted to Fit Pegmatite Domains, Shown with Semi-Transparent Pegmatite Domains

For personal use only

For personal use only

14.4 Data Preparation

14.4.1 Exploratory Data Analysis

The Mineral Resource estimate incorporates a total of 27,183 records of Li_2O assays with a mean sample length of approximately 0.884 m. Li_2O grade varies from 0.000% to 5.318%. Global average Li_2O grade for raw samples (excluding 0.00% assays) is 0.783%.

The following methods were employed to prepare and analyse Li_2O assay data prior to grade estimation:

- All raw assay data intersecting pegmatite domains were assigned individual mineralisation codes using Leapfrog Geo.
- Unsampled intervals in the Project database were assigned a zero grade.
- An evaluation table was created in Leapfrog Geo where all drillholes that intersected a wireframe within each domain were assigned a name representative of the domain. This table was then merged with the assay table to proceed with the descriptive statistics.
- Exploratory data analysis was completed on raw assay data for all the pegmatite domains to determine the correlation of Li_2O grade within each pegmatite domain and to identify high-grade outlier samples. A combination of descriptive statistics and histograms were used to analyse the grade population of the data using Excel and Leapfrog Geo. The findings were used to help define parameters used in the Mineral Resource estimate.
- High-grade outlier assays in each domain were reviewed.
- Li% is converted to Li_2O% for reporting purposes. The conversion used is Li_2O = Li x 2.153.

14.4.2 Compositing

Compositing of drillhole samples was conducted to homogenize the Project database to remove any bias associated with sample length. The compositing length was determined after consideration of original sample length statistics and other factors. Figure 14-6 shows the distribution of the length before and after compositing.




Figure 14-6 – Distribution of the Length Before (Left) and After (Right) Compositing

For personal use only

All assay intervals captured within the pegmatite domains were composited to regular 1.5 m lengths, based on the observed modal distribution of raw sample lengths. Residual intervals at domain edges of up to 0.75 m were equally distributed along the drillhole to maintain consistency in composite lengths. Unsampled intervals were assigned a zero grade. A total of 14,946 composite samples were generated in pegmatite domains.

Compositing was completed within each pegmatite domain. Composite samples do not cross domain boundaries. The composite assays were validated statistically to ensure there was no loss of data or significant change to the mean grade of each assay population.

14.4.3 Grade Capping

An outlier is an observation that appears to be inconsistent with most of the data in the same statistical population. It is common practice to statistically examine higher grades within a population and to trim outliers to a lower-grade value, commonly referred to as capping.

Capping analysis was performed by searching for abnormal breaks or changes of slope on the grade distribution probability plot, whilst ensuring that: (A) the coefficient of variation ("COV") of the capped data was lower than 2.00; and (B) no more than 10% of total contained metal was enclosed within the first 1% of highest-grade samples. This analysis was performed on the entire dataset for all pegmatite domains. The study determined that capping is warranted on the entire set of composites at 3.0 Li_2O (%) (Figure 14-7).




Figure 14-7: Capping Analysis on All Dykes; Capping at 3.0% Li_2O

For personal use only

14.5 Density Estimation

According to previous NAL reports, density measurements were collected from core during past drilling programs. However, the raw data for these measurements were not available to use for the Mineral Resource estimate.

In 2022, a total of 600 samples collected from 97 drillholes throughout the deposit were sent to SGS Canada Inc. laboratories for bulk density measurement. Representative samples were selected for pegmatites and waste rock.

Bulk density measurements were determined by the water immersion method. Core samples were weighed in air and then placed in a basket suspended in water and were weighed again. The samples were not waxed or sealed; however, natural voids were not considered to be a significant issue with respect to bulk density determination.

Table 14-2 lists the median values used for each lithology.

Table 14-2: Bulk Density Values Employed for the Mineral Resource Estimate

Rock Type	Count	Min (g/cm3)	Max (g/cm3)	Median (g/cm3)
Gabbro	35	2.85	3.20	3.11
Granodiorite	30	2.63	3.16	2.77
Pegmatite	482	2.56	2.93	2.70
Volcanic	53	2.83	3.19	3.01
Overburden				2.00

14.6 Geostatistics and Grade Estimation

14.6.1 Variography

A semi-variogram is used to measure the spatial variability of Li_2O grade within specific mineralized zones. Samples collected far apart will typically vary more than samples collected close to each other. A variogram provides a measure of how much two samples taken from the same mineralized zone will vary in grade depending on the distance and spatial orientation between those samples.

Variography studies were completed for eleven of the largest pegmatite domains using Supervisor (Figure 14-8). Experimental variograms were calculated from the composited Li_2O assay data to determine the approximate dimensions and orientations of the search ellipses.

The following steps were considered for each domain analysis:

1. Downhole variograms were created and modelled to define the nugget effect.
2. Experimental semi-variograms were calculated to determine directional variograms for the major, semi-major, and minor orientations.
3. Variograms were modelled using an exponential model with practical range and a normalized sill of 1.

For personal use only




Figure 14-8: Variography Study in Supervisor (Example from Dyke A)

Variogram ranges were observed to be similar for all eleven pegmatite domains. The variogram model for Dykes A and B, which are the two pegmatite domains containing the most composites, was therefore chosen to be used for all domains in the geological model. Table 14-3 summarises the variogram parameters employed for all pegmatite domains.

Table 14-3: Variogram Parameters used for All Pegmatite Domains

Domain	Nugget	First Structure				Second Structure			
		Sill	Range X (m)	Range Y (m)	Range Z (m)	Sill	Range X (m)	Range Y (m)	Range Z (m)
ALL_ZONES	0.05	0.3	60	15	10	0.65	180	180	25

All of the pegmatite domains were estimated using the ordinary kriging (“OK”) method, employing Leapfrog Edge software. All of the pegmatite domains were also estimated using Inverse Distance Square (“ID2”) and Nearest Neighbour (“NN”) methods employing Leapfrog Edge, for comparison and validation purposes. The OK estimation results were determined to be similar to the results for ID2 and NN methods. The OK method was therefore retained as the preferred estimation method for all pegmatite domains to simplify the estimation process.

Three successively less restrictive passes were completed to interpolate Li_2O grades. The ellipse sizes and anisotropies were based on variography, drillhole spacing and pegmatite geometry. The ellipsoid used for the first pass was 50% of the range of the variogram (90 m x 90 m x 12.5 m), for the second pass the ellipsoid was 100% of the range of the variogram (180 m x 180 m x 25 m) and for the third pass, the ellipsoid was 150% the range of the variogram (270 m x 270 m x 37.5 m) and meant to fill the remaining blocks of the block model. The first and second pass has a minimum of four (4) composites and a maximum of eight (8) composites and a minimum of two drillholes were needed to interpolate. The third pass has a minimum of two (2) composites and a maximum of eight

For personal use only

(8) composites with no minimum number of drillholes needed to interpolate. Table 14-4 summarises the search ellipsoid parameters.

Spatial anisotropy of the pegmatite domains was respected during estimation using the Leapfrog Edge Variable Orientation tool. The Variable Orientation tool uses the central reference plane from each individual pegmatite dyke to select the locally appropriate anisotropy orientation and to orient the search ellipse for selection of composites and determination of kriging weights.

Table 14-4: Search Ellipsoids

Pass	Ellipse (m)	Min. Sample	Max. Sample	Max per Hole
1	90 x 90 x 12.5	4	8	3
2	180 x 180 x 25	4	8	3
3	270 x 270 x 37.5	2	8	None

14.6.2 Block Model

Block models were generated in Leapfrog Edge for each of the pegmatite domains. Parent cells of 5 m x 5 m x 5 m were sub-blocked four times in each direction (minimum sub-block of 1.25 m in each direction). Sub-blocks are triggered by the geological model, mining voids, overburden, topography, and classification. The block model is rotated -50 degrees around the Z axis.

Block models include proportional sub-blocks to cover spaces inside the solid boundaries and to honour wireframe volumes. The size of sub-blocking was chosen to best match the thickness of the pegmatite domains and the complexity of the geological model. Block model parameters are shown in Table 14-5. Grades were estimated using the parent block and assigned to the sub-blocks.

Table 14-5: Block Model Parameters used in Leapfrog Edge™

Properties	X (Column)	Y (Row)	Z (Level)
Origin of coordinates	293,380	5,363,260	490
Number of blocks	515	826	170
Block size (m)	5	5	5
Minimum sub-block size(m)	1.25	1.25	1.25
Rotation	-50		

14.6.3 Grade Interpolation

Block models were estimated using Ordinary Kriging (“OK”) and Variable Orientation search algorithms fully implemented in Leapfrog Edge. Variable Orientation allows the orientation of the ellipsoid and variograms to be used for each block individually based on local characteristics. ID2 and Nearest-Neighbour (“NN”) models were produced for validation purposes.

Kriging neighbourhood analysis (“KNA”) was performed to assist with the selection of the estimation parameters. KNA provides a quantitative method of testing different estimation parameters, such as block size, number of samples, optimum search radius, and discretization by assessing their impact on the quality of the resultant estimates in terms of kriging efficiency and slope of regression. This study is dependent on several factors, including the inherent deposit variability, grade continuity, anisotropy, and the data spacing. The variogram mathematically represents these factors and is critical for a KNA. Table 14-6 summarizes the suggested parameters of the KNA analysis.

For personal use only

Table 14-6: Summary of the Suggested Parameters from the KNA Analysis

Properties	Global Optimum
Block sizes (m)	5x5x5
Sample ranges	4 to 8
Search ranges (m)	180, 180, 25
Discretization	3, 3, 3

The interpolation was performed with three search passes. The first pass is interpolated using 50% of the ranges of the second structure of the variogram (0.5x), the second pass uses 100% (1x) and the third pass uses 150% (1.5x) of the ranges of the second structure of the variogram and is meant to fill the remaining blocks. A minimum and a maximum number of composites were required in each pass, as well as a maximum number of composites by drillhole to satisfy the estimation criteria, as shown in Table 14-7.

Hard boundaries were implemented between each pegmatite domain to ensure that grades from adjacent domains were not included during interpolation. Each block was tagged with the pass number corresponding to its estimation. Interpolation was carried out sequentially, domain by domain, and was limited to composites that were uniquely coded for each domain.

Table 14-7: Summary of Parameters used for Li_2O Grade Interpolation

Dyke	Interpolation Method	Pass	Ellipsoid Ranges (m)			Number of Samples		Drillhole Limit
			Max	Intermediate	Min	Max	Min	Max Samples/Hole
All dykes	OK	P1	90	90	12.5	4	8	3
All dykes	OK	P2	180	180	25	4	8	3
All dykes	OK	P3	270	270	37.5	2	8	-

14.7 Block Model Validation

Validation of the block model was performed using Swath Plots in each of the three block model axes, ID2 and Nearest-Neighbour (“NN”) grade estimations, global means comparisons, and visual inspection in 3D and along plan views and cross-sections.

14.7.1 Visual Inspection

Block model grades were visually compared against drillhole composite grades in cross-section and 3D views. This visual validation process also included confirming that the proper parameters were selected for the various domains and checks for global and local bias. The visual comparison shows that the block model is reasonably consistent and correlates well with the primary data without excessive smoothing, as shown in Figure 14-9.




Figure 14-9: Cross-Section Looking West

14.7.2 Swath Plots

Swath plots were generated as part of the block model validation process. A swath plot is a graphical display of the grade distribution derived from a series of bands (or swaths) generated in several directions throughout the deposit. Using swath plots, grade variations from the Li2O_OK model are compared to the distribution of grades interpolated with the Li2O_NN and Li2O_ID2 methods and the composites. This validation method also works as a visual means to identify possible interpolation bias. Figure 14-10 and Figure 14-11 show an example of swath plots through a single pegmatite domain. The Li_2O grades estimated in each block are generally close to the average grades provided by the data source, albeit with some smoothing of values evident. Block grades determined by OK and ID2 estimates are observed to be lower than the composite values in some areas. This is attributed to the interpolation of lower grade composite samples from further away within the search ellipse.

For personal use only

For personal use only




Figure 14-10: Swath Plot for Mineralized Pegmatite Dyke A – Direction X




Figure 14-11: Swath Plot for Mineralized Pegmatite Dyke A – Direction Y

For personal use only

14.8 Mineral Resource Classification

The Mineral Resource estimate includes Mineral Resources classified as Indicated and Inferred categories. The classification of Mineral Resources takes into account the following criteria:

1. Interpolation passes.
2. Distance to closest information.
3. Number of drill holes used to estimate the block's grade.
4. Proximity to known mineralization in the current pit.

The Indicated category was assigned to blocks informed by a minimum of two drillholes where drill spacing is less than 80 m inside the conceptual resource pit shell. The Inferred category was assigned to blocks when the drill spacing was 150 m or less. Classification volumes are created around contiguous blocks at the stated spacing criteria with consideration for the selected mining method. Geological and grade continuity is also taken into consideration during the classification process.

Figure 14-12 shows a longitudinal section of the Mineral Resource classification for one pegmatite dyke wireframe




Figure 14-12: Classification Distribution on a Longitudinal Section of One Pegmatite Dyke, Looking Northeast

Measured category blocks from the previous Mineral Resource estimate have been reclassified as Indicated Resources to align with the more stringent definition of Measured Resources under SEC disclosure standards (§ 229.1300). This standard requires a higher level of geological confidence in the estimates than comparable frameworks for NI 43-101 and JORC (2012). Due to the complex geometry of the pegmatite dykes, characterized by pinching, swelling, and intertwining within the pit, it is not possible to precisely confirm their location. As a result, while the underlying data remains unchanged, the level of geological confidence does not meet the threshold required for Measured classification under SEC disclosure standards, necessitating the downgrade to Indicated.

For personal use only

14.9 Economic Parameters and Cut-off Grade

Mineral Resources were estimated using Leapfrog Edge to create the block model and Deswik. CAD 2025.1.2156 and Deswik.SO 5.1.3878 software to create a pit shell and reasonable underground mineable shapes. To ensure that the Mineral Resource estimate for the Property satisfies the Reasonable Prospects for Eventual Economic Extraction ("RPEEE") requirement, a number of technical and economic factors were considered in the derivation of the Mineral Resource volume used to constrain the mineralization.

Pit shells were used to constrain open-pit sections of the Mineral Resource estimate. Resource-level optimized pit shells and their corresponding cut-off grades were used for the open pit Mineral Resource estimate. The constraining pit shell was developed using pit slopes of 46 to 53 degrees based on geotechnical data.

Reasonable underground mining shapes were based on minimum width and/or the geometry of the mineralization. The solids representing the reasonable mining shapes are based upon contiguous blocks above the cut-off grade.

The Mineral Resource estimate has been tabulated using a cut-off grade ("COG") of 0.60% Li2O for an open pit mining scenario and 0.70% Li2O for an underground mining scenario based on 5.4% spodumene concentrate selling price of USD$1,395/t. A COG of 0.60% Li2O was used for the Mineral Resource estimate due to processing limitations and should be viewed as a mill-feed cut-off grade for an open pit scenario.

Stope Optimiser shapes ("DSO") with a minimum of 3 m were used for reporting underground resources. All material within the shapes, including internal dilution below the cut-off grade of 0.7% Li_2O, was reported.

Forecast lithium product sale prices calculated by BMI (source: Benchmark Mineral Intelligence 2025 Q1 2025 Lithium Forecast Report) are shown in Figure 16-3 (Chapter 16). The average nominal sale price of 6% spodumene concentrate is approximately USD1,550/t between 2026 and 2040. Refer to Chapter 16 (Market Studies and Contracts) for further information.

Table 14-8 summarizes the values used to determine the cut-off grades for the Mineral Resource estimate. The COG should be reassessed periodically, considering market conditions and factors such as the price of lithium, exchange rates, mining techniques and associated costs.

Table 14-8: Reasonable Extraction Factors

Cost	Unit	Open Pit	Underground
Mining	CAD/t mined	8.50	100.00
Processing (including water treatment and tailings Management costs)	CAD/t milled	46.10	46.10
G&A	CAD/t milled	17.09	17.09
6% Li_2O concentrate price	USD/t conc.	1,550	1,550
Concentrate transport	USD/t conc.	126.23	126.23
Exchange rate	USD:CAD	0.74	0.74
Recovery	%	69.20	69.201
Break-even grade	%	0.28	0.72
Cut-off grade applied	%	0.60	0.70

Notes:
1. An average Life-of-Mine metallurgical recovery of 71.2% at a spodumene concentrate grade of 5.4% Li_2O has been applied to the Expansion Case for the purpose of the PEA study, compared with an estimate of 69.2% for the Base Case. See Section 13.5 - Testwork Analysis and Section 16.4.5 - Modifying Factors for further information.

For personal use only

14.10 Mineral Resource Statement

The Mineral Resource estimate as of June 30, 2026, is shown in Table 14-9.

Table 14-9: NAL Mineral Resource Estimate – June 30, 2026

NAL – Total Open Pit and Underground Constrained Mineral Resource Estimate					
Classification	Scenario	Tonnes (Mt)	Grade (% Li_2O)	Cut-Off Grade % Li_2O	Met Recovery %
Indicated	OP	74.4.	1.17	0.60	69.2
	UG	-	-	-	-
	Total	74.4	1.17	0.60	69.2
Inferred	OP	8.6	1.13	0.60	69.2
	UG	10.3	1.01	0.70	69.2
	Total	18.9	1.06		69.2

Notes:

2. The information on Mineral Resources and Ore Reserves is extracted from the announcement entitled “2026 Annual Report” published on the ASX on August 28th, 2026, and is available to view on the Elevra’s website on the ASX. Measured Group and Optimal Mining are responsible for the Mineral Resource estimate presented in this Report.
1. The independent QP for the Mineral Resource estimate, as defined by NI43-101, is Stephen Andrews (MAusIMM) of Measured Group Pty Ltd.
2. The Effective Date of the Mineral Resource estimate. is June 30th, 2026.
3. Mineral Resources are inclusive of Mineral Reserves, but do not include the stockpiled ROM ore.
4. The Mineral Resource has been adjusted for mining depletion up to 30th June 2026 based on LiDAR survey information. No re-estimation of the underlying Mineral Resource model has been undertaken. The Effective Date of the Mineral Resource estimate is June 30th, 2026.
5.
6. 3. The independent QP for the Mineral Resource estimate, as defined by NI43-101, is Stephen Andrews (MAusIMM) of Measured Group Pty Ltd.
7.
8. Mineral Resources are not Mineral Reserves as they do not have demonstrated economic viability. The quantity and grade of reported Inferred resources in this Mineral Resource estimate are uncertain in nature and there has been insufficient exploration to define these resources as Indicated; however, it is reasonably expected that the majority of Inferred Mineral Resources could be upgraded to Indicated Mineral Resources with continued exploration.
9. The geological model created in Leapfrog Geo™ 2024.1 contains a total of 117 pegmatite dykes, of which 93 demonstrate RPEEE ‘reasonable prospects for eventual economic extraction’.
10. Based on the statistical analysis, capping value was set at 3.00% Li_2O and applied after compositing. Compositing of 1.5 m in length was completed using the grade of the adjacent material when assayed or a value of zero when not assayed.
11. The Mineral Resources were estimated using Leapfrog ™ 2024.1 using hard boundaries on composited assays. The OK method was used to interpolate a sub-blocked model (parent block size = 5 m x 5 m x 5 m and subblocks of 1.25 m).
12. The Mineral Resource estimate is categorized as Indicated and Inferred resources. There are no Mineral Resources in the Measured category. The Indicated category was defined for blocks that are informed by a minimum of two (2) drillholes where drill spacing is less than 80 m. The Inferred category was assigned to blocks where drill spacing is less than 150 m. Where needed, some materials have been either upgraded or downgraded to avoid isolated blocks and spotted-dog effects.
13. Fixed density values were established on a per unit basis, corresponding to the median of the bulk density data of each unit ranging from 2.70g/cm^3 to 3.11g/cm^3 (2.70 g/cm^3 for all pegmatite dykes, 2.77 g/cm^3 for Granodiorite, 3.01 g/cm3 for Volcanics and 3.11 g/cm^3 for Gabbro).
14. The Topography used for this Mineral Resource estimate is a combination of Lidar surveys dating from September 2024 to June 29th 2026.
15. Mineral Resources are presented undiluted, pit constrained and within stope shapes and are considered to have reasonable prospects for eventual economic extraction. Although the calculated cut-off grade is 0.28% Li_2O for open pit, a cut-off grade of 0.60% Li_2O was used for the Mineral Resource estimate due to processing limitations. The pit optimization was completed using Deswik mining software. The constraining pit shell was developed using pit slopes of 46 to 53 degrees. The open-pit cut-off grade and pit optimization were calculated using the following parameters (amongst others): 5.40% Li_2O concentrate price = USD1,395 per tonne; USD:CAD exchange rate = 0.74; Hard Rock and Overburden Mining cost = $8.50/t mined; Mill Recovery of 69.2%; Processing cost (including water treatment, tailing management and sustaining capital)= $46.10/t processed; G&A = $17.09/t processed; Transportation cost = $126.23/t conc. The cut-off grade for underground resources was calculated at 0.72% Li_2O but rounded to 0.70% Li_2O; it used identical costs and recoveries, except for mining costs being at $100/t. Cut-off grades will be re-evaluated in light of future prevailing market conditions and costs.
16. The number of tonnes has been rounded to the nearest hundred thousand. Any discrepancy in the total is due to rounding effects.

17. The QPs are not aware of any known environmental, permitting, legal, title-related, taxation, socio-political, marketing, or other relevant issues that could materially affect the mineral resources estimate other than those disclosed in this Report.
18. Mineral resources are 100% attributable to NAL Property. Elevra has 100% interest in North American Lithium.
19. The Mineral Resources were prepared in accordance with the standards set out in the 2012 Edition of the 'Australasian Code for Reporting of Exploration Results, Mineral Resources and Ore Reserves' ("JORC Code") and in accordance with National Instrument 43-101 – Standards of Disclosure for Mineral Projects of the Canadian Securities Administrators ("NI 43-101").

14.11 Grade Sensitivity Analysis

Table 14-10 presents the sensitivity of the open-pit portion of the June 2025 Mineral Resource estimate at different cut-off grades. Each iteration of the cut-off grade sensitivity study was pit constrained only. Sensitivity has not been run on the underground portion of the MRE. Tonnages and grade are presented at 0.10% Li_2O, Li_2O cut-off grade increments within the official RPEEE pit shell from 0.2% to 0.8%.

Note that the figures provided in this table should not be interpreted as a Mineral Resource statement. The reported quantities and grade estimates at different cut-off grades are presented for the sole purpose of demonstrating the sensitivity of the Mineral Resource estimate to the reporting cut-off grade.

Table 14-10: Cut-Off Sensitivity Analysis (Open Pit Portion) of June 2025 Mineral Resources

Classification	Indicated		Inferred		Indicated and Inferred	
Cut-off Grade Li_2O %	Tonnes (Mt)	Li_2O %	Tonnes (Mt)	Li_2O %	Tonnes (Mt)	Li_2O %
0.2	93.7	1.03	11.2	0.96	104.8	1.02
0.3	89.8	1.07	10.7	0.99	100.5	1.06
0.4	85.8	1.1	10.1	1.03	95.9	1.09
0.5	81.4	1.13	9.4	1.08	90.7	1.13
0.6	76.2	1.17	8.6	1.13	84.7	1.17
0.7	70.2	1.22	7.5	1.19	77.7	1.22
0.8	63.6	1.27	6.6	1.25	70.2	1.27

14.12 Iron Content

Iron content (% Fe) can influence metallurgical recovery and the quality of potential spodumene concentrate. As a result, an "Fe" attribute was assigned to both the blocks and sub-blocks of the resource model. This is especially important when converting mineral resources into mineral reserves. The iron content plays a significant role in subsequent stages of studies, including potential mining sequencing and planning. At the mineral reserves stage, iron will not only come from the pegmatites but also from dilution caused by surrounding host rocks. A sampling program conducted in 2022 provided precise data for all lithologies. Since 2022, iron grades have been analysed alongside lithium.

Iron content was incorporated into the block model using the median values for each host rock lithology and was estimated within pegmatite domains using ID2. Where data was insufficient for estimation, the median iron grade of the pegmatite was assigned to the affected blocks.

The median values used for each lithology are shown in Table 14-11.

For personal use only

Table 14-11: Iron Content used for Mineral Resource Estimate

Rock Type	Fe (%)
Gabbro	6.68
Granodiorite	2.30
Pegmatite	ID2 or fixed value of 0.29
Volcanics	5.72

For personal use only

For personal use only

15 Mineral Reserve Estimate

15.1 Summary

North American Lithium (NAL) is an operational mine which allows for the use of current mine designs, equipment operating parameters and historical unit cost rates in the development of the Mineral Reserve estimate. All required processing, maintenance and technical infrastructure required to produce spodumene concentrate and bring the concentrate to market exists on site. The economics of the Mineral Reserve estimate may be materially affected by a significant change to commodity pricing, however spodumene concentrate is forecast to remain at elevated levels.

The NAL Reserve estimates have been prepared using accepted industry practice and in accordance with NI 43-101 reporting standards, by Mr Tony O'Connell who is an employee of Optimal Mining Solutions Pty Ltd, an independent mining consultancy based in Brisbane, Australia.

15.2 Mineral Reserve Estimate

The Mineral Reserve estimate for NAL has been estimated as of June 30th, 2026, with the results shown in Table 15-1.

Table 15-1: NAL Reserves estimate as of June 30th, 2026

Category	Tonnes (Mt)	Li_2O Grade (%)	Li_2O Cut-Off (%)	Fe Grade (%)
Proven Reserves	0.2	0.93%	0.60%	1.48%
Probable Reserves	47.0	1.12%	0.60%	0.81%
Proven + Probable Reserves	47.2	1.12%	0.60%	0.81%

Notes on the Mineral Reserve estimate:

- The effective date for the Mineral Reserves estimate is June 30th, 2026.
- Mineral Reserves are measured as dry tonnes at the crusher above a diluted cut-off grade of 0.60% Li_2O.
- All Proven Reserves are from ROM stockpiles as of June 30th, 2026.
- Mineral Reserves result from a positive pre - tax financial analysis based on a 5.4% Li_2O spodumene concentrate average base price of US$1,250/t for 6% spodumene and an exchange rate of 0.74 US$:1.00 C$.
- The selected optimized pit shell is based on a revenue factor of 0.95 applied to a base case selling price of US$1,250/tonne for 6% spodumene concentrate.
- Topographic surface as of June 29th, 2026, was used as the starting surface.
- The reference point of the Mineral Reserves Estimate is the NAL crusher feed.
- In-situ Mineral Resources are converted to Mineral Reserves based on pit optimization, pit design, mine scheduling and the application of modifying factors, all of which support a positive LOM cash flow model.
- The waste and overburden to ore ratio (strip ratio) is 7.1.
- Totals may not add up due to the rounding of significant figures.
- The Reserve estimate was prepared in accordance with the standards set out in the 2012 Edition of the 'Australasian Code for Reporting of Exploration Results, Mineral Resources and Ore

Reserves' ("JORC Code") and in accordance with National Instrument 43-101 – Standards of Disclosure for Mineral Projects of the Canadian Securities Administrators ("NI 43-101").

15.3 Mineral Reserve Estimation Process

The process followed for the 2026 NAL Mineral Reserve estimate is summarised by the points below, with the points completed in order:

1. Complete a pit optimization assessment on the Resource block model to determine economic limits, with only ore classified as Indicated included. All Inferred material is converted to waste.
2. Generate a practical final pit shell and internal phases within the chosen economic shell from the pit optimization assessment, adhering to all geotechnical parameters and mining limits.
3. Create all dig solids within the final pit shell, subdivided into phases and then into 10m x 10m x 5m regularized solids.
4. Apply loss and dilution calculations to all dig solids to calculate ROM (as mined) quantities and qualities.
5. Import all dig solids into a life-of-mine schedule, along with all dump designs, operating equipment and time usage models.
6. Complete life-of-mine schedule, achieving planned plant throughput rates.
7. Undertake financial assessment of results from life-of-mine schedule ensuring positive cashflow and $NPV_{8\%}$ for the site.

15.4 Resource Block Model

The Resource block mode used for the Mineral Reserve estimate is a Datamine block model titled 2025 BM_20250814.dm, which was used for the June 6, 2025, Mineral Resource estimate.

Parent cells 5m x 5m x 5m were sub-blocked four times in each direction (minimum sub-block of 1.25 m in each direction). Sub-blocks are triggered by both the geological model and mining voids, for precise depletion. This model has proportional sub-blocks to cover the spaces inside the solid boundaries. The size of the sub-blocking was chosen to best match the thickness of the mineralized dykes and the complexity of the geological model. The block model parameters and prototype values are shown in Table 15-2 and Table 15-3 respectively.

Table 15-2: Block Model Parameters

Item	Value
Name	2025 BM_20250814.dm
File Size	18.4 GB
Number of Records	72,316,300
File Format	.dm (Datamine)
Date Generated	2025-08-14

Table 15-3: Block Model Prototype

Item	X (UTM)	Y (UTM)	Z (UTM)
Min. Extent	290216.2364499186	5363260	-360.00
Maximum Extent	295035.1780949428	5367887.2772690365	490.00

For personal use only

Largest (parent) cell	5	5	5
Smallest sub cell	1.25	1.25	1.25
No. of Parent Cells	515	826	170
Rotation	-	-	310 degs

Each cell in the block model was allocated a material type based on the geological zone of the cell. Material types were either overburden, pegmatite, volcanics, gabbro, granodiorite or voids (for underground voids).

15.5 Reserves Topography

The topography used for the Mineral Reserve estimate was created on June 29th from high-definition Lidar information. The topographic surface contained over 9.5 million faces and was used to cut all planned dig solids to provide the final Mineral Reserve estimate values. The topographic surface used for the Mineral Reserve estimate and the dig solids are shown in Figure 15-1.




Figure 15-1: Starting Topographic Surface and Dig Solids

For personal use only

For personal use only

15.6 Pit Optimization

A pit optimization assessment was undertaken to calculate the final economic pit shell based on given financial parameters, processing assumptions and pit slopes that results in the maximum undiscounted value for a specific revenue factor.

15.6.1 Geotechnical Parameters

Overall pit slopes, based on parameters developed by Golder Associates, were included in the pit optimization assessment. The overall pit slopes were lowered slightly after preliminary runs to include allowances for haulage ramps and geotechnical berms. The overall slope angle varied depending on the geotechnical region, as shown in Figure 15-2 and Table 15-4.




Figure 15-2: Geotechnical Regions

Table 15-4: Open Pit Optimization Slope Angles

Region	Units	Overall Slope Angle
GEOT_11	degs	44.9
GEOT_12	degs	47.6
GEOT_13	degs	49.0
GEOT_14	degs	41.5
GEOT_15	degs	41.1
GEOT_16	degs	42.6
GEOT_24	degs	32.1
GEOT_25	degs	33.9

For personal use only

15.6.2 Loss and Dilution

The final ROM quantity of ore and waste, taking into account loss, dilution and cut-off grades, was calculated for each mining dig solid by a set of detailed formulas as described below:

1. If more than 30m^3 of ore exists in the dig solid, then consider the ore as potentially recoverable, otherwise (<30m3 of ore) convert the entire solid to waste.
2. Allocate between 5% and 50% dilution depending on the percentage of ore in the block. Each 1% drop in ore percentage adds 0.3% dilution, up to a maximum of 50% dilution.
3. Allocate between 0% and 30% loss depending on the percentage of ore in the solid. Each 1% drop in ore percentage adds 0.3% loss, up to a maximum of 30% loss.
4. Obtain the diluting rock type (i.e. volcanics, gabbro, granodiorite or overburden) and subsequent Li_2O, Fe and density parameters.
5. Add the dilution quantities and qualities to the ore component of the solid based on the percentage dilution calculated (step 2) and the diluting material properties (step 4).
6. Remove the loss quantities and qualities from the ore component of the solid based on the percentage loss calculated (step 3).
7. Calculate the final ore quantities and qualities (original values less losses plus dilution).
8. If the Li_2O percentage of the final ore quantity is less than 0.60% (the assigned cut-off grade) then convert the ore component to waste.
9. Assign a final ROM material to the block – a block with any ore is allocated “ORE” with all others allocated as “WASTE”.

As the above formulas indicate, a smallest mining unit (SMU) of 30m^3 has been assigned for ore mining. This represents approximately one truckload of ore.

Application of the above formulas results in the following overall loss and dilution values:

- The overall loss percentage is 10.5% (tonne:tonne),
- The overall dilution percentage is 11.6% (tonne:tonne).

15.6.3 Cut-off Grades

The cut-off grade (COG) was calculated considering costs for processing, general & administration (G&A) costs, and other costs related to concentrate production and transport, as shown in Table 15-5.

Based on the parameters shown in Table 15-5, a COG of 0.29% Li_2O has been calculated. However, due to metallurgical recovery limitations, a metallurgical COG of 0.60% Li_2O was selected based on iterative analysis and to assure a feed grade that allows a sufficient metallurgical recovery to produce the required spodumene concentrate grade.

15.6.4 Costs and Revenue

The cost and revenue inputs for the pit optimization process are presented in Table 15-5. A metallurgical recovery of 69.2% was applied to all ore.

For personal use only

Table 15-5: Open Pit Optimization Parameters

Parameters	Unit	Value	Comments
Revenue			
Concentrate price	USD/t of conc.	1,250	For 6% spodumene concentrate (US$1,125 for 5.40%)
Concentrate grade	% Li_2O	5.40%	
Transportation cost	CAD/t of conc.	126.23	
Economics			
Currency	CAD	-	
Exchange rate	USD/CAD	0.74	
Cost Basis			
Mining			
Mining cost	CAD/t mined	9.22	2025 budget mining cost and mining contractor costs (inclusive of attribution of G&A cost of 0.72/t mined)
Incremental mining cost	CAD/t/10m	0.03	Additional cost per tonne for every 10 vertical metres below RL400 (to take into account additional haulage).
Processing and G&A			
Processing	CAD/t milled	51.44	Inclusive of 41.58 processing cost and 9.86 G&A/SIBC (attribution of 5.34 G&A, 4.52 SIBC)
General G&A	CAD/t milled	4.68	

15.6.5 Open Pit Optimization Results

Figure 16-3 shows the results of the pit optimization assessment. The values returned by the pit optimization assessment do not include capital investments as the cashflow generated within the pit shell must be large enough to cover all foreseeable capital outlays.




Figure 15-3: Pit Optimization Results

For personal use only

The revenue factor 0.95 pit shell, where realized prices are 95% of the forecast price, was selected as a guide for the final pit design. The selection of this revenue factor shell was based on maximizing project ore tonnes mined while respecting a relatively high $NPV_{8\%}$.

As Figure 15-3 indicates, the 0.95 revenue factor shell contains approximately 50.8mt of ore and 335.5mt of waste. However, these values are calculated as part of the pit optimization process which generates an evenly spaced grid of the economic pit shell for each scenario. Conversion of the economic pit shell grid from pit optimization to a practical pit design, which contains all required ramps, berms and benches, results in an increase in the strip ratio of the pit incurred by either a reduction in ore tonnes or an increase in waste tonnes, or both.

15.7 Pit Designs

15.7.1 Pit Design Criteria

The final pit and the 15 phase designs utilised a set of detailed geotechnical parameters generated by Golder and Associates as shown in Table 16-7.

Table 15-6: Ultimate Pit Design Parameters

Design Sector	Wall Dip Direction		Bench	Catch Bench	Bench Face	Inter-Ramp	Geotechnical
	From	To	Height (m)	Width (m)	Angle (deg)	Angle (deg)	Berm Interval (m)
Overburden*	0	360	N/A	9	26.6	N/A	N/A
South	355	35	20	16	60.0	45.7	120
Northeast	195	270	20	10	65.0	49.1	120
Northwest	35	195	20	10	70.0	52.6	120
Southeast	270	355	20	10	70.0	52.6	120

Note: A 7 to 9 m setback considered at bedrock contact, depending on various factors listed in section 2.4.2 of the WSP-Golder memorandum (22515754-166-MTF-RevB).

Dual-lane ramps were designed into the final pit shell as well as the phase designs. The final pit shell is shown in Figure 16-7 and Figure 15-5.

15.8 Life-of-Mine Schedule

The life-of-mine schedule, as detailed in Chapter 16 of this report, was completed and generated physicals which provided a positive cashflow and net present value for the operation.

15.9 Mineral Reserve Estimate Compared to Expanded Feasibility Study

The difference between the Mineral Reserve estimate and the total quantities mined in the Expansion Feasibility Study is due to the slightly differing start dates. The Expansion Feasibility Study commences on 1st May 2026; however the Mineral Reserves are declared at the slightly later date of June 30th, 2026.

The Expansion Feasibility Study mines a total of 47.3mt from the pit, whereas the Mineral Reserve Estimate (pit only) is 47.0mt.



Figure 15-4: Final Pit – Plan View




Figure 15-5: Final Pit – Isometric View

For personal use only

For personal use only

16 Mining Methods

The open pit will be mined using conventional drill-blast-load-haul methods, with 10m bench heights installed for delivery of run-of-mine (ROM) ore from the open pit to the stockpiles or crusher. The Project has been operational since November 2022 using the same mining practices. Historical underground openings are within the proposed open pit and mining in these areas will take place in the near term, necessitating particular consideration in detailed mine planning and operations.

The NAL final pit design, as shown in Figure 16-1, was based on a pit optimization assessment which determined the economic limits of the deposit. The in-pit haul road has been designed on the hanging wall side of the deposit to maximise ore recovery within the pit shell, provide more direct access to the waste storage facilities and ROM and to provide access for the final mining pushback. The final pit reaches a maximum depth of approximately 380 m below topography.



Figure 16-1: NAL Final Pit Design

A life-of-mine plan for NAL has been developed based on the results of a pit optimization assessment and subsequent practical pit and stage designs. The life-of-mine schedule undergoes multiple increases in the wet plant processing rate as summarised below:

- Initial daily processing rate of 3,780tpd through wet plant;
- Wet plant processing rate increased to 4,354tpd on 1st July 2027;
- Wet plant processing rate increased to 4,500tpd on 1st January 2028;
- Wet plant processing rate increased to 6,100tpd on 1st April 2028;
- Wet plant processing rate increased to 6,500tpd on 1st October 2028.

An ore sorter is added to the processing circuit on July 1st, 2029. The ore sorter has an annual capacity of 1.1mt per annum and is fed the lowest quality and most diluted ore for pre-treatment prior to processing through the wet plant. The ore sorter rejects 90% of the waste and dilution contained

For personal use only

within the ROM ore, whilst recovering 90% of the contained Li_2O. More information on the ore sorter can be found in Section 16.4.6.

To accommodate the increase in wet plant throughput and the addition of an ore sorting circuit, the ore mining rate from the pit is limited to 5,100 tonnes per day annual average until April 1, 2028, gradually increasing up to a maximum of approximately 7,000 tonnes per day annual average. The life-of-mine schedules only mine Resources classified as Indicated, with no Inferred Resources mined. The deposit contains no Measured Resources.

This chapter provide an overview of the key assumptions used in the pit optimization assessment, the development of the practical pit shell and completion of the life-of-mine schedule for the Mineral Reserves PFS.

16.1 Pit Optimization

Pit optimization is the process which calculates the ultimate economic and practical pit limits of a deposit based on cost, revenue, processing and geotechnical assumptions. Pit optimization generates a surface which defines the economic limits for the deposit. The surface generated by the pit optimization process is used as a guide for the design of the final detailed pit shell.

Pit optimization is run over a range of scenarios where the revenue factor varies for each scenario. For each scenario, the revenue factor is multiplied by the forecast sale price for the concentrate produced. The scenarios which utilise a low revenue factor (i.e. 50%) highlight areas within the deposit that are the most profitable, as these areas generate an economic pit even with revenues reduced. The high revenue factor scenarios (i.e. 150%) highlight areas for potential future growth if commodity prices increase in the future. The high revenue factor scenarios provide guidance on where infrastructure such as the mining industrial area, tailings storage facilities, etc. should be located. This reduces the likelihood of having to relocate infrastructure at a later date if commodity prices increase.

Pit optimization is undertaken assessing the operating cost of the operation only, with capital costs excluded. The resultant economic pit shell must generate enough free cash to pay for all foreseeable capital outlays. Pit optimization was carried out at NAL on the diluted mining block model using the Whittle mining planning software package. Inferred and unclassified resources were converted to waste as part of the pit optimization assessment.

The following sections summarize the pit optimization which was undertaken.

16.1.1 Optimization Inputs

The inputs for the pit optimization process are presented in Table 16-1.

Table 16-1: Open Pit Optimization Parameters

Parameters	Unit	Value	Comments
Revenue			
Concentrate price	USD/t of conc.	1,250	For 6% spodumene concentrate (US$1,125 for 5.40%)
Concentrate grade	% Li_2O	5.40%	
Transportation cost	CAD/t of conc.	126.23	
Royalty		0%	
Economics			
Currency	CAD	-	
Exchange rate	USD/CAD	0.74	
Discount rate	%	8.0%	

For personal use only

Parameters	Unit	Value	Comments
Cost Basis			
Mining			
Mining cost	CAD/t mined	9.22	2025 budget mining cost and mining contractor costs (inclusive of attribution of G&A cost of 0.72/t mined)
Incremental mining cost	CAD/t/10m	0.03	Additional cost per tonne for every 10 vertical metres below RL400 (to take into account additional haulage).
Processing and G&A			
Processing	CAD/t milled	51.44	Inclusive of 41.58 processing cost and 9.86 G&A/SIBC (attribution of 5.34 G&A, 4.52 SIBC)
General G&A	CAD/t milled	4.68	
Operating Parameters			
Ore production	Mtpa	1.36	Average ore production sent to the crusher
Overall recovery	%	69.2%	
Geotechnical			
Overburden (IRA)	degree	26.6	Golder-WSP Memo Feb. 2023
Rock	degree	Variable	Golder-WSP Memo Feb. 2023

Overall pit slopes were based on the parameters developed by Golder Associates. The overall pit slopes were lowered slightly after preliminary runs to include allowances for haulage ramps and geotechnical berms. The overall slope angle varied depending on the geotechnical region, as shown in Figure 16-2.




Figure 16-2: Geotechnical Regions

The overall slope angles are shown in Table 16-2. Revenue factors were applied to evaluate the sensitivity of the pit size versus selling prices, varying from 0.5 to 1.0 in 0.025 increments.

For personal use only

Table 16-2: Open Pit Optimization Slope Angles

Region	Units	Overall Slope Angle
GEOT_11	degs	44.9
GEOT_12	degs	47.6
GEOT_13	degs	49.0
GEOT_14	degs	41.5
GEOT_15	degs	41.1
GEOT_16	degs	42.6
GEOT_24	degs	32.1
GEOT_25	degs	33.9

16.1.2 Optimization Results

As described in the previous chapter, pit optimization calculated the final economic pit shell based on given financial parameters, processing assumptions and pit slopes that results in the maximum undiscounted value for a specific revenue factor.

Table 16-3 presents the results of the pit optimization in table form, while Figure 16-3 presents the results in graphical format. The values returned by the pit optimization model do not include capital investments as the cashflow generated within the pit shell must be large enough to cover all foreseeable capital outlays.

The revenue factor 0.95 pit shell, where realized prices are 95% of the forecast price, was selected as a guide for the final pit design. The selection of this revenue factor shell was based on maximizing project ore tonnes mined while respecting a relatively high $NPV_{8\%}$.

Table 16-3: Pit Optimization Results

Revenue Factor	Ore Tonnes (mt)	Ore Li_2O Grade (%)	Waste Tonnes (mt)	Strip Ratio (t:t)	Total Cost (M$CAD)	Total Revenue (M$CAD)	Total Cashflow (M$CAD)
0.500	0.8	1.26%	1.2	1.49	$62	$183	$121
0.525	1.1	1.24%	1.8	1.66	$83	$234	$151
0.550	1.5	1.21%	3.0	1.99	$121	$322	$201
0.575	2.0	1.18%	4.4	2.21	$166	$419	$252
0.600	2.5	1.16%	6.2	2.45	$217	$520	$303
0.625	3.3	1.14%	9.3	2.79	$301	$678	$377
0.650	7.5	1.13%	29.3	3.92	$772	$1,498	$726
0.675	14.5	1.13%	68.8	4.75	$1,636	$2,916	$1,279
0.700	17.2	1.13%	85.3	4.95	$1,985	$3,462	$1,476
0.725	21.0	1.12%	108.0	5.15	$2,465	$4,184	$1,719
0.750	27.9	1.11%	151.8	5.44	$3,375	$5,494	$2,118
0.775	29.4	1.10%	161.4	5.49	$3,574	$5,770	$2,197
0.800	31.5	1.10%	176.0	5.59	$3,861	$6,150	$2,289
0.825	42.4	1.08%	256.7	6.05	$5,428	$8,158	$2,730
0.850	44.1	1.08%	270.4	6.13	$5,687	$8,472	$2,785
0.875	45.0	1.08%	277.8	6.17	$5,872	$8,637	$2,810
0.900	49.2	1.08%	321.4	6.53	$6,572	$9,465	$2,893
0.925	49.9	1.08%	327.6	6.56	$6,686	$9,588	$2,903
0.950	50.8	1.08%	335.5	6.61	$6,826	$9,737	$2,910
0.975	51.2	1.08%	340.0	6.64	$6,905	$9,816	$2,911
1.000	53.4	1.08%	368.3	6.90	$7,359	$10,257	$2,898

For personal use only

As Table 16-3 indicates, the 0.95 revenue factor shell contains 50.8mt of ore and 335.5mt of waste. However, these values are calculated as part of the pit optimization process which generates an evenly spaced grid of the economic pit shell for each scenario. Conversion of the economic pit shell grid from pit optimization to a practical pit design, which contains all required ramps, berms and benches, usually results in an increase in the strip ratio of the pit incurred by either a reduction in ore tonnes or an increase in waste tonnes or both.




Figure 16-3: Pit Optimization Results

16.2 Mining Method

The Project will be mined using conventional open-pit drill-blast-load-haul methods, with 10m bench heights installed for delivery of ROM ore from the open pit to the stockpiles or crusher. The Project has been operational since November 2022 using the same mining practices. Historical underground openings are within the proposed open pit and mining in these areas will take place in the near term, necessitating particular consideration in detailed mine planning and operations.

16.3 Geotechnical Consideration

16.3.1 Planning Around Underground Workings

Based on the current understanding of the geometries and locations of the existing underground openings in relation to the pit shell, all of these underground openings are contained within the final pit shell and will not intercept the final pit wall. Local modifications to the slope design may be required to enable safe and stable excavations in areas where stopes intersect the pit wall or floor, or drifts that run parallel to the pit wall.

For personal use only

Approximately 90% of the underground solids are contained within phase 3, which is currently being excavated. Figure 16-4 shows the location of the underground solids with phases 4 to 8 inclusive shown.



Figure 16-4: Underground Solids with Phases 4 to 8 (Phases 1 to 3 Removed)

The historical underground openings represent an operational hazard, a risk to local bench-scale and multi-bench stability and a potential rockfall hazard, depending on the character of the openings and any backfill. Systematic investigation and mitigation design will be required to manage these risks for both interim and final pit walls. Investigation and evaluation of these hazards, and design of mitigation, are currently underway by Alius and ASAGeotech for Elevra and will be continued through the operating life of the mine. Site has developed multiple Safe Operating Procedures (SOPs) to manage the risks associated with mining adjacent to voids. Significant mining around underground workings has been undertaken in the past two years, with no incidents being reported.

16.3.2 Operational Considerations

Good quality operational practices will be essential for the safe development of stable and steep slopes. The slope design recommendations based on pre-split blasting assume that a workforce and supervisors skilled in implementing effective, controlled blasting and excavation procedures will be available throughout the mining operations. Optimized controlled blasting designs should be developed early in the mine life for use on long-term and final slopes. Blasting experience and trials should be developed and optimized in the interior of the open pit prior to applying it to the final slopes.

16.4 Pit Design Parameters

16.4.1 Block Models

The geological basis for the study is the Resource block model, a Datamine block model titled *2025 BM_20250814.dm*, which was used for the June 6, 2025, Mineral Resource estimate. 5m x 5m x 5m parent cells were sub-blocked four times in each direction (minimum sub-block of 1.25 m in each direction). Sub-blocks are triggered by both the geological model and mining voids, for precise

For personal use only

depletion. This model has proportional sub-blocks to cover the spaces inside the solid boundaries. The size of the sub-blocking was chosen to best match the thickness of the mineralized dykes and the complexity of the geological model. The block model parameters and prototype values are shown in Table 16-4 and Table 16-5 respectively.

Table 16-4: Block Model Parameters

Item	Value
Name	2025 BM_20250814.dm
File Size	18.4 GB
Number of Records	72,316,300
File Format	.dm (Datamine)
Date Generated	2025-08-14

Table 16-5: Block Model Prototype

Item	X (UTM)	Y (UTM)	Z (UTM)
Min. Extent	290216.2364499186	5363260	-360.00
Maximum Extent	295035.1780949428	5367887.2772690365	490.00
Largest (parent) cell	5	5	5
Smallest sub cell	1.25	1.25	1.25
No. of Parent Cells	515	826	170
Rotation	-	-	310 degs

Each cell in the block model was allocated a material type based on the geological zone of the cell. Material types were either overburden, pegmatite, volcanics, gabbro, granodiorite or voids (for underground voids). Each material type was allocated a density, an Li_2O grade and an Fe grade as shown in Table 16-6.

Table 16-6: Material Properties

Material	Density (t/m^3)	Li_2O (%)	Fe (%)
Pegmatite	2.70	As modelled	As modelled, else 0.29%
Overburden	2.00	0%	0%
Volcanics	3.01	0%	5.72%
Gabbro	3.11	0%	6.68%
Granodiorite	2.77	0%	2.30%

16.4.2 Pit Wall Parameters

Detailed mine designs were carried out using the selected 0.95 revenue factor pit shell from the pit optimization process as a guide. The pit design parameters are detailed in Table 16-7.

Table 16-7: Ultimate Pit Design Parameters

Design Sector	Wall Dip Direction		Bench	Catch Bench	Bench Face	Inter-Ramp	Geotechnical
	From	To	Height (m)	Width (m)	Angle (deg)	Angle (deg)	Berm Interval (m)
Overburden*	0	360	N/A	9	26.6	N/A	N/A
South	355	35	20	16	60.0	45.7	120
Northeast	195	270	20	10	65.0	49.1	120
Northwest	35	195	20	10	70.0	52.6	120
Southeast	270	355	20	10	70.0	52.6	120

Note: A 7 to 9 m setback considered at bedrock contact, depending on various factors listed in section 2.4.2 of the WSP-Golder memorandum (22515754-166-MTF-RevB).

16.4.3 Ramp Design Parameters

The proposed pit design includes the practical geometry required in a mine, including pit access and haulage ramps to all pit benches, pit slope designs, benching configurations, smoothed pit walls and catch benches.

The haulage fleet operated by the mining contractor utilizes 90t capacity haul trucks, with ramps and access roads designed to accommodate this class of truck. Table 16-8 presents the haul road design parameters. This is also shown graphically in Figure 16-5 and Figure 16-6 for in-pit single- and dual-lane haul ramps, respectively.

The haul and ramp design parameters used in the generation of the ultimate pit shell, and all phases are summarized in Table 16-8.

Table 16-8: Haul Road Design Criteria

Parameters	Units	Dual Lane	Single Lane	Comments
Reference Haul Truck	-	90T-class	90T-class	Largest haul truck expected for the NAL project
Operating Width	(m)	6.7	6.7	Includes clearance for mirrors and accessories
Running Surface Multiplier	(factor)	3.0	1.9	Minimum value for adequate clearance
Running Surface Width	(m)	20.0	12.5	For temporary and permanent roads
Tire Diameter	(m)	2.7	2.7	For 27.00 R49 tires
Berm Height: Tire Ratio	(ratio)	0.5	0.5	Minimum recommended value
Berm Height	(m)	1.3	1.3	For temporary and permanent roads
Berm slope xH:1V Ratio	(ratio)	1.3H:1.0V	1.3H:1.0V	Angle of Repose 37.5
Berm Width (Top)	(m)	0.5	0.5	Minimum recommended value
Berm Width (Bottom)	(m)	4.0	4.0	For temporary and permanent roads
No. of Berms - Surface Road	(#)	2.0	2.0	Industry standard practice
No. of Berms - Pit Ramp	(#)	1.0	1.0	Industry standard practice
No. of Berms - Pit Slot	(#)	0.0	0.0	Industry standard practice
Ditch Depth	(m)	0.8	0.5	For temporary and permanent roads
Ditch slope xH:1V Ratio	(ratio)	1.0H:1.0V	1.0H:1.0V	Maximum recommended value
Ditch Width (Bottom)	(m)	0.5	0.5	Minimum recommended value
Ditch Width (Top)	(m)	2.0	1.5	For temporary and permanent roads
No. of Ditches - Surface Road	(#)	0.0	0.0	Industry standard practice
No. of Ditches - Pit Ramp	(#)	1.0	1.0	Industry standard practice
No. of Ditches - Pit Slot	(#)	2.0	2.0	Industry standard practice
Overall Width - Surface Road	(m)	28.0	20.5	For temporary and permanent roads
Overall Width - Pit Ramp	(m)	26.0	18.5	For temporary and permanent roads
Overall Width - Pit Slot	(m)	24.0	15.5	For temporary and permanent roads
Maximum Grade - Permanent Road	(%)	10.0	10.0	Maximum recommended value
Maximum Grade - Temporary Road	(%)	12.0	12.0	Maximum recommended value
Haul Road Drainage Crossfall	(%)	2.0	2.0	For temporary and permanent roads

For personal use only




Figure 16-5: Single-Lane in-Pit Haul Ramp Design




Figure 16-6: Dual-Lane in-Pit Haul Ramp Design

For personal use only

16.4.4 Final Pit Design

The final pit was designed with one main haul road servicing the entire pit for the life of the mine. The decision to utilise one main haul road was chosen based on reducing the strip ratio, pit shell disturbance area and operating cost for the operation. An additional haul road would have added significant additional waste stripping.

The main haul road has been designed on the hanging wall side of the deposit to maximize ore recovery within the pit shell and to provide access for the final mining pushback. Blasting and excavation around the main haul road must be carefully executed as any geotechnical issue with the main haul road will cause significant disruptions and issues for all levels below the geotechnical issue. Scaling of the final wall and other stabilizing methods should be implemented as the main haul road is progressively extended.

A secondary haul road has been designed along the south-west limit of the pit to access phase 8, one of the last phases to be mined. The secondary haul road to phase 8 is used by the upper levels of some of the phases.

Figure 16-7 and Figure 16-8 show the final pit design in plan view and isometric view respectively.



Figure 16-7: Final Pit – Plan View

For personal use only

For personal use only



Figure 16-8: Final Pit – Isometric View.

As Figure 16-8 shows, the pit is serviced by one main haul road (black line) whilst an upper ramp services the phase 8 area located at the southern end of the operation. Both haul roads exit the pit at the same pit located in the north-west corner of the operation. The exit point is the closest location to the ROM area and also the main haul road to the waste dumps.

Some waste which is hauled to the central and southern sections of the HS4 waste dump (located adjacent to the pit) may exit the pit at the point highlighted by the “X” in Figure 16-8. This exit point provides a shorter haulage distance between the pit and the dump location.

Figure 16-9 shows a cross section through the deposit, showing the final pit design and the resource block model cells.




Figure 16-9: Final Pit Cross Section with Resource Block Model

As Figure 16-9 indicates, the resource block model contains variable sized blocks, with sub-cells down to 1.25m x 1.25m x 1.25m used around the modelled pegmatites. The stringy nature of the Li_2O-containing pegmatites can be seen clearly in the cross section. The cells are colour coded by Li_2O grade, with red (2.4%) and light cyan (0.6%) representing the limits of the ore cells.

Figure 16-9 also shows that several pegmatites have been modelled but contain Li_2O values below the cut-off grade of 0.60% Li_2O, or the pegmatite contains material classified as Inferred and has therefore not been included in the mined pegmatite quantities.

16.4.5 Material Flow Diagram

Figure 16-10 shows the simplified flow of material from the mine and to the possible final destinations: the waste dumps, the tailings storage facilities or concentrate.

ROM waste material is drilled and blasted before being excavated and hauled to the waste dumps. ROM ore material is also drilled and blasted before being mined by excavators and hauled out of the pit. The ROM ore is either placed on the ore sorter stockpile or the direct feed ROM stockpile.

ROM ore that is sent to the ore sorting circuit is processed with the product material reporting to the ROM stockpile, whilst the reject material is trucked to the waste dumps. The ore sorter rejects are usually high quality, crushed and sorted materials that are suitable for road surfaces and also blast stemming. This material may be stockpiled and used in a strategic manner if required. For this study, it has been assumed that the ore sorter reject material is hauled and stored in the waste dumps.

For personal use only

For personal use only




Figure 16-10: Material Flow Diagram

16.4.6 Modifying Factors

16.4.6.1 Metallurgical Recoveries

As Figure 16-10 shows, ore is either fed directly to the plant or sent to the ore sorting circuiting prior to processing. The poorest quality ore with the lowest Li_2O grade or highest dilution is sent to the ore sorter, however this is dependent on stockpile inventories and the quality of the ore being mined and on the stockpiles.

The assumptions and metallurgical factors for the material sent to the ore sorting circuit are summarised below:

- Annual ore sorting capacity - 1.1mt per annum

For personal use only

- % of ore sorter feed to ore sorters - 75%
- % of ore sorter feed sent to ROM stockpile (fines) - 25%
- % of ore sorter feed Li_2O recovered - 90%
- % of ore sorter waste/dilution removed - 90%

An example of the application of the above assumptions through the ore sorting circuit is provided below for a mined block with the following arbitrary values:

- Mined block total tonnes - 128t
- Mined block pegmatite tonnes - 105t
- Mined block dilution tonnes - 23t
- Mined block total Li_2O grade - 0.98%
- Mined block contained Li_2O tonnes - 1.2544 (128t x 0.98%)

The values through the ore sorting circuit for the block above are summarised below:

- Tonnes sent to ore sorting circuit - 128t
- Tonnes sent to ROM stockpile (fines) - 32t (25% of 128t)
- Total tonnes sent for ore sorting - 96t (75% of 128t)
- Pegmatite tonnes sent for ore sorting - 78.75t (75% of 105t)
- Dilution tonnes sent for ore sorting - 17.25t (75% of 23t)
- Pegmatite tonnes recovered from ore sorter - 70.875 (90% of 78.75t)
- Dilution tonnes recovered from ore sorter - 1.725t (10% of 17.25t)
- Reject tonnes to waste dump - 23.4t (96t – 70.875t – 1.725t)

The final product from the ore sorting circuit is summarised below:

- Total product tonnes from ore sorter - 72.6t (70.875t + 1.725t)
- Total Li_2O product tonnes from ore sorter - 0.84672t (128t x 0.98% x75% x 90%)
- Total Li_2O product grade from ore sorter - 1.166% (0.84672t / 72.6t)

The final product placed on the ROM stockpile from the ore sorting circuit (fines plus ore sorter product) is summarised below:

- Total product tonnes to ROM stockpile - 104.6t (72.6t + 32t)
- Total Li_2O product tonnes to ROM stockpile - 1.16032t (0.84672t + 32t x 0.98%)
- Total Li_2O product grade to ROM stockpile - 1.109% (1.16032t / 104.6t)

Two recoveries have been applied for the plant:

- 69.2% Li_2O recovery prior to the plant upgrades,
- 71.2% Li_2O recovery after the plant has been upgraded.

Upgrades at the plant are forecast to be completed by 1st April 2028, at which point the plant is operating at 6,500t per day and Li_2O recovery is 71.2%.

For personal use only

16.4.6.2 Cut-Off Grade

The breakeven cut-off grade (COG) is calculated considering costs for processing, general & administration (G&A) costs, and other costs related to concentrate production and transport. Table 16-9 presents the parameters used to determine the mill COG.

Table 16-9: Cut-Off Grade Calculation Parameters

Parameter	Units	Value
Recovery	%	69.20%
Gross 6.0% Li_2O Price	USD/t conc.	1,250.00
Concentrate Transportation Cost	USD/t conc.	126.23
Royalties	USD/t conc.	0.00
Net 5.4% Li_2O Selling Price	USD/t conc.	1,125.00
Concentrate Grade	%	5.40%
Exchange Rate	USD/CAD	0.74
Processing Cost	CAD/t milled	41.58
Processing G&A and SIBC Cost	CAD/t milled	9.86 (5.34 G&A, 4.52 SIBC)
Calculated Cut-Off Grade	% Li_2O	0.29%
Metallurgical Cut-Off Grade	% Li_2O	0.60%

Based on a 5.40% Li_2O concentrate selling price of $1,250 USD/t, the COG would be 0.29% Li_2O. However, due to metallurgical recovery limitations, a metallurgical COG of 0.60% Li_2O was selected based on iterative analysis and to assure a feed grade that allows a sufficient metallurgical recovery to produce the required spodumene concentrate grade.

16.4.7 Main Pit Phase Designs

A series of six mining phases, numbered 3 through 8 inclusive, were developed including the ultimate pit design. Special attention was given to the historical underground openings when setting the physical limits for every phase. Consideration was taken to ensure that the phase walls did not intersect the old workings. The following criteria was applied during the phase design construction:

- Minimum mining width of 60m considered between phases on the surface and 40m at the phase base.
- Ease of access to different mining areas.
- Mining and processing production rate.
- Physical constraints posed by historical underground workings.

Table 16-10: Material Quantities by Phase

Item	Units	Total	Phase 3	Phase 4	Phase 5	Phase 6	Phase 7	Phase 8
Total In-Pit	(dMt)	385.2	30.0	54.8	56.5	48.0	180.8	15.1
Waste Rock	(dMt)	337.9	24.8	47.4	50.4	41.1	160.9	13.3
ROM Ore	(dMt)	47.3	5.2	7.4	6.2	6.9	19.9	1.8
Lithium Grade	(% Li_2O)	1.12%	1.15%	1.08%	1.06%	1.24%	1.11%	1.03%
Iron Grade	(% Fe)	0.8173%	0.8976%	0.8981%	0.8672%	0.7258%	0.7974%	0.7374%
Strip Ratio	(twaste : tore)	7.1	4.8	6.4	8.2	6.0	8.1	7.4

**Note: Totals may not add up due to rounding.*

Each of the phases was then subdivided into sub-phases to allow for a more detailed progressive development of the operation. The sub-phases developed were:

- Phase 3 - 3B and 3F,
- Phase 4 - 4A, 4B and 4F,
- Phase 5 - 5A, 5B, 5C, 5D and 5F,
- Phase 6 - 6A and 6F,
- Phase 7 - 7A and 7F,
- Phase 8 - 8F.

To show the design of each individual sub-phase, the starting topography with each of the sub-phases cumulatively cut out are presented in Figure 16-11 to Figure 16-26 respectively, including the starting position of the mine as of May 1st, 2026. It should be noted that Phases 1 and 2 plus 3A have been mined out previously.

For personal use only



Figure 16-11: Isometric View of Starting Position as of May 1st, 2026




Figure 16-12: Isometric View of Pit with Phase 3B Removed

For personal use only




Figure 16-13: Isometric View of Pit with Phases 3B to 3F Removed




Figure 16-14: Isometric View of Pit with Phases 3B to 4A Removed

For personal use only




Figure 16-15: Isometric View of Pit with Phases 3B to 4B Removed




Figure 16-16: Isometric View of Pit with Phases 3B to 4F Removed

For personal use only



Figure 16-17: Isometric View of Pit with Phases 3B to 5A Removed



Figure 16-18: Isometric View of Pit with Phases 3B to 5B Removed

For personal use only



Figure 16-19: Isometric View of Pit with Phases 3B to 5C Removed



Figure 16-20: Isometric View of Pit with Phases 3B to 5D Removed

For personal use only




Figure 16-21: Isometric View of Pit with Phases 3B to 5F Removed




Figure 16-22: Isometric View of Pit with Phases 3B to 6A Removed

For personal use only




Figure 16-23: Isometric View of Pit with Phases 3B to 6F Removed




Figure 16-24: Isometric View of Pit with Phases 3B to 7A Removed

For personal use only




Figure 16-25: Isometric View of Pit with Phases 3B to 7F Removed




Figure 16-26: Isometric View of Pit with Phases 3B to 8F Removed (Ultimate Pit)

For personal use only

For personal use only

16.4.8 Lortie Lake

Lake is a small lake located to the north of the current mining operations. The lake is very shallow with a maximum depth of 5m. Phases 3 to 5 inclusive have been designed to stay at least 60m from the lake edge. Phase 6 traverses the southern half of the lake and the phase 7 crest runs through the middle of the lake. The pit crests for phases 5, 6 and 7 relative to Lortie Lake are shown in Figure 16-27.

At full capacity, the lake holds 350,000 m^3 of water over an area of 12.4 hectares, which leads to an average depth of 2.2m. The lake drains to the north, away from mining operations and has a local catchment of 39 hectares.

The mine operating plan involves partial or complete drainage of the lake and the creation of waterways to regulate the natural flow of water around the final perimeter of the pit. Environmental and ecological studies were conducted in 2025, and additional studies are planned for 2026 to support the submission of an Environmental and Social Impact Assessment, which is expected to be reviewed by the BAPE and ultimately lead to the approval and extension of the mining lease covering mining phases 6 and 7.

For more information on the proposed Lortie Lake dyke, refer to Section 18.8 - Lortie Lake Dyke.




Figure 16-27: Lortie Lake Location

For personal use only

16.5 Life-Of-Mine Plan

The life-of-mine dig and dump designs were completed using Deswik.CAD. The life-of-mine schedule, including haulage modelling, was developed for the PFS using Micromine's Spry software package.

16.5.1 Dig Solids

Regularized three-dimensional dig solids 10m wide by 10m long by 5m high were drafted in Deswik.CAD across the entire deposit. The solids were then cut by each sub-phase to provide an initial set of dig solids for each sub-phase.

The quantity of waste and ore within each dig solid was calculated via an interrogation of the Resource block model (as described in chapter 16.4.1). The final ROM quantity of ore and waste, taking into account loss, dilution and cut-off grades, was calculated for each mining dig solid by a set of detailed formulas as described below:

1. If more than 30m^3 of ore exists in the dig solid, then consider the ore as potentially recoverable, otherwise (<30m^3 of ore) convert the entire solid to waste.
2. Allocate between 5% and 50% dilution depending on the percentage of ore in the block. Each 1% drop in ore percentage adds 0.3% dilution, up to a maximum of 50% dilution.
3. Allocate between 0% and 30% loss depending on the percentage of ore in the solid. Each 1% drop in ore percentage adds 0.3% loss, up to a maximum of 30% loss.
4. Obtain the diluting rock type (i.e. volcanics, gabbro, granodiorite or overburden) and subsequent Li_2O, Fe and density parameters.
5. Add the dilution quantities and qualities to the ore component of the solid based on the percentage dilution calculated (step 2) and the diluting material properties (step 4).
6. Remove the loss quantities and qualities from the ore component of the solid based on the percentage loss calculated (step 3).
7. Calculate the final ore quantities and qualities (original values less losses plus dilution).
8. If the Li_2O percentage of the final ore quantity is less than 0.60% (the assigned cut-off grade) then convert the ore component to waste.
9. Assign a final ROM material to the block – a block with any ore is allocated "ORE" with all others allocated as "WASTE".

As the above formulas indicate, a smallest mining unit (SMU) of 30m^3 has been assigned for ore mining. This represents approximately one truckload of ore. The final dig solids with a ROM material of "ORE" can contain mineable quantities of both ore and waste, whereas "WASTE" material only contains waste material.

16.5.2 Waste Dump Designs

The site currently utilizes two existing waste dump areas named HS-2 and HS-3 for the storage of waste rock mined from the pit. These two areas will continue to be used for waste storage along with three additional waste dump areas:

- HS4 - the largest waste rock pile area located between the pit and TSF1,
- TSF2 wall - the bulk material for tailing storage facility 2 (TSF2) located on the western side of the operation,

For personal use only

- TSF3 wall - the bulk material for tailings storage facility 3 (TSF3) located to the south of HS4.

The location of all current and proposed waste and tailings storage facilities are shown in Figure 16-28.




Figure 16-28: Waste Dump and Tailings Storage Facility Locations

Geotechnical slope stability recommendations were provided by Golder. Current dump designs were adjusted according to the recommendations included in this report and the ongoing geotechnical campaign data.

A swell factor of 30% was applied to all waste rock material to calculate waste storage requirements.

Permits for current non-permitted areas (HS-4, TSF-2 and TSF-3) are expected to be granted prior to the planned commencement dates. With exception of TSF 1 and 2, it should be noted that all proposed dumps and tailings facility shown above are conceptual at this stage, with final location and designs to be completed after approvals have been gained.

TSF-1 is currently in operation and the footprint of the TSF-2 has already been approved by Fisheries and Oceans Canada (DFO). The TSF-2 design, presented in the following chapters, will remain within the approved footprint. For HS-4 and TSF-3, a variants analysis will confirm the location of these two facilities. These infrastructure components will be optimized in the next studies of the project.

16.5.3 Waste Dump Solids

All waste designs shown in the previous chapter were converted to a solid and then subdivided into 100m x 100m x 10m high solids in Deswik.CAD. The subdivided solids were then imported into Spry for use in the dump scheduling component of the life-of-mine plan.

16.5.4 Dig Schedule Strategy

The schedule utilised two stages of capital investment which gradually increased the processing production rate up to 6,500 tonnes per day. The dates and subsequent increase in processing rate are summarised below:

- Initial production rate - 3,780 tonnes per day
- Stage 1 - 4,500 tonnes per day from 1st July 2027
- Stage 2 - 6,500 tonnes per day from 1st April 2028

Additionally, an ore sorting circuit comes online on 1st July 2029 with a throughput of 1.1mt per annum.

The life-of-mine dig schedule strategy was based on the following:

- Ensure target plant throughput (3,780tpd to 6,500tpd) is achieved each year,
- Target the lowest strip ratio areas to achieve the required ore tonnes, and
- Ensure stockpile inventories remain at manageable levels.

16.5.5 Mining Processes

Nine mining and two processing processes were established in Spry to provide a detailed life-of-mine schedule that included all major operations. The processes included in Spry life-of-mine model are:

1. Drill Presplit (114mm holes)
2. Load and Fire Presplit Blast
3. Drill Ore (140mm holes)
4. Drill Waste (171mm holes)
5. Load Explosives
6. Fire Production Blast
7. Mine Waste
8. Mine Ore
9. Rehandle Material Off Stockpiles
10. Dispose of Ore Sorter Rejects
11. Dispose of Tailings from Plant

For personal use only

16.5.6 Equipment

Equipment to undertake the processes summarised in the previous chapter were established in Spry. The selection of the equipment types and classes was based on current equipment operating at site, the availability of equipment in the local area, ongoing support and physical suitability for the NAL operation. Large 200t excavators were added to the fleet to assist with maintaining the required stripping quantities. The equipment utilised in the life-of-mine schedule, grouped into general classifications, are summarised below:

- Drill and Blast:
  - Presplit drill (114mm holes)
  - Ore drill (141mm holes)
  - Waste drill (171mm holes)
  - Blast crew
- Mining:
  - PC800 excavator (80t class)
  - PC1250 excavator (125t class)
  - PC2000 excavator (200t class)
- Processing:
  - Ore sorter
  - Processing plant
  - Loader (for ROM ore feed and ore sorter rejects)
  - Tailings disposal

The PC2000 excavators are limited to mining waste only, whilst all other excavators can mine waste and ore. All ore is dumped on a stockpile at the ROM before being rehandled into the plant or ore sorter crushing units at a later date.

16.5.6.1 Time Usage Models

For all pieces of equipment, the number of operating hours is controlled by availability and utilisation values assigned each month in the time usage model established in Spry. The following availability and utilisation values have been applied, with the subsequent number of operating hours per non-leap year also shown:

- Drills:
  - 78% availability,
  - 65% utilisation,
  - 4,441 operating hours per annum
- 200t and 125t class excavators:
  - 78% availability,
  - 80% utilisation,
  - 5,466 operating hours per annum
- 80t class excavators:
  - 78% availability,
  - 75% utilisation,
  - 5,125 operating hours per annum

For personal use only

16.5.6.2 Production Rates

For all pieces of equipment, the production rate achieved for every operating hour has been hardwired for each process undertaken by the equipment. The production rates for the mining equipment is summarised below:

- Presplit drills (114mm holes) - 50m per operating hour
- Ore drills (140mm holes) - 50m per operating hour
- Waste drills (171mm holes) - 65m per operating hour
- Blast crew - 50t of explosives per day
- 200t class excavators - 310bcm per operating hour
- 125t class excavators - 180bcm per operating hour
- 80t class excavators - 142bcm per operating hour

16.5.7 Mining Dependencies

A suite of dependencies was created in Spry to ensure a safe and practical schedule is generated. The dependencies control the progression of the equipment by limiting the number of tasks available to the equipment at the conclusion of a task.

The primary dependencies created in Spry are summarised below:

- Block Above:
  - the dig block directly above must be completed first (no undermining)
- Process Order:
  - the processes in each block must be completed in order (i.e. drilling before blasting before mining)
- Previous Sub-Phase:
  - the block directly in front of the current block (in the previous sub-phase) must be mined first (no funnelling down)
- Develop Out From Ramp:
  - each bench is developed radially out from the ramp mouth

16.5.8 Mining Constraints

Similar to dependencies, a range of constraints to control the progression of the equipment. The constraints controlled two primary aspects of the schedule: the proximity of the equipment (ensuring each piece of equipment did not operate too close to other equipment) and the maximum tonnage mined in a given period.

In general, the proximity constraints ensure that:

- Each excavator is at least 100m away from any other excavator at all times, and
- A maximum of 3 excavators are operating in phase at any one time, except for phase 7a (which is very large) where up to 4 excavators are permitted.

For personal use only

For personal use only

16.5.9 Schedule Results

All dig solids and dump solids were imported into Spry for dig and dump scheduling. Haulage modelling was also completed to provided annual truck hours for both waste and ore haulage. The quantities of tailings placed in the tailings storage facilities were also included in the LOM schedule, to provide accurate planning for the development of new tailings storage facilities and wall lifts.

The key highlights of the LOM plan are summarized below:

- Mine life of approximately 20 years – from May 2026 to September 2046.
- Total of 47.3mt of ore mined.
- Total of 337.9mt of waste mined, leading to an overall strip ratio of 7.14:1, which fluctuates over the years.
- 17.7mt of ore sent to the ore sorting circuit at an average grade of 0.96% Li_2O and 1.00% Fe.
- 14.4mt of product from the ore sorter at an average grade of 1.08% Li_2O and 0.69% Fe.
- 44.0mt of ore sent to the processing plant at an average grade of 1.17% Li_2O and 0.66% Fe.

Figure 16-29 shows the annual tonnes processed through the plant and the Li_2O feed grade.




Figure 16-29: Annual Processed Tonnes and Li_2O Grade

As Figure 16-29 indicates, the target production rate of 6,500 tonnes per day (2.37mt per annum) is achieved every year from FY2029 onwards.

A summary of the LOM plan is presented in Table 16-11 and Figure 16-30 to Figure 16-31 on the following pages.

Isometric views showing progression of the LOM schedule, including dig faces, dump faces and tailings dam utilisation, are presented in Figure 16-32 to Figure 16-43 on the following pages.

Table 16-11: NAL LOM Production Plan and Material Movement

Physicals	Units	Production									Total
		FY26	FY27	FY28	FY29	FY30	FY31-FY35	FY36-FY40	FY41-FY45	FY46-FY49	
Ore											
Ore Tonnes	(Mt)	0.28	1.61	1.77	2.34	2.63	13.00	12.68	12.80	0.21	**47.33**
Ore Li_2O Grade	(%)	0.94%	1.02%	1.06%	1.09%	1.10%	1.13%	1.10%	1.17%	1.02%	**1.12%**
Ore Fe Grade	(%)	1.22%	1.00%	1.01%	0.91%	0.89%	0.81%	0.84%	0.71%	0.76%	**0.81%**
Waste											
Waste Tonnes	(Mt)	2.2	14.0	17.9	19.6	21.0	118.0	107.1	37.5	0.7	**337.9**
Strip Ratio	(t:t)	7.6	8.7	10.1	8.3	8.0	9.1	8.4	2.9	3.4	**7.1**
Processing											
Feed Tonnes Processed	(Mt)	0.21	1.38	1.77	2.34	2.37	11.9	11.9	11.9	0.4	**44.05**
Feed Li_2O Grade	(%)	1.02%	1.08%	1.06%	1.08%	1.17%	1.20%	1.15%	1.23%	0.95%	**1.17%**
Feed Fe Grade	(%)	0.84%	0.78%	0.83%	0.78%	0.71%	0.61%	0.66%	0.62%	0.67%	**0.66%**
Product Li_2O	(t)	1,488	10,307	13,274	17,974	19,843	101,662	97,288	103,606	2,504	**367,947**
Concentrate Tonnes	(t)	27,560	190,876	245,820	332,859	367,465	1,882,635	1,801,626	1,918,623	46,373	**6,813,837**

personal use only

For personal use only




Figure 16-30: NAL Ore Mining Summary




Figure 16-31: NAL Total Movements



Figure 16-32: Conceptual Isometric View of Mine as of 1st May 2026



Figure 16-33: Conceptual Isometric View of Mine as of 1st July 2026

For personal use only



Figure 16-34: Conceptual Isometric View of Mine as of 1st July 2028



Figure 16-35: Conceptual Isometric View of Mine as of 1st July 2030

For personal use only




Figure 16-36: Conceptual Isometric View of Mine as of 1st July 2032




Figure 16-37: Conceptual Isometric View of Mine as of 1st July 2034

For personal use only




Figure 16-38: Conceptual Isometric View of Mine as of 1st July 2036




Figure 16-39: Conceptual Isometric View of Mine as of 1st July 2038

For personal use only




Figure 16-40: Conceptual Isometric View of Mine as of 1st July 2040




Figure 16-41: Conceptual Isometric View of Mine as of 1st July 2042

For personal use only




Figure 16-42: Conceptual Isometric View of Mine as of 1st July 2044




Figure 16-43: Conceptual Isometric View of Mine as of 1st October 2045 (end of mining)

For personal use only

16.6 Key Dates

A series of key dates from the schedule is provided in Table 16-12.

Table 16-12: Key Dates

Item	Start Date	Finish Date
Mining Phases		
Phase 3B	1/05/2026	1/06/2029
Phase 3F	19/05/2026	13/07/2030
Phase 4A	1/07/2026	15/08/2031
Phase 4B	13/03/2031	17/08/2031
Phase 4F	31/08/2027	13/03/2034
Phase 5A	21/07/2027	9/01/2031
Phase 5B	9/01/2031	24/01/2031
Phase 5C	13/12/2030	14/12/2031
Phase 5D	25/09/2031	4/07/2034
Phase 5F	4/04/2034	10/07/2037
Phase 6A	1/01/2030	1/08/2036
Phase 6F	24/02/2036	2/09/2038
Phase 7A	28/01/2030	28/03/2040
Phase 7F	14/09/2032	26/07/2045
Phase 8F	24/08/2033	3/09/2045
Waste Dumps		
HS2	1/05/2026	9/11/2028
HS3	22/08/2028	3/09/2045
HS4	18/06/2031	12/07/2043
TSF1		
Tailings Deposition	1/05/2026	14/11/2029
TSF2		
Dam Wall	4/01/2028	9/07/2042
Dam Wall RL410 Lift	4/01/2028	11/06/2028
Dam Wall RL421 Lift	8/03/2031	19/06/2031
Dam Wall RL432 Lift	20/11/2033	23/02/2034
Dam Wall RL443 Lift	2/10/2036	20/12/2036
Dam Wall RL454 Lift	20/07/2039	31/10/2039
Dam Wall RL465 Lift	18/04/2042	9/07/2042
Tailings Deposition	14/11/2029	24/03/2044
TSF3		
Dam Wall	20/07/2032	19/08/2044
Dam Wall RL384 Lift	20/07/2032	22/07/2032
Dam Wall RL394 Lift	22/07/2032	9/08/2032
Dam Wall RL404 Lift	24/05/2044	19/08/2044
Tailings Deposition	24/03/2044	3/09/2045

16.7 Mining Activities

To achieve minimal mining dilution and ore losses, mining operations must follow specific procedures, depending on the width and physical properties of the Li_2O-containing pegmatite. Grade control drilling will assist with resource definition and the reduction of both losses and dilution.

The mining direction for ore and waste mining when exposing the dykes should be into the dip of the dyke, as shown in Figure 16-44.

For personal use only




Figure 16-44: Section View of Mining Method

16.7.1 Drilling and Blasting

Typical blast patterns for pre-split, ore material and waste rock material are described in

Table 16-13 and are currently implemented on site. Blasting parameters will constantly be adjusted as mining progresses in the pit according to the geotechnical properties of the rock and dyke configuration. Pre-split is undertaken on ultimate pit walls, using prepackaged emulsion. Pre-split holes are drilled on double bench height (20 m) and have a 114mm diameter.

Waste rock material is excavated in 10m benches, while ore is mined on flitches of 5 m or less, where operational considerations allow.

Table 16-13 Standard Blast Patterns

Description	Units	Pre-Split	Ore Pattern	Waste Pattern
Bench Height	m	20.0	10.0	10.0
Hole Diameter	mm	114.0	140.0	171.0
Hole length	m	20.0	9.0	9.0
Burden	m	-	2.8	3.4
Spacing	m	1.6	5.1	6.8
Collar	m	-	2.5	3.0
Sub-drilling	m	-0.6	-1.1	-1.0
Powder Factor	kg/m3	-	0.5	0.5

For personal use only

For personal use only

16.7.2 Haulage Assumptions

Haulage modelling assumptions were configured in Spry for each excavator class in the fleet, with trucking parameters assigned per dig unit and material process. All excavators were allocated Caterpillar 777G Dual Slope rear dump trucks, with loading times varying by excavator size and dig rates reflecting the productivity of each class. Trucking and haulage assumptions are shown in the following tables.

Table 16-14: Trucking Assumptions by Excavator

Item	Process	Dig Rate (bcm/hr)	Truck Payload (bcm)	Loading Time (min)	Dumping Time (min)	Queue Time (min)	Additional Time (min)	Efficiency Factor
200t	Waste	310	33	4.0	1.5	0.0	2.0	0.95
200t	Ore	315	33	4.0	1.5	0.0	2.0	0.95
PC1250	Waste/Ore	180	33	6.9	1.5	0.0	2.0	0.95
PC800 Ore	Ore	142	33	8.7	1.5	0.0	2.0	0.95
PC800 Waste	Waste	142	33	8.7	1.5	0.0	2.0	0.95

Table 16-15: Caterpillar 777G Truck Specifications

Parameter	Unit	Value
Truck model	-	Caterpillar 777G Dual Slope
Gross engine power	kW	765
Net engine power	kW	704
Tyre size	-	27.00R49
Heaped tray capacity	m³	60
Empty weight	kg	73,618
Full weight (rated)	kg	164,654
Rated payload	t	91.0
Simulated payload	t	90.4
Max acceleration	m/s²	1.8
Max deceleration	m/s²	1.5
Max traction for braking	%	60
Fuel usage (0% load)	l/hr	10.0
Fuel usage (100% load)	l/hr	206.0

Table 16-16: Haul Road Segment Speed Restrictions

Segment	Description	Rolling Resistance	Retarder Use (Full / Empty)	Max Speed Full (km/h)	Max Speed Empty (km/h)
A	Main haul road	2.0%	70% / 70%	60	60
B	Main in-pit and dump haul road	3.0%	85% / 85%	30	60
C	Around dig face and tiphead	4.0%	85% / 85%	25	30
D	Round-a-bout	3.0%	85% / 85%	12	12

Table 16-17: Ramp Speed Restrictions

Code	Ramp Grade	Retarder Use (Full / Empty)	Max Speed Full (km/h)	Max Speed Empty (km/h)
RA	Down ≥ 5.0%	100% / 100%	20	40
A	Up ≥ 5.0%	100% / 100%	100 (engine limited)	100 (engine limited)

Table 16-18: Corner Speed Restrictions

Code	Direction Change	Max Speed Full (km/h)	Max Speed Empty (km/h)
CA	≥ 45° and < 65°	30	35
CB	≥ 65° and < 85°	20	25
CC	≥ 85°	10	10

16.7.3 Haulage Results

Haulage modelling was completed on the life-of-mine plan, with haul profiles created using Networkr, a module in Spry which generates accurate haul profiles from the active topographic surface. Haulage modelling was based on the allocation of Caterpillar 777 trucks, with a capacity of 90t (33bcm), to all dig units and processes (waste, ore and ore sorter rejects), using historical performance factors.

The haulage modelling generated a haul profile for every waste and ore dig solid/dump combination (155,000 haul profiles) with the load time, haulage time, dump time, queue time and spot time added to calculate a total cycle time for each profile. The number of truck hours, fuel consumed, changes in elevation, TKPH and other haulage performance indicators are calculated for each haul profile. The results of the haulage modelling assessment are shown in Figure 16-45.




Figure 16-45: Haulage Modelling Results

The number of Caterpillar 777 trucks required were smoothed on annual basis with a maximum fleet size of 30 trucks required from FY2036 to FY2039, when production from the pit is at its highest level. Excavators start parking permanently from FY2039 which reduces the number of trucks required.

For personal use only

16.7.4 Road Maintenance

Existing roads connect the various site service buildings and provide passage for heavy trucks between the pit, the crusher, the waste rock dumps, and the truck maintenance shop. The NAL haulage network is shown in Figure 16-46.

The haulage network shown in Figure 16-46 displays the in-pit haul roads (black lines), the dump access haul roads (green lines) and the main haul roads linking each of the operating areas (red lines).



Figure 16-46: Haulage Network

16.7.5 Mobile Mining Equipment

It is currently forecast that mining will be conducted by a mining contractor for the duration of the schedule. The mining contractor is responsible for providing and maintaining all equipment required to supply ROM ore to the crusher.

Table 16-19 details the primary mining equipment types and sizes that are planned, with their peak requirements. An additional fleet may be added or modified by the contractor, as needed, to support operations. Pumping is carried out using diesel pumps, HDPE piping and generators.

For personal use only

For personal use only

Table 16-19: Mining Equipment Description and Maximum Number of Units

Equipment Type	Description	Peak Requirement
Mining truck	Caterpillar 777 - 90t	30.0
Hydraulic excavator	PC2000 (200t class)	4.0
Hydraulic excavator	PC1250 (120t class)	2.0
Hydraulic excavator	PC800 (80t class)	1.0
Production drill	DTH – 4” to 7” hole size	4.0
Track Dozer	Net Power – 197 kW	4.0
Track Dozer	Net Power – 265 kW	4.0
Road grader	Net Power – 216 kW	3.0
Utility Excavator	Net Power – 308 kW	1.0
Wheel Dozer	Net Power – 249 HP	1.0
Water Truck/Sand spreader	Capacity – 80 000L	1.0
Wheel Loader	Bucket payload – 7.8 m^3	1.0
Fuel and Lube Truck	n/a	4.0
Service Truck	n/a	1.0
Pick-Up Trucks	n/a	15.0
Tower Lights	n/a	8.0

16.7.6 Water Management Strategy

The general water management strategy developed for the Project aims to:

- Divert off-site, all non-contact water from non-perturbed areas surrounding the site.
- Manage by draining, conveying, and containing runoff from surface infrastructure from the mill and waste (tailings and waste rock) management areas as well as underground water.
- Recycle a maximum of the mine site water from runoff, process, and groundwater for water supply purposes.
- For TSS sedimentation, retain water in ponds prior to treatment for release to the environment.
- Treat all contaminated water before releasing it to the environment.

The Water Management Plan (WMP) addresses the management of runoff water that has been in contact with the mine site as well as the clean water that flows through the Project site. The WMP update includes the tailings and waste rock storage facility runoff water, which represents a major addition in impacted surface area to the Project. Runoff water and underground water from the open pit are also collected. The domestic water is collected, and an appropriate treatment system is to be provided.

In preparing the WMP, priority was given to minimizing the impacted areas that generate contact water, to reduce the water volumes that will be managed. On the other hand, reclaim of contact water is prioritized to maximize the re-utilization ratio. Particular consideration was given to water management based on watersheds. The WMP mitigates the volume of contact water inflows to be managed on-site by diverting clean water to the environment.

16.7.7 Mine Personnel

Contractors are responsible for providing all personnel required to carry out mining activities such as drilling, blasting, loading, and hauling material, for the duration of its contract with the mine. Mining contractor personnel includes superintendents, mine supervisors, operators, drill-and-blast personnel, maintenance supervisors and mechanics. Elevra’s team will consist of technical services and management personnel for the duration of the entire operation.

For personal use only

17 Recovery Methods

The recovery methods for the Project were established based on the existing plant, historical operational data, historical metallurgical testwork, and lessons learned from other spodumene projects. Expansion process design is based on the operational and metallurgical reviews of the past process plant operation and testwork data. The work completed established the design basis of the plant, capital costs, and operating costs that were developed in this Mineral Reserves PFS.

17.1 Existing Plant Description

NAL's current operations are authorized at 4,500 tpd average annual production for the processing plant to produce spodumene concentrate. It consists of the following distinct areas:

- The primary, secondary and tertiary crushing, and ore sorting circuits on the ROM to produce an upgraded plant feed for downstream processing.
- The spodumene processing plant including grinding, desliming, magnetic separation, flotation and dewatering circuits to produce a final spodumene concentrate.
- Process water and utilities circuits including tailings thickeners, reagents preparation, reverse osmosis treatment, and tailings management.

In addition to the areas described above, the processing plant includes an area for the conversion of the spodumene concentrate into lithium carbonate. This area is currently not in operation and Elevra has indicated that there are no plans to produce lithium carbonate at the NAL facility.

17.2 Process Improvements

The process design developed for the Mineral Reserves PFS captures opportunities which were previously identified during the Updated Scoping Study.

17.2.1 HPGR Trade-off and Grinding Simulations

Process modelling confirmed the concerns that the previous design basis had underestimated the required circuit modifications required to achieve targets, resulting in additional power/equipment being required or a relaxed grind size. Based on this modelling, a trade-off study assessed three comminution circuit configurations to achieve a target throughput of 300 tph at a primary grind size of 200 µm P80 with the following scenarios as described below:

- Scenario 1: High Pressure Grinding Rolls (HPGR) and 1.6 MW ball mill circuit followed by two parallel ball mills (existing rod mill converted).
- Scenario 2A: Duplication of existing comminution circuit (rod mill and ball mill circuit).
- Scenario 2B: Duplication of existing comminution circuit with larger ball mill for future expansion.
- Scenario 3: Primary 2.1 MW ball mill followed by two parallel ball mills (existing rod mill converted).

The analysis demonstrates that all scenarios are technically capable of meeting the production target, but each presents different trade-offs in terms of cost, risk, and long-term flexibility. Scenario 2B was found to be the preferred option from a multi-criteria analysis (MCA) evaluating ease of implementation, operability, capital and operating costs, layout constraints, additional equipment and technology, and future expansion potential.

The qualitative scoring is presented in Table 17-1.

For personal use only

Table 17-1: HPGR Trade-off MCA Score Summary

Criterion	Scenario 1	Scenario 2A	Scenario 2B	Scenario 3
Ease of Implementation	1	5	5	3
Operability	2	4	4	3
Cost	1	5	4	4
Layout	1	4	4	4
Technology	2	5	4	4
Future Expansion	2	1	5	2
TOTAL	**9**	**24**	**25**	**20**

The design for Scenario 2B was implemented as the base case for the PFS process design and the flowsheets modified.

17.2.2 Plant Layout Considerations

The NAL operations team raised concerns related to layout constraints which could impact the initial updated scoping study design. The initial design included new conditioning tanks to implement two-stage conditioning for the existing rougher and scavenger flotation circuits due to issues reported by the operations team.

A review of the layout revealed that there is insufficient space to install new conditioning tanks for the rougher and scavenger flotation circuits. The PFS process design was therefore updated to repurpose the existing rougher and scavenger dilution tanks into conditioning tanks in Stage 1. As the existing rougher circuit will be reconfigured as a scavenger duty in Stage 2, the loss of the dilution tank is considered an acceptable trade-off during Stage 1.

17.2.3 Tailings Management

The updated scoping design had a new process thickener added in Stage 2 to increase the capacity of the existing thickener circuit. In this previous design, the existing process thickener would be operated in conjunction with a new flotation thickener as it was deemed adequate for a 15-20% increase in capacity combined with the reduced duty because of the split of water circuits. The new Stage 2 thickener would then only be added to match the difference in throughput from Stage 1 to Stage 2. This approach had the disadvantage of requiring operation of the existing thickener and new process thickener operating in parallel, thus increasing complexity.

A new process water circuit configuration is proposed for the PFS. A new process thickener will be installed to replace the existing thickener immediately from Stage 1. This new thickener will be sized for the Stage 2 throughput. The existing thickener could potentially be used in the future for water clarification but this was not part of the scope for the PFS.

The tailings from both process and flotation water circuits will be combined in an agitated tailings tank. The combined tailings will be sent to the TSF though two main pipelines with one pipeline in standby to provide redundancy to the TSF system.

17.3 PFS Expansion Design

The NAL expansion is based on a staged approach to reach authorised processing plant capacities:

- Stage 1: Increase of 15-20% in spodumene concentrate production within the 4,500 tpd permit.
- Stage 2: Expansion to a new milling throughput limit of 6,500 tpd average annual rate.
- Stage 3: New crusher circuit (milling capacity unchanged from Stage 2)

For personal use only

The targeted capacities will be achieved through the following modifications to the existing facility:

- Stage 1: Plant optimization
  - Addition of lump breakers in the ore feed circuit to the plant to prevent ice lumping
  - Increased stacksizer capacity to the existing ball mill circuit
  - Optimization of the desliming and magnetic separation circuit
  - Increased flotation conditioning capacity
  - Refurbishment of carbonate filtration unit for new spodumene dewatering and filtration unit
  - Replacement of existing thickener with a larger process thickener
  - Addition of a flotation thickener circuit to prevent flotation reagent contamination
  - Reconfiguration of tailings pumping to TSF
- Stage 2: Plant expansion
  - Contracting of a temporary crusher to balance plant feed with existing crusher
  - Addition of a second rod mill and ball mill line circuit including stacksizers
  - Addition of a trash screen to remove oversize (+1mm) material before magnetic separation
  - Addition of a third magnetic separation line to match increase throughput
  - Addition of a new rougher unit and conversion of the existing rougher to scavenger duty
- Stage 3: New crusher construction
  - Construction of new crusher to handle target throughput
  - Construction of new fine covered ore stockpile complete with reclaim and conveyors
  - Conversion of the existing crusher circuit to an ore sorting facility

17.3.1 Process Design Criteria

The key design criteria for the various stages of the expansion are summarized in Table 17-2 below. The design will be based on the existing mine and facility, the lithium recovery anticipated is 71.20% and is based on improvements to current plant performance of 69.00% recovery. The recovery is also based on a plant feed Li_2O grades presented below and a target concentrate Li_2O grades of 5.40%.

Table 17-2: General Process Design Criteria

Criterion	Unit	Base Case	Stage 1	Stage 2	Stage 3
Crushing Plant Availability	%	65	65	65	65
Processing Plant Availability	%	90	90	90	90
Total ROM Crusher Feed	tpd	5,815	6,646	10,000	10,000
Total Processing Plant Feed	tpd	3,780	4,320	6,500	6,500
Plant Feed Li_2O Grade	%	1.01	1.095	1.080	1.080
Target Concentrate Li_2O grade	%	5.40	5.40	5.40	5.40
Target Concentrate Production	tpa	178,058	213,670	338,000[1]	338,000[1]
Concentrate P80	mm	0.200	0.232	0.200	0.200

Note 1: The financial model prepared for the PFS considers a LOM average annual 5.4% Li_2O concentrate production rate of 348 ktpa (or 373 ktpa post expansion). These rates are superior to the process design criteria due to the production rate being dependant on the plant feed grade; the financial model considers a 1.17% feed grade. The process design is based on lower grades but the design supports the rates used for the financial model. The financial model is discussed in greater detail in Chapter 22 – Economic Analysis.

17.3.2 Process Flowsheets

The simplified block flow diagram is shown in Figure 17-1. The simplified process flow diagram is shown in Figure 17-2. The changes to existing equipment and additional equipment to be installed are colour coded according to the expansion Stage.




Figure 17-1: Simplified Block Flow Diagram

For personal use only




Figure 17-2: Simplified Process Flow Diagram

For personal use only

For personal use only

17.4 Process Description

The following sections detail the plant design optimisations and expansion modifications to the existing NAL facility proposed by Sedgman Novopro and approved by Elevra for the Mineral Reserves PFS. The key areas of the NAL facility following the various stages of expansion are described in the following subsections.

As the expansion will be delivered in a staged approach, the process is described below following the three stages of expansion.

17.4.1 Stage 1 Description

The existing crusher will continue regular operations during Stage 1. It is expected that the crusher capacity can be increased to meet the 15-20% concentrate production increase required for Stage 1 without any expansion. Due to reported issues with ice lumps forming in the fine ore silo due to the cold weather conditions, lump breakers will be installed at the outlet of the silos ahead of the plant feed conveyor to ensure the quality of the plant feed.

The Stage 1 plant process flow is as follows:

- Fine ore is fed from the fine ore silo to the grinding circuit via the plant feed conveyor.
- The existing grinding circuit consists of a rod mill and ball mill circuit with six stacksizers; three additional stacksizers are added to the circuit to improve the performance of the milling circuit. The combined rod mill and ball mill discharge reports to the stacksizers, and the oversize is returned to the ball mill.
- The stacksizer undersize is sent to a new primary desliming cyclone to remove slimes. The desliming cyclone targets a cut point (D50) of 10 µm. The overflow reports to the process thickener.
- The primary desliming cyclone underflow is sent to a new magnetic separation circuit which consists of two lines each including a low-intensity magnetic separator (LIMS) and a primary wet high-intensity magnetic separator (WHIMS). The intermediate non-magnetic product from both lines is combined and sent to parallel secondary WHIMS (existing, repurposed). The magnetics extracted by all stages are combined and pumped to the process thickener.
- The non-magnetic slurry from the secondary WHIMS is fed to a new secondary desliming cyclone to reach a solids concentration of 65% in the underflow. The cyclone overflow is returned to the primary desliming cyclone in Stage 1. The cyclone underflow reports to rougher conditioning. Conversion of the existing dilution tank into a new conditioning tank allows for a two-stage rougher conditioning when combined with the existing high-density rougher conditioning tank. The conditioned slurry is diluted and fed to the existing rougher flotation circuit.
- The rougher tails are further deslimed in a cyclone and conditioned before scavenger flotation. The scavenger dilution tank will be converted to conditioning duty to have a two-stage conditioning like the rougher circuit. The scavenger tails are sent to the flotation thickener.
- The concentrate from the rougher and scavenger circuits is combined and sent to cleaner 1 flotation. Cleaner flotation tails are sent to a new classifier cyclone with the underflow returned to the grinding circuit and the overflow sent to the flotation thickener.
- The cleaner concentrate is pumped to a new concentrate storage tank which serves as a buffer between the upstream process and the downstream dewatering and filtration. The new dewatering unit consists of a concentrate dewatering cyclone and a concentrate scavenger cyclone. The purpose of the scavenger cyclone is to recover misreporting material from the dewatering cyclone and vacuum filters.

For personal use only

- The new filtration unit consists of parallel vacuum belt filters (1 Duty/1 Standby). These filters are refurbished lithium carbonate filters that are existing in the plant. The spodumene concentrate is dewatered to a final moisture content of 6%. The existing filter unit will be bypassed by not dismantled.
- The final 5.4% spodumene concentrate is stored in a new enclosed stockpile in the location of the carbonate calciner which will be dismantled. The stockpile will have a capacity for ~200 hours in Stage 1 and have truck access for loading of the product.

The processing plant will operate with new separate process water and flotation water circuits. This design will isolate water contaminated with flotation reagents from sensitive equipment such as the LIMS and WHIMS. The existing thickener will be bypassed but not dismantled.

The process water circuit consists of a single thickener receiving the following tails streams:

- Slimes from primary desliming
- Magnetic material from magnetic separation (LIMS and WHIMS)

The new flotation water circuit consists of a single thickener and receives the following tails streams:

- Cyclone overflow from cleaner classification
- Scavenger flotation tailings
- Scavenger concentrate dewatering cyclone overflow

The thickener underflow from both thickeners will be combined in a tank and pumped to the TSF through two parallel pipelines.

17.4.2 Stage 2 Description

The existing crusher will continue regular operations as during Stage 2. A temporary contract crusher will be added in Stage 2 to balance the requirements of the processing plant after the expansion to a milling throughput of 6,500 tpd. The contract crusher will feed the emergency ore stockpile.

The Stage 2 plant process flow is as follows:

- A new grinding circuit with rod mill and ball mil is added in Stage 2. To feed the new circuit, the transfer conveyor from the emergency ore stockpile will be extended to feed a new line of conveyors. The second grinding circuit will be fed uniquely from the emergency stockpile until a permanent solution is installed in Stage 3. The feed from the fine ore silo for the existing line is unchanged. The total fine ore fed to the grinding circuit via conveyor will be at a total rate of 6,500 tpd by a combination of the existing crusher and a temporary contract crusher.
- The fine ore feed to the existing and new grinding circuits will be at a ratio of 50%/50% respectively. The new grinding circuit includes a larger ball mill than the existing one to provide the opportunity to further increase capacity in the future. The new grinding circuit will include six stacksizers. Should a future expansion be completed to reach a throughput of 200 tph in the new ball mill, additional stacksizers will be required.
- The stacksizer undersize from the two griding circuits is collected and screened through a new trash screen to remove product over 1 mm. The screen undersize is sent to the primary desliming cyclone to remove slimes as in Stage 1. The cyclone will be installed in Stage 1 but sized for the capacity of Stage 2.
- The primary deslime cyclone underflow is sent to the magnetic separation circuit as in Stage 1. A new third line of LIMS and primary WHIMS is added in Stage 2 for the increased capacity. The intermediate non-magnetic product from all three lines is combined and sent to two parallel

For personal use only

secondary WHIMS as in Stage 1. The final non-magnetic slurry is collected and sent to the new rougher flotation circuit. The magnetics extracted by all stages are combined and pumped to the process thickener as in Stage 1.

- The non-magnetic slurry is fed to a new secondary desliming cyclone to reach a solids concentration of 65 % in the underflow. The cyclone overflow is returned to the trash screen. The secondary deslime cyclone underflow is sent to new two-stage rougher conditioning tanks followed by a new rougher flotation circuit. The first step of rougher flotation consists of two cells in parallel and individual cell level control to ensure the effectiveness of the flotation. Tails from the first stage is sent to the second step of rougher flotation. The concentrate from both stage of rougher flotation are sent to cleaner 1 flotation. The design also allows for the first step of rougher flotation to bypass straight to cleaner 2 or cleaner 3. The tails from the new rougher flotation are sent to the scavenger unit.
- With the new rougher flotation circuit added in Stage 2, the Stage 1 rougher circuit, including secondary deslime cyclone, is converted to a scavenger flotation duty to increase scavenger capacity. Each scavenger flotation circuit is preceded by a scavenger cyclone and two-stage conditioning. This new scavenger unit will be configured with the converted scavenger circuit in series with the existing scavenger circuit. It will also be possible to bypass the first scavenger circuit or run the scavenger circuits in parallel if required. The scavenger cyclones overflows and scavenger cells tails are sent to the flotation thickener. The scavenger concentrate is returned to cleaner flotation.
- The remaining steps for the cleaner flotation, dewatering, and filtration are unchanged from Stage 1. Equipment added in Stage 1 are sized for the Stage 2 capacity.

The storage area for the final 5.4% Li_2O spodumene concentrate is unchanged from Stage 1. The process thickener circuit and the flotation thickener circuit are sized for the capacity of Stage 2 and are unchanged from Stage 1.

17.4.3 Stage 3 Description

In Stage 3, the existing crusher will be repurposed as a dedicated ore sorting facility once the new crusher is operational. This ore sorting unit will increase the operations' flexibility, as well as simplify the design and reduce the capital cost of the new crusher facility. The existing secondary ore sorters will be replaced with XRT ore sorters, which use the density of the particles as opposed to the surface properties. The primary ore sorter will not be modified and will be maintained for processing of coarse ore. The sorted ore will be conveyed to a new sorted ore silo or transported to the ROM. Sorted ore will then be fed to the Stage 3 crusher ahead of the crusher screen.

Fresh ore from the ROM is discharged to the new Stage 3 crusher through a 90 mm aperture vibrating grizzly, with oversize feeding a jaw crusher. Primary crusher product will be conveyed to a double deck banana screen. The top deck oversize will be conveyed to the secondary cone crusher, and the bottom deck oversize material will be conveyed to the tertiary cone crusher. The crushed product will be conveyed back to the double deck screen for re-sizing. Crushed product underflowing the double deck screen will have a nominal size (F80) of <10.2 mm and will be conveyed to a new fine ore stockpile. Fine ore will be reclaimed from the ore stockpile and conveyed to the plant feed conveyors.

The processing plant is unchanged from Stage 2 as the required modifications to increase capacity to 6,500 tpd are completed for Stage 2.

17.5 Production and Recoveries

The NAL expansion project is scheduled to process an annual average rate of 6,500 tpd of blended ore. Based on a plant feed Li_2O grade of 1.17%, the spodumene concentrate average annual production rate post-expansion is estimated at 373,000 tpa.

For personal use only

The existing crusher, ore sorting, new crusher and ore storage areas are designed to operate with an availability of 65%. The processing plant, including the milling, classification, desliming, magnetic separation, flotation and dewatering, is designed to operate at 90% availability. The processing plant will operate on a 24-hour per day and 7 days per week basis.

Metallurgical recovery is improved at the onset of the stage implementation and will achieve an estimate of 71.2 % average over the life of mine as disclosed in the previous study. This recovery is well supported by previous testwork as described in Chapter 13 – Mineral Processing and Metallurgical Testing.

The recovery benefits from the existing operation will come from the following flowsheet improvements:

- Improved flotation feed sizing due to increased classification capacity and mill power.
- Improved magnetic separation circuit (LIMS and WHIMS)
- Improved flotation conditioning
- Improved rougher flotation control and flexibility
- Improved cleaner tails handling

These improvements targeting specific areas will lead to recovery gradually increasing through the staged approach with the full benefits achieved by Stage 2 with all optimisations captured.

17.6 Recommendations

The process design proposed for the Mineral Reserves PFS is based on previous metallurgical studies, operating data from the existing plant, and experience acquired from work on similar spodumene projects across the world. The work completed should be further advanced during a detailed engineering phase to bring the engineering to a level suitable for construction.

The work described below is underway and will help confirm and support design parameters used in the Mineral Reserves PFS.

- Plant trials on operating the existing WHIMS in parallel. These trials will help validate the increases in recovery assumed in the design.
- Flotation conditioning tests and lip surveys in the processing plant to increase understanding of the potential improvements and impact on downstream flotation, as well as understand the existing circuits limitations and potential bottlenecks to be addressed.
- Repeat surveys and simulations to assess the new flotation feed PSD and expected slimes generation.

To further de-risk the project, the following test is recommended in addition to the planned testwork described above. This additional testwork program would be completed in the next phase of the project.

- Optimisation testwork on the WHIMS to understand the limitations and set targets for plant operations.

For personal use only

18 Project Infrastructure

This chapter describes the project infrastructure of the existing NAL operation and projected infrastructure required for expansion. This chapter contains information which was previously published by Sayona in a NI 43-101 Technical Report titled “Definitive Feasibility Study Report for the North American Lithium Project”, dated April 14th, 2023 (BBA, 2023).

Site infrastructure at the NAL operation is established and operating, currently including:

- An open pit.
- A processing plant and a ROM ore pad.
- Waste rock and overburden storage areas (WR#2, WR#3 & OB#1).
- A conventional tailings storage facility (TSF-1).
- The administration facility, including offices and personnel changing area (dry rooms).
- Workshop, mechanical workshop, warehouse, and storage areas.
- Fuel, lube, and oil storage facility/equipment.
- Reticulated services, including power, lighting and communications, raw water and clean water for fire protection, process water and potable water, sewage collection, treatment, and disposal.
- A crushed ore dome.
- Access roads.
- Water management infrastructures.

Additional infrastructure is required to the meet the requirements of the expansion design, which includes:

- An expansion of the open pit and associated water management infrastructure.
- Pit sedimentation basin
- New crushing and ore sorting circuit including crushed ore dome.
- New grinding, magnetic separation and flotation.
- Concentrate dewatering filters and new concentrate storage and loading facility.
- Tailings thickeners.
- Additional mechanical workshop, operation room, and supervisor offices.
- Additional tailings management facilities and associated water management infrastructure:
  - TSF-2 (required for base case and expansion)
  - TSF-3 (required for base case and expansion)
- An additional waste stockpile area (WR#4) and associated water management infrastructure.
- Multi-service buildings:
  - Additional offices, engineering, administration etc.
  - Additional capacity for the mine change rooms, showers and ablutions.
  - Additional mine offices and mining dispatch control room.
- Mine maintenance shop:
  - Two additional mining service bays.
  - Additional warehouse storage.

  - Additional supervisory and administration offices.
  - Wash bay.
- Auxiliary buildings:
  - Warehouse domes.
  - Relocation of the mine fuel depot and additional capacity. (required for base case and expansion)

Figure 18-1 shows the overall site layout and offers a general overhead view of existing and new infrastructure required to manage the process plant expansion, mine waste and impacted water. They represent the planned infrastructure at the end of the current life-of-mine plan.

18.1 Access Roads

18.1.1 Public Roads

The site can be accessed by existing public roads, Route 111, and Route du Lithium from the municipality of Barraute, 17.2 km away, via Chemin du Mont-Vidéo and Route du Lithium. From Route du Lithium, there are multiple small access roads that can lead into the pit area. These access roads have been blocked, and their access will be limited during blasting operations.

18.1.2 Site Roads

Existing roads connect the various site service buildings and provide passage for heavy trucks between the pit, the crusher, the waste rock dumps, and the truck maintenance shop.

18.1.3 Security and Access Point

Site access is through a guard/security house located at the entrance to the site on the main access road. The guard house is a prefabricated building with separate entrance and exit doors. Parking bays for trucks and visitors' reception are provided next to the guard house.

For personal use only

For personal use only




Figure 18-1: Preliminary Layout – Expansion

For personal use only

18.2 Electrical Power Supply and Distribution

18.2.1 Site Electrical Utility Supply

Power for the Project is taken at 120 kV from transmission line No. 1301, which is owned by the provincial utility company, Hydro Québec. This transmission line runs on the west side of the Project site and the spur feeding the plant is approximately 600 m long.

18.2.2 Site Electrical Distribution

The plant's outdoor substation steps down the incoming voltage to 13.8 kV, which is used to power up the different transformers, all located indoors, further stepping down the voltage to 4.16 kV and 600 V, two voltage levels at which process equipment is operated. NAL is in the process of purchasing a new larger 120/13.8 kV transformer to meet future needs and improve reliability. The power distribution to the process equipment is through armoured cables installed in cable trays.

Power for the expansion project will be subject to an additional request. Stage 1 expansion falls within current contract limits whereas Stage 2 and 3 will require approval from the Ministère de l'Économie, de l'Innovation et de l'Énergie (MEIE) and studies by Hydro Québec. Coordination is currently underway to process the forecasted increase.

18.2.3 Emergency Power Supply

In the event of a power failure, emergency power for operating critical equipment is provided by a single 4.16 kV, 1,400 kW emergency stand-by generator. The generator is connected to the main 4.16 kV switchgear to back feed the 13.8 kV switchgear during emergency operations. This configuration allows emergency power to be routed to any load in the plant. All switching is done manually, with interlocks in place to prevent unsafe operations.

18.3 Fuel Storage

There are two fuel stations at the site:

- A gasoline station near the garage with a 2,359 L capacity tank dedicated to light vehicles.
- A three-tank diesel station for heavy equipment located near the pit operations. The capacity of each tank is 50,000 L.

As part of the expansion project, the current fuel storage facility will require re-location prior to mining activities in future phases. Cost for the relocation and expansion of the facility capacity has been allowed for in the Sustaining Capital.

18.4 Natural Gas and Propane

Propane tanks are in two areas on the site:

- A station near the plant at the south side with two tanks of 2,000 L each. This station is used to heat a part of the plant.
- A station on the west side of the plant with two tanks of 50,000 L each. This station is used to heat a part of the plant.

A 30 km natural gas line was built while the Project was under CLQ; natural gas can be supplied from local natural gas distributor Énergir's Abitibi network. The line runs to the site, but the tie-in has not been done at this point. Previous discussions indicated the natural gas pipeline tie-in is possible with Énergir for an assured supply of 3,400 m^3/h. This is the maximum that can be secured by the distribution system. Peak winter loads are expected to exceed the assured supply. Énergir has indicated that they are investigating ways to expand the network's capacity.

Additional studies into possible pipeline supply of gas will be investigated in the next phase of project

18.5 Water Supply

18.5.1 Water Reclaim System

The Project has no infrastructure in place to draw water from any external source for processing purposes, and the expansion does not require the installation of water drawing infrastructure. Groundwater and run-off from the mine pit are recovered for use as fresh water in the process plant. All water used in the concentrator is recycled internally or is reclaimed from the tailings ponds, where levels must be managed seasonally.

To support the NAL expansion, a site-wide water balance was performed based on major infrastructure expansion footprint (see Figure 18-14). The water balance shows an excess of water on the overall site for all stages of development. To manage future water balance, infrastructure such as basins and drainage ditches has been incorporated into the expansion project.

18.5.2 Water for Fire Protection

Water for fire protection is currently stored in the lower section of the process water tank. Water pumps feed the process plant fire water ring main and also supply fire water hydrants at the mine garage and at the administration building. Exterior sections of the fire water piping are buried below the frost line to prevent freezing. Additional fire protection capacity is not envisaged for the expansion project.

18.5.3 Potable Water

Potable water is supplied by a contractor who is responsible for managing bottled water supplies. The potable water demand will be evaluated in the next phase of the project. The demand is expected to increase due to the increase in the number of employees at the site. Use of safety showers is also not currently possible due to the lack of a potable water system.

18.5.4 Sewage and Waste

A complete sewage water plant with two septic tanks (20 m^3 and 10 m^3) were installed at the west end of the main building in the summer of 2022. These units treat the wastewater from the concentrator, dry house, the main building, and the garage. The drain water is being discharged into a septic field. Sewage and waste capacity assessment will be undertaken in the next project phase. The current water treatment system is at the limit of its capacity; an increase in the number of employees would likely further strain the system.

For personal use only

For personal use only

18.6 Tailings Storage Facility

18.6.1 Estimated Needs

The current site includes a conventional tailings storage facility (TSF-1) as part of the tailings management infrastructure, located 500 m south of the processing plant. However, the mine plan for NAL forecasts mining operations continuing beyond the capacity of the existing Tailings Storage Facility (TSF) No. 1. Consequently, new mine waste and tailings facilities are planned to manage the additional waste streams coming from a larger mining operation.

Two tailings storage facility identified as TSF-2 and TSF-3 are required to accommodate the volumes associated with the recently published Mineral Resources and LOM plan.

Total mine waste to be managed by the expanded NAL site storage facilities is given by Table 18-1.

Table 18-1: Design Criteria Based on the Tailings Generation Rate

Criterion	Value	Source
Tailings average dry density	1.3 t/m^3	PEA mine plan
Tailings Production	40.5 Mt (NAG tailings, non-leachable)	PEA mine plan
Mine waste production	340,8 Mt (NAG waste rock, slightly leachable)	PEA mine plan

18.6.2 Project Overview

18.6.2.1 Existing TSF-1

TSF-1 is a conventional slurry tailings storage facility located approximately 500 m south of the processing plant. Golder Associates performed geotechnical and hydrologic engineering services for the design of the TSF-1 Phase 1C, including geotechnical foundation investigation programs, design of the peripheral dykes and ancillary hydraulic structures, and tailings deposition planning. Englobe Corp. has then been responsible for Phases 1D and 1E development.

TSF-1 comprises of a perimeter dyke with variable elevation along its length and raised in stages using the downstream method. Tailings deposition is carried out via a single spigot deposition point, with a reclaimed water system to manage TSF water levels seasonally.

TSF-1 was raised to an elevation of 415 m under Phase 1C works, achieving a total residue storage capacity of 1.8 Mt. Detailed engineering of Phase 1D is complete and includes a 3 m raise, increasing total capacity to 2.34 Mt. The final raise of the TSF-1 will use waste material for its construction. TSF-1 is ultimately planned for a total capacity of 2 Mt. With every raise the emergency spillway is adapted to safely convey the probable maximum flood. Peripheral ditches collect seepage water and convey them to water pond (380B, B01 and the polishing pond) where they are returned to the reclaim or safely discharge to the environment.

As well, the previous NAL operators included a secondary transformation process to make lithium carbonate, which generated additional residues, and is not part of current plans.

TSF-1 is expected to service the existing operation and early years of the LOM. Once its ultimate capacity is reached, tailings will be directed to TSF-2 and subsequently TSF-3, as described in the sections below.

Mine waste management forecasted facilities are shown on the expanded NAL site configuration in Figure 18-2.

For personal use only




Figure 18-2: Plan view – Preliminary Mine Waste Storage Facilities Locations

18.6.2.2 Planned Expansion Details: TSF-2

TSF-2 is a new tailings storage facility required in the short-term for the storage of LOM concentrator tailings. TSF-2 facility that can manage a total of 25.6 Mt of tailings produced at the concentrator and the possibility to use waste rock from the mine. The projected TSF-2 capacity is 25.6 Mt; for a LOM of 25.9 Mt over 14 years, TSF-2 is expected to be in operation for 14 years.

The conceptual design for TSF-2 consists of a compacted waste rock perimeter embankment constructed using a centreline method, with hydraulically deposited tailings forming a central pond. Tailings will be discharged from spigots along the crest to maintain a water pond and adequate beach length for embankment stability. The main reclaimed water pond will be managed by a barge-mounted pump system connected to the plant reclaim water system, which also provides storage for process water and the design flood.

The new facility will be located to the west of the current TSF-1 across the Hydro-Quebec corridor. The original selection of the proposed location has been defined as per the following steps:

- Analysis of site characteristics based on aerial photos, LIDAR information, and regional land use information, which includes the identification of existing infrastructure such as electric lines, roads, forestry domains, and natural water bodies.
- Volumetric compliance for tailings and waste rock placement.

- Preliminary analysis of the environmental and social constraints of the selected deposition storage facility footprints.

The size of the TSF water pond shall be controlled by a new pump system (e.g., barge-mounted pump station) as part of the new reclaimed water system. This new infrastructure envisioned an additional pond to store plant process water in winter (and possibly to contain the environmental design flood). The reclaimed water system must ensure reclaimed water supply to the concentrator plant and maintain sufficient volume and minimum water cover depth for tailings settling.

A new water management basin (B2 pond) will be located to the northeast of the facility. A total of three new pumping stations around TSF-2 are required over the life of the project for runoff water management: two at the south end (B3 and B4) and one at the north end of the facility (B1). For each pumping point, a surge pump basin has been designed. All pumped water will be transferred to TSF2 and then to the B2 basin. A treatment system primarily based on decantation, complemented by additional TSS control measures, will be implemented to allow environmentally compliant discharge of Basin B2 water. A spillway will be located on the west side of the TSF-2 along the lowest section of the Dam. The spillway will be gradually adapted as the dyke is raised.

The proposed layout of the TSF is presented in Figure 18-3. The TSF-2 is scheduled to begin operations in 2029.

18.6.2.3 Planned Expansion Details: TSF-3

Later in NAL project lifetime, it is currently projected that following operation of TSF-2, a new tailings stream will be managed in a new TSF-3. TSF-3 is designed to store 18 Mt of tailings. TSF3 can accommodate the last 6 years of production from 2042 to 2047 (total production of 9.2 Mt of tailings). A preliminary location and conceptual design for TSF-3 have been undertaken for the purposes of the Pre-feasibility study. The proposed location for TSF-3 is located east of the existing TSF-1. The final location of the tailings is currently under review and will be confirmed through a detailed Variant Analysis. Figure 18-4 presents the proposed location of TSF-3 at the southern end of the mining property at the east side of TSF-1.

Similarly to TSF-2, the TSF-3 comprises a compacted waste rock peripheral dyke to contain the deposited tailings. The dyke will be built along a natural topographic high point minimise the embankment requirements. The dyke will be raised using the central raise method. Tailings will be discharged from a single discharge point regularly moved along the crest to maintain a central water pond and adequate beach length for embankment stability.

A spillway will be located at the south end of the peripheral dam and excavated in the natural ground to convey water to the stream located further south. Peripheral ditch will collect seepage water and convey it to a temporary pumping pond (Basin B5) located at the toe of the dam at a low topographic point. Once the waste rock stockpile #4 encroach on the pond it will be moved further south closer to the WR#4 sedimentation pond as shown in Figure 18-5.

For personal use only




Figure 18-3: TSF-2 Final configuration Layout

For personal use only




Figure 18-4: TSF-3 Final configuration Layout

For personal use only




Figure 18-5: Revised location of Bassin B5 once WR#4 encroach on the Bassin B5

18.6.3 Regulatory and Compliance Requirements

The following standards and regulations were considered for the design of the new TSFs as well as all their related water management infrastructure:

1. Québec' *Directive 019 sur l'industrie minière* (MELCCFP, 2025).
2. Guidelines for preparing mine closure plans in Québec (MRNF, 2024).
3. The Dam Safety Act applied in Québec (LSB) and the associated regulation (RSB).
4. The Dam Safety Guidelines and Technical Bulletins produced by the Canadian Dam Association.
5. Metal and Diamond Mining Effluent Regulations (MDMER) in Canada.
6. Regulation respecting occupational health and safety in mines, Act respecting occupational health and safety – Québec (2014) (Québec Health and Safety Regulations).
7. The local, Québec and/or the Canadian Legal framework applied to the environment and water sectors.

For personal use only

For personal use only

18.6.4 Design Considerations

18.6.4.1 Tailings Material Characterization

The most recent tailings geochemical characterisation completed at the end of 2017 and the beginning of 2018, showed that tailings from spodumene concentrate production are neither PAG, nor leachable. Whereas previous geochemical tests were relevant, their results are no longer representative of the tailings management approach going forward since the current plan is to produce only spodumene tailings (no lithium carbonate tailings). This would remain consistent, going forward; even if carbonate tailings are to be produced at some point, the NAL management strategy would be to keep such tailings separate from the spodumene tailings. Results from geochemical studies showed that NAL site waste rock is neither PAG, nor leachable; therefore, no special geochemical precautions for waste rock stockpiling and runoff water management.

18.6.4.2 Subsurface investigation extent

BBA Consulting has been mandated in 2022 and late 2025 to extensively investigate TSF-2' footprint. In total, twenty-seven (27) boreholes, including fifteen (15) monitoring wells installations, and twenty-nine (29) tests-pit have been performed to describe and sample the projected infrastructure foundation. The stratigraphy of the TSF-2 site is relatively uniform. Generally, the overburden soil encountered is predominantly glacial till ranging from silty sand to sandy silt with some gravel, traces of clay, and presence of cobbles and boulders. The soil was generally moist to saturated and mainly grey in colour, with some soil having lighter and darker brown colours. Based on N-SPT indices computation and interpretation, early conclusion sates the glacial till shows no potential to liquefaction. The overburden soil is directly seating on the bedrock encountered at an average depth of 4.3 m. Additionally, completed and ongoing laboratory tests have been performed to characterize the glacial till rheology and mechanical behaviour in order to feed TSF-2 geotechnical and hydrotechnical design.

As TSF-3's location is not confirmed yet, BBA Consulting investigation work has been limited in its footprint compiling one (1) borehole and four (4) tests-pit, complementary to a few early 2010's boreholes performed in the same area. The stratigraphy of the TSF-3 differs from TSF-2' site as the overburden soil encountered is predominantly a fluvioglacial deposit. The overburden soil is directly seating on the bedrock encountered at depths exceeding 30 m. If TSF-3' footprint is eventually defined, additional geotechnical and hydrogeological investigation efforts will be necessary to support its engineering design.

18.6.4.3 Embankment Configuration

As mentioned in sections above, TSFs peripheral compacted waste rock dykes will be built following the centreline method with the characteristics presented in Table 18-2 and typical cross-section presented in Figure 18-6.

Dam design criteria include storage for the Environmental Design Flood (EDF) defined as a 1 in 1,000 years return hydrologic event (24-hour storm or 30-day spring freshet) with no discharge through a spillway. An emergency spillway will be installed in the future to safely pass the Inflow Design Flood (IDF) consisting of a routed Probable Maximum Flood (PMF) of 24-hour duration. The dams are designed for seismic events of 1:10,000 years (Maximum Credible Earthquake). Stability will be assessed by considering loading conditions and minimum factors of safety, as described in Directive 019. The Consequence Category if the Dam is considered "very high". due to Potential Loss of Life. This classification may be revised once the Dam breach assessment is completed. Both TSF-2 and TSF-3 final configurations are summarized in Table 18-2.




Figure 18-6: Typical Cross Section of Peripheral Embankment

For personal use only

For personal use only

Table 18-2: TSF-2 and TSF-3

Item	TSF-2	TSF-3
Crest elevation	465 m	440 m
Downstream slope	2.5H: 1V	Refer TSF-2
Upstream slope	2H: 1V	Refer TSF-2
Impervious lining	Along the TSF perimeter at interface between tailings and starting dyke first bench	Refer TSF-2
Dyke crest final width	10 m	Refer TSF-2
Tailings minimum freeboard in operation	0,5 m	Refer TSF-2
Water minimum freeboard in operation	1 m	Refer TSF-2
Access ramp maximum slope	10%	Refer TSF-2
Footprint	~90 ha	~111 ha
Maximum height	±70 m	±60 m
Bench height	10 m	10 m

18.6.4.4 Water Management

The design criteria for the hydraulic deposition tailings storage facilities, as established in Directive 019, aim to ensure the environmental safety and long-term sustainability of the TSFs. In the context of NAL site, where the tailings are neither acid-generating nor leachable, the directive states that the containment structure must be designed to manage the design flood event without discharging water through the emergency spillway.

At all times, for any event equal to or less than the design flood, a freeboard of at least 1 m must be maintained. To ensure compliance with this requirement during exceptional weather events, the following must be met:

- The design of the structures (based on minimum design flood recurrences of 1:1,000 years, 1:2,000 years or more, with allowances applied to account for climate change) must include an additional distance that allows the minimum required freeboard to be always maintained.
- The maximum operating level, meaning the highest level that the retained water can reach under normal operation of the structure, including seasonal fluctuations and peak periods, must be set and maintained as a precaution to ensure the minimum 1 m freeboard during exceptional weather events.

To verify compliance with the Ministry's requirements, the freeboard measured at the time of inspection must meet the maximum operating level.

The design flood must be determined by taking into account critical rainfall events with a recurrence interval of 1 in 1000 years, combined with the average snowmelt over a 30-day period, and considering the maximum expected snow accumulation with a recurrence interval of 1 in 100 years.

Regarding the drainage networks surrounding the tailings management infrastructure—including drainage ditches and pumping ponds—they must be sized to properly evacuate a 100-year flood (recurrence interval of 1 in 100 years), combined with the average snowmelt over a 30-day period and accounting for the snow accumulation expected from a 1 in 100-year event. An additional safety margin must also be applied to incorporate the effects of climate change in the design of the water management infrastructure.

As a result, the infrastructures developed for this phase of the project will have the following characteristics presented in Table 18-3.

For personal use only

Table 18-3: Design Criteria for TSFs Water Management

Infrastructure	Parameter	Value
Main water management basin	Design return period (storm)	1,000 years
	Return period for spring snowmelt (30-day)	100 years
	Minimum freeboard	1.0 m
Emergency spillway	Design return period	PMP (Probable Maximum Precipitation)
Plant water pump basin	Design return period	100 years
	Minimum freeboard	0.3 m
	Impermeabilization (seepage control)	Geomembrane liner to prevent seepage to environment
Drainage ditches	Design return period	100 years
	Cross-section profile	Trapezoidal
	Minimum freeboard	0.3 m
	Slope protection / lining	Riprap (rock armouring) for slope protection; geomembrane for sealing
Surge pump basin	Design return period	100 years
	Cross-section profile	Trapezoidal
	Minimum freeboard	1 m
	Slope protection / lining	Riprap (rock armouring) for slope protection; geomembrane for sealing

18.6.4.5 Seepage mitigation and control

Seepage mitigation measures have been included in the TSFs designs with the construction of a granular material drain extended to the whole dyke's footprint above the natural foundation.

18.6.4.6 Closure design

NAL site's tailings storage facilities are to remain in place after mine closure. Once the water quality of the tailings pond will be deemed suitable for discharge to the environment, runoff from the TSFs will be directed through the overflow spillway into the environment. The integrated reclamation strategy plans the backfilling and seeding of exposed tailings beaches with vegetal substrate and the construction of a gravity-driven ditches network towards the existing spillway.

18.6.4.7 Monitoring

The NAL site's TSFs are to be implemented with an exhaustive monitoring system including instrumentation tracking dykes' integrity, water table levels and discharges quality over time, from operation to closure. Such monitoring program will be developed accordingly to the best practices of the industry. Additionally, monitoring and periodic inspection programs for the mine waste management infrastructure, respectively during the operational, restoration, and post-restoration phases will be developed.

18.6.5 Risk Assessment and Challenges

The following table presents different technical challenges inherent to the proposed TSF design. These challenges need to be addressed prior the development of the following engineering phases.

Table 18-4: Technical Challenges of the Proposed TSF Design

Category	Description
Construction challenges	Some constructions challenges before placement of waste rock on the tailings beach (spigottes tailings). Following freshet and rainfall events the tailings will be saturated and may pose constraints when grading/compacting the tailings beach forming the foundation of the embankment. No specialized crew required.

For personal use only

Category	Description
Operational challenges	Building the dyke in waste rock reduces slope erosion maintenance. However, deposition from the entire perimeter means more piping, hence more pipeline maintenance (no geomembrane is used in this option, so no liner-related issues).
Design challenges	- Lack of any impermeable layer above the starting bench will increase seepage through the raises of the dyke. Detailed seepage analyses will be needed to support the water management strategy and demonstrate dyke stability. - Water management strategy is more complex. - Lab and field testing will be needed to determine tailings geotechnical and hydraulic parameters. - Specific investigation (piezocone) and tests to evaluate the expected compacted tailings beach bearing capacity and tailings' liquefaction potential and detail dyke material mechanical behaviour will be required. - Presence of a groundwater discharge area feeding the network of stream in the footprint of the TSF. Foundation preparation consideration.
Environmental challenges	Dusting from exposed tailings, low dust levels expected, thanks to the central location of the pond. High seepage rates increase risk of environmental contamination. Social acceptability considerations, since no geomembrane is present (the absence of a liner will need to be justified and proven acceptable during the permitting process).
Water management challenges	Requires a barge-mounted pump station. An additional pond will be needed to store plant process water in winter (and possibly to contain the environmental design flood). There are constraints on maintaining sufficient volume and minimum water cover depth for tailings settling, and on maintaining a minimum beach length to ensure dyke stability. Higher seepage rates necessitate larger downstream water retention ponds and more powerful pumps. Increased monitoring of water levels will be required. Challenges in tailings deposition near the emergency spillway.
CAPEX (initial capital) (Cost)	No geomembrane to install. Requires construction of an additional pond to store plant water in winter (and potentially the environmental design flood). The site drainage network must accommodate a greater volume due to higher seepage rates.
OPEX (operational) (Cost)	The process plant will need higher-capacity pumps due to the greater final height of the TSFs. Barge operation is more complex (as the pond is larger/deeper). Maintaining careful control of water levels and deposition is critical. Groundwater monitoring is critical given higher seepage and the risk of internal erosion.
SUSEX (raises capital) (Cost)	Moderate volume of waste rock to haul for raises. No geomembrane installation needed for raises (simpler construction), this option has the lowest sustaining capital needs overall).

18.6.6 Recommendations

The following recommendations are presented to address current information gaps that might have a significant influence on the projects CAPEX/OPEX, and to inform further decision stages in the next engineering phases.

Table 18-5: Technical Recommendations and Further Actions

Aspect	Recommendation
Tailings properties and deposition	ONGOING – Undertake a **targeted tailings investigation and test program** (piezocone, large-strain consolidation, CRS/Rowe, cyclic/LIQ screening, hydraulic conductivity vs void ratio) to replace assumed input values and support liquefaction/deformation analyses flagged as required.
	Validate beach slope and in-situ density assumptions with site-specific trials (e.g., pilot spigoting, beach surveys) to support the "≤10 m below rock berm" operating premise and NAL nominal slopes/densities.
Geochemistry	ONGOING - Update **geochemical characterisation** for *spodumene-only* tailings (the report notes legacy, mixed-tailings work; spodumene-only needs its own program).
	Undertake kinetic tests to inform closure Capex, and to include preventive actions during the operation phase that could influence the TSFs Opex.
Stability analyses/monitoring and seismic inputs	ONGOING – Undertake **stability analyses** for the *wet disposal* configuration for both TSF-2 and TSF-3, covering all Directive-019 load cases and the pseudo static hazard basis.
	Perform a **Probabilistic Specific Hazard Assessment (PSHA)** for NAL site in order to define representative seismic events and inputs to support TSFs detailed design.
	Develop a monitoring and surveillance plan. Design a monitoring network accordingly. The selected instrumentation (e.g., VWP) must be part of the CAPEX.
Seepage and liners	Because the embankment concept has **no geomembrane/impermeable layer**, complete **finite-element seepage modelling** (transient and steady). The outcome will allow the assessment for **internal drains/cutoffs** as additional controls if needed to manage gradients and exit heads.

Aspect	Recommendation
	Develop a **groundwater monitoring plan** and baseline model; the document highlights high seepage risk and the need for strong groundwater monitoring.
Hydrology, pond and water balance	Size the **main basin/emergency spillway** to 1:1,000-year storm and PMP respectively; confirm **100-year** criteria for ditches/pump basins and implement the **18% climate change uplift** noted.
	Complete the **water balance** and **winter storage pond** sizing for process water and flood containment; integrate the three new pump stations and surge basins into the control philosophy.
	Produce a **deposition plan** that maintains a central pond and **minimum beach length**, with special rules near the emergency spillway (called out as an operational challenge).
Hydraulic and mechanical systems	Finalise **pump sizing** (reclaim and decant barge systems) and pipeline routing; the concept notes higher head requirements and more complex barge operations with a larger/deeper pond.
Civil and constructability	Detail **construction sequencing** for centreline raises, granular material filters, and wet deposition interfaces (the report flags sequencing and rainy-day pond constraints near the upstream crest).
	Verify **foundation preparation** scope and volumes (foundation stripping ~550,000 m² referenced) and confirm foundation stratigraphy given “no clayey soils identified”.
Regulatory, risk and classification	Complete the **CDA consequence classification** and ensure alignment of design criteria and emergency planning with the outcome.
Engineering design review	Establishment of Independent Tailings Review Board (ITRB) for TSF infrastructure design operation and monitoring review.
Costing	Close the OPEX by modelling power, pump duty, barge ops, pipeline maintenance; carry groundwater monitoring costs explicitly, etc.
	Revisit **layout/volume optimisation** in Detailed Design (the design reports notes optimisation potential) and test **variant options** (e.g., partial liners/under-drains) against seepage, CAPEX/OPEX, and permitting risk.

18.7 Quebec Lithium Tailings Storage Facility Retaining Structure

The spodumene pegmatite deposit on the Québec Lithium property was mined between 1954 and 1965. At that time, the deposit was developed from a vertical shaft, and the mine tailings were contained within two dikes located north of the former mine, in an east–west-oriented valley between Lortie and Roy lakes. Waste rock was deposited around the perimeter of this storage area, thereby contributing to the containment and retention of the mine tailings.

Following the planned expansion of the current pit, the pit walls will intersect the Québec Lithium tailings storage facility (QL-TSF). As a result, a portion of the tailings currently in place will need to be excavated, leaving part of the remaining tailings without containment.

The proposed retaining structure at the QL-TSF is intended to ensure the stability of the overburden and tailing slope at this location. In addition, the structure will provide long-term containment and retention of the remaining tailings, thereby ensuring the continued integrity and safe management of the QL-TSF during and after pit expansion operations.

18.7.1 Preliminary Geotechnical Design of the Retaining Structure for the Tailings Storage Facility (QL-TSF) at the Québec Lithium Tailings Management Area

The proposed retaining structure at QL-TSF is located in the central portion of the tailings storage area, as shown in Figure 18-7.

For personal use only




Figure 18-7: Plan View of the proposed Retaining Structure

A typical cross-section of the Lortie Lake dyke is shown in Figure 18-8. The proposed retaining structure features 1.0V:3.0H slopes and consists of 0–600 mm rockfill underlain by a 0–80 mm filter layer. A 50 m separation distance is maintained between the slope of the proposed pit and the toe of the retaining structure.

18.7.2 Site Conditions

The QL-TSF has been the subject of several geotechnical investigations conducted between 1995 and 2026. Geotechnical investigations at the QL-TSF identified layered subsurface conditions: a thin vegetation cover, mine waste rock encountered within the containment dikes, fill materials, a compressible peat layer (0.8–2.2 m), natural sand and silt deposits, a thin till layer, and bedrock at 23–36 m depth. Hydrogeologically, despite varying material hydraulic conductivities, groundwater data indicate a single aquifer system mainly controlled by fractured bedrock, allowing vertical water flow between layers.

18.7.2.1 Assessment of Liquefaction Potential

Liquefaction potential was assessed using simplified methods, indicating that certain layers of mine tailings, sand deposits, and silt deposits are considered susceptible to liquefaction. The estimated impacts include vertical settlements ranging from centimetres to decimetres and lateral displacements ranging from decimetres to metres in the vicinity of the planned pit. Given the conservative nature of these methods, a one-dimensional (1D) dynamic response analysis was also conducted to refine the assessment. The dynamic response analysis of the deposits demonstrated the absence of liquefaction potential at boreholes TF-01-26 and sCPT-01-26, located within the QL-TSF.

For personal use only




Figure 18-8: Typical Cross-Section AA' of the Proposed Retaining Structure shown on Figure 18-7

For personal use only

18.7.3 Stability and Settlement Analysis of the Proposed Retaining Structure

Static and pseudo-static stability analyses of the proposed retaining structure were conducted as part of this study to validate the proposed design concept. The analyses were performed on Section AA', shown in Figure 18-7.

18.7.3.1 Stability

The calculated factors of safety, presented in Table 18-6, exceed the minimum required values, thereby indicating satisfactory stability of the proposed retaining structure under the analyzed conditions.

Table 18-6: Results of the Stability Analyses for the Proposed Retaining Structure

Analysis case	Slope Component	Factor of Safety	Minimum Required Factor of Safety
Long-term - Static	Benches	1.7 - 2.1	1.3
Long-term - Static	Overall slope	2.1	1.5
Short-term - Pseudo-static	Benches	1.4 – 1.7	1.0
Short-term - Pseudo-static	Overall slope	1.6	1.1

18.7.3.2 Settlements

Given that the works will be carried out by excavation, no significant settlement associated with additional loading is anticipated. Consequently, no settlement analysis was performed as part of this study.

18.7.4 Risks

The required construction material quantities depend on the limits of the QL-TSF. At this stage, the undisturbed tailings profile has been estimated based on data obtained from boreholes as well as information presented in the PhD thesis Hydrogeochemical Behaviour of Mine Wastes from Spodumene Pegmatites (December 2023). It should be noted, however, that no borehole has directly defined or constrained the limits of the QL-TSF.

The tie-ins between the overburden slopes of the proposed retaining structure and the slopes of the planned pit located outside the tailings storage footprint should be subject to additional geotechnical verification, given the uncertainties associated with the topography and surface data provided by Elevra, particularly in areas of overburden cover and bedrock outcrops.

18.8 Lortie Lake Dyke

As part of the open pit expansion, the construction of a dyke at Lortie Lake is being considered to allow the extraction of mineral resources located beneath a portion of the waterbody. This dyke is intended to maintain the water level in the retained section of the lake, notably to limit impacts on fish habitat, while ensuring safe conditions for mining operations.

18.8.1 Design of the Lortie Lake Dyke

The dyke is located in the northern portion of Lortie Lake, north of the projected pit as shown on Figure 18-9.

For personal use only




Figure 18-9: Plan view of the proposed Lortie Lake dyke

A typical cross-section of the Lortie Lake dyke is shown in Figure 18-10. Preliminary design criteria and assumptions, based on applicable Québec standards and project-specific requirements, were established to evaluate the feasibility of the proposed Lortie Lake dyke, including its geometry, construction materials, setback distance, and reservoir operating conditions. Key design parameters include upstream and downstream slopes of 2.5H:1V, a 9.0 m-wide crest at elevation 400.0 m, a minimum freeboard of 1.5 m, and a minimum setback distance of 50 m from the pit crest. The proposed dyke section comprises a low permeability till core, a sand filter, a fine rockfill transition zone, and a coarse rockfill shell.

18.8.2 Sites Conditions

The stratigraphic conditions in the Lortie Lake area are characterized by fine lacustrine sediments (primarily a clayey silt to clay deposit with organic matter) overlying a gravelly sand deposit, which in turn overlies a dense till deposit and bedrock at variable depths. The clayey silt to clay deposit, with an assumed thickness of approximately 2 m, has geotechnical and hydraulic properties that remain unknown at this stage. This material may significantly influence the performance of the dyke, particularly with respect to stability, settlements, and seepage conditions.

From a hydrogeological perspective, Lortie Lake behaves as a perched lake system. The lake water level is maintained above the regional groundwater table due to the low hydraulic conductivity of the lacustrine sediments. The underlying aquifer system is interpreted as a single regional aquifer primarily hosted within the fractured bedrock and characterized by relatively higher transmissivity.

For personal use only




Figure 18-10: Typical section BB' of the proposed dyke identified on Figure 18-9

For personal use only

For personal use only

18.8.3 Stability and Settlement Analysis of the Lortie Lake Dyke

Static and pseudo-static stability analyses, as well as settlement analyses, of the Lortie Lake dyke were conducted as part of this study to validate the proposed design concept. The analyses were performed on Section BB', shown in Figure 18-10, identified as the most critical section of the Lortie Lake dyke.

18.8.3.1 Stability

The calculated factors of safety, presented in Table 18-7, exceed the minimum values recommended by the Canadian Dam Association (CDA), thereby indicating satisfactory stability of the proposed Lortie Lake dyke under the analyzed conditions.

Table 18-7: Results of the Stability Analyses of the Proposed Lortie Lake Dyke

Analysis Case	Loading Condition	Upstream Water Level (m)	Direction	Factor of Safety (min. – max.)	Minimum Required
Static	Short term (end of construction)	392.0 / 398.5	Upstream / Downstream	1.4 – 1.9	1.3
Static	Long term (permanent)	398.5	Upstream / Downstream	1.9	1.5
Pseudo-static	Short term (seismic loading)	392.0 / 398.5	Upstream / Downstream	1.1 – 1.3	1.1

18.8.3.2 Settlement

The results indicate that maximum crest settlements could reach approximately 1 m at the end of construction. These settlements are primarily attributed to the presence of underlying compressible lacustrine sediments. However, these results remain preliminary due to uncertainties associated with the geotechnical properties of this deposit.

18.8.4 Foundation Seepage Control

The presence of a clayey silt to clay layer at the bottom of the lake makes Lortie Lake a perched lake, thereby limiting hydraulic exchanges with the underlying aquifer. However, since this layer has not yet been fully characterized, there is a risk that it could be disturbed during construction activities or mining operations. Disturbance of this layer could create a hydraulic connection between the lake and the underlying aquifer, potentially resulting in increased seepage through the foundation soils, the development of internal erosion mechanisms, or a lowering of the lake water level.

To mitigate these risks, foundation seepage control measures may be required. Potential solutions include the installation of an upstream impermeable blanket or the construction of a soil-bentonite cutoff trench. The selection of the appropriate solution will depend on actual conditions observed during additional investigations.

18.8.5 Lortie Lake Emergency Spillway

An emergency spillway will be constructed in the northeastern section of Lortie Lake to maintain the existing drainage pathway. The spillway is designed to convey the 24-hour PMF peak discharge of 9.9 m^3/s from the identified watershed and prevent overtopping of the Lortie Lake dyke. The emergency spillway consists of two trapezoidal channels connecting Lortie Lake to the pond and the pond to the existing gravel road, as shown on Figure 18-11.




Figure 18-11: Plan View of the Lortie Lake Emergency Spillway

The channels are designed to operate under supercritical flow conditions immediately downstream of the lake and pond, ensuring that discharge is controlled by the upstream water levels and is not influenced by downstream conditions. The channels have base widths ranging from 6 m to 10 m, side slopes of 3H:1V, and are protected against erosion with geotextile and riprap lining. Culverts beneath the existing gravel road convey flow to an energy dissipation basin designed in accordance with established hydraulic engineering guidelines. The spillway alignment maintains the existing drainage pathway from Lortie Lake, allowing flood flows to re-enter the natural environment in a manner consistent with current conditions.

For personal use only

18.8.6 Risks

The principal risks associated with the design of the Lortie Lake dyke and recommended works are presented in Table 18-8.

Table 18-8: Risks associated with the Lortie Lake dyke and recommended works

Potential Event	Effect of the Potential Event	Recommended Works
Presence of a clayey silt to clay deposit with unknown geotechnical properties and thickness.	Differential and excessive settlements; dyke instability.	Conduct additional geotechnical investigations, including drilling, in situ testing, and laboratory testing, to characterize the clayey silt to clay deposit and assess the foundation conditions beneath the lakebed.
Borrow materials unsuitable for construction of the low permeability core et filters.	Inability to meet required material properties, potentially requiring a change in the dyke design concept.	Characterize potential borrow-source materials through test pits, and laboratory testing.
Seepage through the dyke body.	Internal erosion of the core.	Design filters suitable for the low permeability core material based on establish engineering guidelines.
Hydraulic connection between Lortie Lake and the underlying aquifer.	Seepage through foundation soils, potentially generating high hydraulic gradients and initiating internal erosion. The rate of lake water seepage into the foundation exceeds natural recharge, resulting in dewatering the remaining portion of Lortie Lake.	Design appropriate foundation seepage control measures, where required.
Erosion of the upstream slope due to wave action, ice loading, and wind.	Damage to the upstream slope and loss of material, potentially leading to dyke instability.	Design appropriate upstream slope protection, including riprap armouring and bedding/filter layers.
Vibrations generated by blasting operations associated with pit development.	Dyke deformation and instability.	Assess the effects of blasting-induced vibrations on dyke performance.

18.9 Site Water Management

18.9.1 Water Management Strategy

The general water management strategy for the Project aims to:

- Divert off-site, all non-contact water from non-perturbed areas surrounding the site.
- Manage by draining, conveying, and containing surface infrastructure runoff from the mill and waste (tailings and waste rock) management areas as well as underground water.
- Recycle a maximum of the mine site water from runoff, process, and groundwater for water supply purposes.
- For Total Suspended Solids sedimentation, retain water in ponds prior to treatment for release to the environment.
- Treat all contaminated water before releasing it to the environment.

The Water Management Plan (WMP) address the management of runoff water which has been in contact with the mine site as well as the clean water which flows through the Project site. The WMP update includes the tailings and waste rock storage facilities runoff water, which represents a major addition in impacted surface area to the Project. Runoff water and underground water from the open pit are also collected.

In preparing the WMP, priority was given to minimizing the impacted areas that generate contact water, to reduce the water volumes to be managed. On the other hand, reclaim of contact water is prioritized to maximize its re-utilization. Particular consideration was given to water management

For personal use only

based on watersheds. The WMP mitigates the volume of contact water inflows to be managed on-site by diverting clean water to the environment.

The WMP was updated to manage flows from the expansion scenario.

18.9.2 Basins and Ditches Design Criteria

The minimal design criteria applying to the ditches of TSF and WR are based on a design rainfall of a 100-year recurrence as per Directive 019. To prevent environmental impacts associated with mine tailing's accumulation areas, strict water management is required in accordance with Directive 019. All runoff and seepage water generated by these facilities must be collected through a drainage network designed to direct the water to treatment ponds or monitoring stations prior to any discharge into the environment.

This drainage network must be sized to withstand extreme hydrological events, including a 100-year flood combined with the average snowmelt over a 30-day period, while accounting for future climate scenarios. Ditches, conduits, and pumping basins must be engineered to meet this capacity. When accumulation areas pose a risk of groundwater contamination, protective measures must be implemented. These include hydrogeological studies, sealing systems or leachate collection systems, as well as groundwater monitoring and surveillance programs.

Finally, water management infrastructure must be designed with long-term climate projections in mind, including increased precipitation, more frequent flooding, permafrost thaw, and prolonged droughts. Post-closure and post-restoration monitoring programs must also be established to ensure the long-term integrity of the structures and the protection of water quality. For water management basins where retaining structures are considered, an emergency spillway and exit channel must be able to safely discharge the most severe flooding event. This is the probable Maximum Flood (PMF) as specified in Directive 019. Furthermore, freeboard requirements are as stipulated by Directive 019 (section 2.9.3.1) and the CDA guidelines.

18.9.3 Sediment Basins

Based on the design criteria and the water management approach previously described, the environmental design flood was established. The volume entering the basins was estimated considering summer and spring rainfall combined with snowmelt (over a 30-day period), with a coefficient of 18% to incorporate the effects of climate change. Summer rainfall, having generated higher volumes, was therefore used to calculate the volume of the pumping basins. Basin volumes will be attained partially through excavation and partially through the construction of dams.

18.9.3.1 Waste Rock Storage 4 Sedimentation basin

A sedimentation basin is required to manage contact runoff from Waste Rock Pile WR#4. The WR#4 sedimentation basin will be located at the south end of WR#4, where it can receive runoff from the contributing catchment. The basin will be formed partially in excavation and partially by a low earth dam constructed downstream of the excavation. Locally, surface runoff will drain naturally toward the basin due to the existing topography, and a perimeter collection ditch will be constructed as needed to intercept and convey contact water to the pond. Sedimentation ponds are widely used in mining to capture runoff, promote settling of suspended solids, and control suspended sediment discharge to the environment.

Water collected in the WR#4 sedimentation basin will be discharged to the environment once it meets applicable water quality criteria or pumped back to the process plant where needed. The conceptual design of the WR#4 sedimentation basin is shown on Figure 18-12. Sediment removal and pond maintenance will be planned so that adequate live storage and freeboard are maintained throughout operations, consistent with typical sedimentation pond design guidance for mine drainage

For personal use only

For personal use only




Figure 18-12: Sedimentation basin WR#4

18.9.3.2 Pit Sedimentation Pond

A second sedimentation basin will be constructed north of the site, adjacent to the open pit, to receive water pumped from the pit starting at Stage 5 of pit development. This basin will provide retention time for suspended solids to settle prior to discharge, in line with common practice for pit dewatering management at mine sites. Similar to the WR#4 basin, water accumulated in the pit dewatering sedimentation basin will be discharged to the environment once monitoring confirms that water quality meets prescribed criteria or returned to the process plant. The location and conceptual design of the pit dewatering sedimentation pond are shown on Figure 18-13.




Figure 18-13: Conceptual design of the Pit Sedimentation basin

18.9.4 Wastewater Treatment

All solid waste coming from the NAL mine and mill are considered to be non-acid generating and non-leaching. As such, a conventional sedimentation and physical-chemical treatment approach can be considered for the treatment of TSS. A water treatment facility may be required for this Project depending upon the availability of spare capacity of the reverse-osmosis treatment system that is currently installed.

Basins have been designed as a sedimentation basin for water management around HS. As such, no additional treatment has been planned. However, in the event that the water quality does not meet the required effluent criteria, additional water treatment infrastructure would be required.

A flow diagram of the current operating conditions at the NAL facility is shown in Figure 18-14. A flow diagram of the projected operating conditions is shown in Figure 18-15.




Figure 18-14: Flow Diagram at NAL Facility – Current Operating Conditions

For personal use only




Figure 18-15: Flow Diagram at NAL Site - Projected Operating Conditions

For personal use only

For personal use only

18.9.5 Uncertainties

The existing water treatment capacity (Reverse Osmosis) could be limited given the needs of the new infrastructure; it was assumed that TSS is the only potential contaminant. If the settlement capacities of new basins are not appropriate for finer TSS or for additional contaminants, use of additives to enhance the settlement or use of auxiliary treatment units will be used. Since 2024, exfiltration of ferrous water coming from OBP-1 is treated through flocculation with satisfactory results.

18.10 On-Site Buildings

18.10.1 Non-Mineral Waste Management

General, green, and regulated waste is sorted, stored, and disposed of according to the regulations and good practices. Bins are labelled for sorting. Two categories are defined: hazardous waste and non-hazardous waste.

For the non-hazardous waste, recyclable materials are collected and sent to a subcontractor for recycling, while non-recyclable materials are sent to the landfill site.

All categories of hazardous waste are collected by a licensed contractor and managed according to the regulations.

18.10.2 Explosives Magazines

Two explosives' magazines are managed on-site by the explosive's provider. The first is the cap magazine that houses priming explosives such as detonators, and the second explosive magazine will contain boosters and pre-shear explosives.

The magazines are strategically located in a fenced and gated area just outside of the mine site.

18.10.3 Administration Office

The administration building accommodates senior staff, including the general manager, human resources, health and safety, environment, geology, mining, procurement, and accounting, but excludes process plant personnel. In addition to the offices, the prefabricated wood frame building includes facilities such as lunchrooms, toilets, print rooms, conference rooms, etc. All workstations are provided with basic furnishings, internet, and telephone connections. Potable water is supplied to the kitchen and drinking fountains. Power outlets are provided in all rooms.

Additional administrative office space has been allowed for the expansion case.

18.10.4 Mine Workshop

The mine workshop is attached to the administration building and is a prefabricated structure, constructed of light steel, that was brought to site and erected. The garage has two service bays and a warehouse area, all of which are currently used by the mining contractor.

The mining workshop requires two additional service bays to accommodate the expansion fleet accounting for current utilisation.

18.10.5 Process Plant Building

The process plant building is a steel structured building with aluminium siding with an approximate surface area of just under 8,000 m^2. The building, which has a height of about 26 m, houses the concentrator, including ball mill and rod mill, ore sorters, flotation, and WHIMS. There are dedicated areas for offices, a control room, and electrical room, as well as the analytical laboratory. The building has some overhead cranes for service and maintenance.

The southern area of the process plant building currently houses the legacy carbonates plant. The carbonates plant area will be repurposed for the expansion converting the existing filters for re-purposed concentrate filters, concentrate shed, and flotation extension.

18.10.6 Assay Lab

The plant laboratories, metallurgical and analytical, are located inside the concentrator building. The metallurgical lab is fully equipped to operate bench scale flotation tests. The analytical laboratory is split into three sections, comprising a sample preparation room, a wet lab, and an instrument lab.

The analytical laboratory includes sample preparation equipment and analytical equipment, including ICP-EOS and Flame AA for elemental analyses. The analytical lab treats geological, grade control, and plant metallurgical samples.

NAL owns the laboratories and all installed equipment. NAL sub-contracts the operation of the analytical lab to a specialized and certified contractor.

The current laboratories are located next to the milling area in the concentrator building. The laboratories will be relocated to the carbonate plant area before Stage 2 to provide the required space for an additional ball mill with the expansion of plant capacity.

18.11 Communications

On-site communications consist of interconnected, pole-mounted fibre optic cables linking the various infrastructure buildings. The plant is equipped with communication fire wall protection, Ethernet switches and telephone server, Internet web server for the personnel's computer network, and a camera server for monitoring the plant and operations.

Additional fibre optic infrastructure is assessed as part of the expansion.

For personal use only

For personal use only

19 Market Studies and Contracts

Portions of this chapter have been adapted from the “Lithium Forecast Report” study prepared by Benchmark Minerals for Sayona dated Q1, 2026 (Benchmark Minerals, 2026). The author believes that the information in this study is relevant for the Mineral Reserves PFS report.

In the short-term, prices for 6% spodumene concentrate (SC6) are forecast to fluctuate between US$2,181 (2026) and US$1,260 (2031), with an average price of US$1,664 per tonne realized up to 2032. The long-term price after 2035 is US$2,430/t.

Forecast lithium product sale prices are shown in Table 19-1.

Table 19-1: Forecast Sale Prices (USD/t, real 2025)

Product	Lithium Carbonate	Lithium Hydroxide	Spodumene Concentrate (6%)
Incoterm	CIF Asia	CIF Asia	FOB Australia
2026	18,893	18,048	2,181
2027	16,500	16,000	1,838
2028	14,500	14,000	1,500
2029	15,500	15,000	1,670
2030	13,500	13,000	1,400
2031	13,000	12,500	1,260
2032	17,000	16,500	1,800
2033	19,000	18,500	2,040
2034	20,500	20,000	2,230
2035	21,000	20,500	2,300
2036	22,000	21,500	2,430
2037	22,000	21,500	2,430
2038	22,000	21,500	2,430
2039	22,000	21,500	2,430
2040	22,000	21,500	2,430

The Mineral Reserves PFS utilises the forecast sale prices shown in Table 19-1. An SC6 price of US$2,430 has been adopted for years past the 2040 forecast period.

19.1 Market Balance

Global lithium supply is expected to increase materially in 2026, despite the pricing pressure seen through much of 2025. Supply is forecast to rise by around 250 kt LCE year-on-year, or approximately 15%, including recycling.

China will provide most of the growth, adding ~46kt LCE, whilst African-based projects will add an extra 89kt LCE. Australia and South America will add ~40kt together in 2026 as several projects progress through commissioning and scaling phases.

Despite strong supply growth, the market is still expected to remain in deficit in 2026, as robust demand growth — particularly from electric vehicles and energy storage systems — continues to outpace new supply. By 2027, the surplus remains modest at less than 1% of total market size, pointing to a market that is close to balance.

As a result, prices are forecast to experience upward pressure over 2026 and 2027. Figure 19-1 shows the market balance forecast between 2027 and 2040.




Figure 19-1: Lithium Market Balance Forecast 2027 – 2040

19.2 Demand Forecast

Overall, demand is projected to grow at 7.1% Compound Annual Growth Rate (CAGR) from 2025 to 2040 under BMI's base case scenario. In the near term, lithium demand rises from 1,610kt LCE in 2025 to 1,885kt LCE in 2026 and 2,096 kt LCE in 2027, representing an increase of 17% and 11% year-on-year respectively.

The short-term lithium demand outlook remains constructive, with growth increasingly supported by electric vehicles (as the dominant demand base) and energy storage systems as the fastest-rising source of new demand. Portable devices and industrial applications remain comparatively stable but make only limited contributions to overall growth, reinforcing the increasingly central role of battery-driven demand.

Energy storage systems are emerging as the fastest-growing segment and the secondary driver of lithium demand. After a standout year of deployment growth, ESS makes an increasingly meaningful contribution to incremental demand, reflecting strong project pipelines, improving system economics and wider adoption across grid and behind-the-meter applications.

China remains the largest contributor to incremental demand, supported by strong EV adoption, battery manufacturing and energy storage system deployment. Europe remains the second most important growth market in the near term, while North America's contribution becomes more meaningful from 2027 onwards as electric vehicle and battery supply chains improve.

19.3 Supply Forecast

From 2025 to 2026, supply is forecast to increase by 260kt LCE (+15% year-on-year), with the largest increase coming from Africa, which is forecast to contribute 107kt LCE (+35%) to global supply growth in 2026.

Australian production will improve in 2026 driven by several projects including Greenbushes' new CGP3 plant and Pilgangoora's return to full capacity. China's forecast growth in 2026 will come from Zijin's new Xiangyuan and Lakkor Tso mica and brine projects.

South American lithium supply is projected to grow by around 22kt, or 5%, in 2026 with Argentina is expected to account for the majority of this increase followed by Chile and Brazil. Most of the

For personal use only

additional output will come from existing operations that are currently ramping up or undergoing an expansion phase.

From a long-term perspective, global supply is forecast to grow at CAGR of 9% over the next decade with all the current major producing regions seeing a reduction in their market shares. Recycling is expected to assume a more prominent position as significant end-of-life stock becomes available through the end of the decade.

North America and Europe, particularly through North American unconventional clay and DLE sources, will quintuple their share relative to 2026, combining for 10% of the world's output.

19.4 Product Pricing

Over the next seven years, prices for 6% spodumene concentrate are forecast to fluctuate between US$2,181 (2026) and US$1,280 (2031), with an average price of US$1,664 per tonne realized. Historical sale prices (2015-2025) as well as forecast lithium product sale prices are shown in Figure 19-2. The average sale price of 6% spodumene concentrate in the BMI analysis averages approximately US$2,025 between 2026 and 2040. The long-term price after 2034 is US$2,430/t.




Figure 19-2: Lithium Product Price Actuals and Forecast 2026 – 2040

19.5 Contract Sales

Through the merger consolidation of Sayona and Piedmont into Elevra, the offtake agreement between Sayona and Piedmont has been unwound. The underlying offtake agreements with Tesla and LG Chem remain intact. The contracts with Tesla for 125 kt over 3 years (refer to PLL ASX release 4 January 2023) and LG Chem for 200 kt over 4 years (refer to PLL ASX release 16 February 2023) remain in place. Further, Elevra also has an agreement with Mitsubishi for a total of 100 kt per year (including base volume and mutual options) over the 2025 to 2028 calendar years.

For personal use only

19.6 Packaging and Transportation

Spodumene concentrate is bulked transported by truck from the NAL Property to a rail transport boarding facility in Val-d'Or where concentrate is transferred into mineral covered railcar gondolas and then shipped on CN's mainline to the Québec City port.

19.7 Risks and Uncertainties

As shown by the actual values realised historically in Figure 19-2, the lithium market is extremely volatile and is expected to remain volatile in the near future.

For personal use only

For personal use only

20 Environmental Studies, Permitting and Social or Community Impact

This chapter describes the environmental, permitting, social and community aspects of the existing NAL operation and any additional considerations required for expansion project.

This Chapter is intended to provide all relevant information regarding environmental studies, permitting and social community impact for NAL's expansion projects. The expansion projects are to proceed in stages in order to reflect the permitting requirements for each stage

1. Permitting Stage 1.0 – reaching a 15-20% increase in the plant's capacity under the limit of 4,500 tpd, to be carried out in accordance with current regulations. This precedes Permitting Stage 2.
2. Permitting Stage 2.0 – increasing the plant's capacity to 6,500 tpd (''Milling capacity''). This includes infrastructure for Tailings Storage Facility TSF no.2.
3. Permitting Stage 3.0 – expansion of the mine pit for Phases 6 through 8. (''Pit expansion''). This includes tailings Storage facility TSF no. 3 and Waste Rock Pile HS no.4

NAL has already committed to delivering a complete Environmental, Social Impact Assessment for its Permitting Stage 3.0 and has proceeded since 2025 with multiple environmental, social, hydrogeological and geotechnical studies to support permitting efforts of its expansion project.

20.1 Summary

20.1.1 Permitting Stage 1.0 - Current Activities

Since the restart of operation in 2023, the site is staffed with a complete environmental team that ensures compliance with regulatory procedures and monitors social environmental activities at the site. The NAL project has existing environmental permits for mining operations including the disposal of waste rock, storage of tailings, water supply from open pit and tailings and final release of treated water to the environment. Elevra is currently operating in accordance with existing approvals and permits received from both provincial and federal authorities. Current activities are in the process of ramping up towards an increased annual throughput of 4500 tpd for the concentrator while the mine is authorized to extract 5,100 tons per day since approval of Phase 4.

20.1.2 Permitting Stage 2.0 - Milling Capacity Increase

Regarding the plant's capacity expansion, the project will be submitted in three main phases to the government authorities for permitting based on the addition of various equipment. It should be noted that the plant capacity expansion to 6500tpd will be made within the current building's footprint. The Government of Quebec guidelines regarding permitting requirements for capacity increase are subject to the standard authorization process under Section 22 of the Environment Quality Act, as long as the plant's capacity increase does not exceed 50% and is limited to 6,500 tons per day. Regarding federal authorities, Elevra has also received confirmation that the increase in the plant's capacity is not subject to the environmental assessment process under the Physical Activities Regulations (SOR/2019-285), provided that the total infrastructure, including the plant's capacity, remains within a 50% increase.

Permitting required for Stage 2.0 are currently in the application process and will be obtained in the coming months. For example, TSF-2 authorizations will soon be submitted to provincial authorities to obtain ministerial approval under section 22 of the Environment Quality Act (Q-2). Elevra recently received final approval for Waste Rock Pile #2 (HS) for several years of production.

For personal use only

20.1.3 Permitting Stage 3.0 Pit Expansion

The expansion of the mining pit will affect Lortie Lake by partially impacting the aquatic environment and fish habitat. The Regulation respecting the environmental impact assessment and review of certain projects (Q-2, r. 23.1) specifies in Section 2.2 of Schedule 2 that any project affecting an area greater than 15,000 m² of a lake or river must be submitted to the environmental assessment process, including a public hearing by the Bureau d'Audiences Publiques sur l'Environnement (BAPE). The pit expansion involves draining an area of several hectares of the lake, thereby triggering the provincial process for BAPE hearings. Accordingly, the Ministry of the Environment, Climate Change, Wildlife, and Parks (MELCCFP) has confirmed that the project will be subject to the provincial environmental impact assessment process. This assessment will require that the planned new mining infrastructure—TSF#3 and HS#4— be evaluated alongside the pit expansion.

For its part, the Department of Fisheries and Oceans Canada (DFO) will require that the impacts of mining activities on the fish habitat in Lortie Lake be offset by an approved habitat compensation project. Consultation will be undertaken with First Nations for the design of the compensation project(s). The new mining infrastructure (TSF & HS) could take place within a fish habitat, which would require registration under Appendix II of the Metal and Diamond Mining Effluent Regulations (SOR/2002-222). To do so, Elevra will need to demonstrate that the chosen solution was selected in accordance with the Guidelines for the Assessment of Alternatives for Mine Waste Disposal, as required by the Department of Fisheries and Oceans (DFO).

The extension of mineral resources under Lortie Lake will require the approval from the MRNF for the conversion of this lease area to a mining lease. The MRNF will require an update to the Closure and Rehabilitation Plan and the update of the approval by the MELCCFP. The BAPE process will provide the necessary decree to obtain the permits required for the conversion of the area to a mining lease.

20.2 Environmental Baseline and Impact Studies

20.2.1 Physical Environment

20.2.1.1 Climate

The Val-d'Or area experiences a subarctic continental sub-humid climate, characterized by short, cool summers and long, cold winters. The nearest weather monitoring station with data on climate properties maintained by Environment Canada (climat.meteo.gc.ca) is the Val D'or station, approximately 40 km south of the Property. In 2025, NAL proceeded with an independent review of climatic data from 1991-2020 and performed forecasts with various climate change scenarios up to 2070. Data obtained from the Val-d'Or weather station, located 40 km to the south, between 1991 and 2020 indicates that the average daily temperature for January was -16.3 °C and the daily average temperature in July was 17.7 °C. The record low during this period was -42.7 °C, and the record high was 36.1 °C.

The total average annual precipitation at Val d'Or is 868 mm, with peak rainfall occurring during September (102 mm average), July (101 mm average) and August (93 mm average). Snowfall is light to moderate from October to April, with an annual average of 228 cm.

20.2.1.2 Topography

The regional study zone is in the physical geography unit of the region's lower plateau, called the Bas-Plateau de l'Abitibi. The slightly hilly relief was moulded and smoothed out somewhat by the introduction of thick clay deposits from the Ojibway-Barlow Lake vestiges. The site also has a few chain of rocky cliffs that cut across the clay plain, including Mont-Vidéo, a hill that rises to 470 m (m.a.s.l.). The other hills are between 420 m and 450 m high, and the lowlands have an average altitude of around 360 m.

The Property contains small hills and is located at a mean elevation of 400 m.a.s.l., but the topography is generally flat with swamps, sand plains and an esker along its edge.

20.2.1.3 Geology

The study zone lies within the Superior Province of the Canadian Shield. The rocks in this zone date back to the Archean era. The batholith consists of several parallel dykes, ranging from pegmatite to spodumene, feldspar and quartz. These dykes are nearly 3 km long and run northwest/southeast. They are present to a maximum depth of 260 m, are very continuous and contain a uniformly distributed spodumene mineralization.

20.2.1.4 Geomorphology

The glacial footprint of the existing landscape is the one left by the last glacier in the region, nearly 9,000 years ago. A key feature of the last deglaciation in Abitibi-Témiscamingue is the development of the Harricana till. This till delineates the convergence of the Hudson and the Nouveau-Québec glaciers. Several major fluvio-glacial deposits, e.g., eskers and spreads, emerged during the glacial retreat.

The region is essentially characterized by the presence of a continuous cover till, generally over 1 m in thickness, over the pit and the mining complex. The existing till has an average permeability and can be considered a discontinuous aquifer, enabling the flow of groundwater.

20.2.1.5 Hydrography

Three lakes – Roy, Legendre and Lortie – are the main bodies of water near the mine, as shown in Figure 20-1. Lortie Lake, located north of the planned pit, is an isolated lake with no surface outlet. The Hydrological Atlas of Canada indicates that it drains northwest, into the Landrienne River basin. The Harricana till is located at the Continental Divide, between the waters flowing towards the Landrienne River, a Harricana River tributary, and the Barraute Stream, a Laflamme River tributary.

The mining site is located at the head of the sub-watersheds of the Laflamme, Fiedmont and Landrienne Rivers. The concentrator and tailings site are in the Fiedmont River sub-basin, the area of waste rock accumulation is in the Landrienne River basin, and the pit is at the intersection of the three sub-watersheds.

Further hydrologic studies were performed in 2025 in order to define impacts of mining infrastructures on the hydrologic network for the Lortie Lake, as well as northern catchment basins of Riviere Landrienne and the R1 (East and R1 (West) affluent basins to Lortie Lake. These hydrological reports define any potential required mitigation measures and form an intrinsic part of the complete ESIA.

For personal use only

For personal use only



Figure 20-1: Location of Lakes Around NAL Operations

20.2.1.6 Background Surface Water Quality

As part of the Environmental and Social Impact Assessment (ESIA) completed in 2012, two characterization campaigns of the surface water and sediment quality were conducted in 2009 and 2010. The quality of the surface water of the three local lakes and three nameless streams was analysed and compared to known quality criteria. Globally, the environmental protection criteria for the analysed substances were rarely exceeded. Some exceedances have been observed for fluoride, total phosphorus, pH, aluminium, iron, manganese, and mercury.

NAL's site environmental team performs a surface water monitoring program is carried out yearly to ensure continuous monitoring of surface water quality around the site.

For personal use only

20.2.1.7 Background Sediment Quality

The stations for which a stream sediment quality analysis were performed are the same as those used for the water quality assessments. The substances analysed in the sediments include metals and organic compounds, such as oils, greases, and aliphatic hydrocarbons (C10–C50). The 2010 campaign also included an analysis of polychlorinated biphenyls (PCBs). The Lortie Lake station contains more aluminium, lithium, potassium, sodium, and zinc than other stations. This difference can be explained by the nearby presence of the former Québec Lithium tailings storage facility that operated from 1955 to 1965. A polishing basin discharged directly into Lortie Lake. Petroleum hydrocarbons were detected but no PCBs were detected. Some exceedances of criteria have been observed for cadmium, arsenic, mercury, lead, and zinc.

20.2.1.8 Hydrogeology

An integrated hydrogeological study and numerical modelling was conducted for the planned expansion of the open pit mine for NAL in 2025. The work completed supports regulatory requirements (Directive 019 – Industrie minière) and aims to inform the feasibility of pit expansion, new tailings storage (TSF-3), and waste rock management.

The study included:

- Compilation and validation of geological, hydrogeological, and piezometric data from 2010–2025, including previous studies, recent fieldwork, and public datasets.
- Development of a conceptual hydrogeological model based on stratigraphy, aquifer properties, and groundwater flow mechanisms.
- Construction and calibration of a numerical groundwater model to simulate current and projected conditions, including sensitivity analyses.

Notable findings form this study are:

- The site stratigraphy comprises permeable granular deposits (mainly Quaternary sands), glacial till of lower permeability, and fractured bedrock. Groundwater flow is primarily controlled by topography and the distribution of these units.
- Hydraulic conductivities range from approximately 1×10^{-5} m/s in sands to 1×10^{-8} m/s in bedrock, as determined by slug and pumping tests.
- Regional groundwater flow is generally west to west-northwest, following topographic gradients and natural drainage. Local variations are influenced by the geometry of permeable units and natural discharge zones. Importantly, no hydraulic connection was identified between Lortie Lake and the aquifers in the pit zone.
- Groundwater levels are highest in the central and northern site areas (>400 m elevation), decreasing toward lower-lying zones. Both overburden and fractured bedrock aquifers are present.
- Pumping tests have confirmed that the aquifer yield of the Harricana moraine is well below 25m³/h which is a threshold defined by MELCCFP Directive 019 (2025).

The numerical model predicts drawdown (dewatering) requirements for the proposed pit, estimates necessary pumping rates, and delineates the hydraulic zone of influence. Sensitivity analyses show the model's response to changes in precipitation and hydraulic conductivity.

The hydrogeological work carried out establishes a solid technical basis for the preliminary feasibility of mine expansion, identifying key aquifer characteristics, flow regimes, and dewatering requirements. The integrated approach ensures that groundwater management strategies are aligned with both operational and environmental objectives and will support regulatory submission requirements.

20.2.1.9 Groundwater Quality

The quality of the groundwater is very good and only two exceedances of criteria for iron and nickel have been observed in ESIA baseline studies produced in 2018. Groundwater monitoring is performed on a regular basis, twice a year, covering the whole site area. With a few exceptions, the groundwater on the property is of the calcic bicarbonate type, representative of water in the recharge zone.

20.2.2 Biological Environment

20.2.2.1 Vegetation

The regional study zone is located within the western balsam fir-yellow birch bioclimatic domain. The forest landscape is dominated by stands of pine and white spruce, intermingling with white birch trees.

The regional study zone includes several open environments, e.g., farmer's fields, non-forest wetlands, recent logging areas, etc., but is nonetheless primarily comprised of forest. Conifer stands predominate, followed by mixed stands. Hardwood or deciduous stands are less frequent and consist almost solely of young stands or trees undergoing regeneration. The numerous disturbances of the late '70s, e.g., epidemics, logging, plantations, and windfall, all resulted in major occurrences of these types of stands.

According to the Centre de Données sur le Patrimoine Naturel du Québec (CDPNQ), the sector concerned by the Project does not include any plant species designated as threatened, vulnerable or likely to be thus designated. There were no special-status species observed in the ESIA baseline studies of 2010 and an update of the baseline environmental studies conducted in the summer of 2025 confirmed the findings of 2010.

The sector contains no Exceptional Forest Ecosystems (EFEs), forest stands with a phytosociological interest or biological refuges. Furthermore, the past few years have seen considerable logging activity.

20.2.2.2 Wetlands

There are numerous forest wetlands in the deciduous or mixed stands, or in areas where trees were recently felled.

Types of wetlands include open bogs, wooded bogs, anthropogenic wet meadows, treed swamps (including anthropogenic), and marshes. Wetland vegetation is characterized by species such as sphagnum moss, sedges, willows, and various obligate wetland plants (e.g., broadleaf cattail, bluejoint reedgrass, marsh cinquefoil).

These zones are characterized by hydric and sub-hydric drainage. The area also has non-forest wetlands consisting of alder groves and stripped wetlands.

20.2.2.3 Aquatic Fauna

Fish Fauna and Aquatic Habitats

Overall, the quality of the fish habitats is very poor, which is due to the homogeneity of the aquatic habitats, very low flow rates that are intermittent or below ground with numerous obstacles. According to the MRNF (formerly MERN), there may be up to 49 fish species in the Abitibi-Témiscamingue watercourses; with 15 of these species having already been identified in the sectors surrounding the operation.

For personal use only

For personal use only

Through samplings, nine species of fish were confirmed as present in the inventoried bodies of water around the mine, specifically lake cisco, brook stickleback, lake whitefish, goldeye, monkfish, white sucker, pearl dace, brook trout and yellow perch. In addition to the species identified, the MRNF noted the presence of three other species in the area's lakes; they are the brown bullhead (Ameiurus nebulosus), the northern pike (Esox lucius) and the walleye (Sander vitreus), which are all found in Lake Legendre. None of these species has a special status, be it provincial or federal. Results from the update of the baseline environmental studies conducted in the summer of 2025 do not reveal any additional fish species.

Herpetofauna

Several species of herpetofauna were observed during the survey conducted in the summer of 2025. Of all these species, none is designated as vulnerable or likely to be designated as vulnerable. All these species are widely distributed in the region. A special effort was made to observe the wood turtle (Glyptemys insculpta), which is likely to be found in the study area, but no sightings of this species were recorded during the 2025 ecological inventory campaign.

Avian Fauna

Although no species with a threatened status were observed in 2012, the 2025 survey revealed the presence of the Common nighthawk, the Evening Grosbeak, and the Rusty blackbird in the study area. These three species are classified as vulnerable or are likely to be classified as vulnerable.

Mammals

The local study zone could be a habitat for a wide variety of mammals. The large animals most likely to be found are the moose (Alces americanus) and the brown bear (Ursus americanus). The presence of white-tailed deer (Odocoileus virginianus) is unlikely.

The site zone potentially includes 13 species of small mammals and seven species of bats, five of which could be designated threatened or vulnerable. The small mammals in this latter group are the rock vole (Microtus chrotorrhinus) and the southern bog lemming (Synaptomys cooperi), while the bats are the silver-haired bat (Lasionycteris noctivagans), the eastern red bat (Lasiurus borealis) and the hoary bat (Lasiurus cinereus).

While the sub-sections for the different animal groups indicate the possible presence of a few special-status species, the information obtained from the CDPNQ in 2010 reveals that no threatened or vulnerable faunal species, or faunal species likely to be designated as such, were identified in the site zone. The 2025 wildlife inventory revealed the presence of five bat species, four of which are classified as vulnerable or likely to be designated as vulnerable.

20.2.3 Social Considerations

20.2.3.1 Territory Use

The NAL Project is situated in the administrative region of Abitibi-Témiscamingue (08), within the boundaries of the Abitibi RCM. All planned mining infrastructure for the Project are within the municipality of La Corne.

The lands in the immediate area of the site are mostly comprising Crown Land, hence a territory under the administrative responsibility of the MRNF.

Of the nine major land uses for the territory identified in the Abitibi RCM's territory development and activities plan (Schéma d'Aménagement et de Développement, SAD), three major assignments concern the surrounding mining site:

- Forestry.
- Recreational.
- Vacationing resorts.

Most of the land near the mining site is designated for forestry purposes. In the immediate area of the mining site, there is a recreational zone around Lake Roy, Lortie Lake, and Mont Vidéo. This zone has mixed zoning and allows mining activities. Lake Legendre is considered a year-round vacation area with residences.

20.2.3.2 Development and Activities

As regards the major activities included in the SAD, the Abitibi RCM wants to ensure available space for the development of various types of industries, while protecting the existing environment and activities. The need to minimize the impact of mining activities on nearby sectors, protect the aquifers, including those of the Harricana moraine, ensure adequate protection for the various natural environments and their elements of interest, and promote the integrated enhancement of forest resources should be highlighted.

20.2.3.3 Land Use

The three municipalities included in the mining site area are characterized by a low land use density. The residential environment is concentrated in urban sectors, all of which are less than 15 km from the Project site. There are no landholdings on the planned site. However, two groupings of private, resort-type homes are located nearby at Lake Legendre and Mont Vidéo.

20.2.3.4 Public Utilities Infrastructure

With respect to transport infrastructure, the regional sector includes a section of provincial Route 111, which links Val-d'Or and Amos (blue line in Figure 20 2), and runs through La Corne. Two regional routes also pass through the zone: Route 386, between Landrienne and Amos (purple line in Figure 20 2), and Route 397, between Barraute and Val-d'Or (red line in Figure 20 2). The Abitibi RCM's electricity network is managed by Hydro-Québec and a 120 kV power line crosses the site.

20.2.3.5 Recreation and Tourism Activities

The Centre de plein air du Mont-Vidéo, an outdoor recreation centre, is located approximately 2 km to the east of the Project. This complex includes a downhill skiing centre, snowshoe, and cross-country ski trails, hiking and mountain bike trails, a campsite with a beach on the shore of Lake Roy and a number of summer camps. Fishing and hunting, in turn, are regularly practiced throughout the region. Snowshoe and mountain bike trails pass near Lortie Lake and will need to be relocated as NAL expands its activities.

The recreational or leisure network includes numerous snowmobile trails and a few quad trails, which are currently being developed.

20.2.3.6 Forestry and Agricultural Activities

Selected areas of Crown land located near the mining site are subject to forest logging rights, i.e., guarantee of supply. The area is included in the common area of UAF 086-51. There are no agricultural zones designated as protected under the Act respecting the preservation of agricultural land and agricultural activities on the site dedicated to Project infrastructure.

For personal use only




Figure 20-2: Provincial and Regional Routes Around NAL Operations

20.2.3.7 First Nations

The Project site is situated at the boundary of the First Nations communities of Lac Simon and Pikogan. Since mining operations have commenced NAL have consistently held constructive dialogue with First Nations communities. The 2018 ESIA review report of the Federal government Agency notes that taking into account the mitigation measures anticipated by NAL, the Project was

For personal use only

For personal use only

not likely to cause significant adverse environmental effects on the current use of lands and resources for traditional purposes and on structures, sites or things of historical, archaeological, paleontological or architectural significance in the study area.

First Nations participation in the existing monitoring committee has been constructive to date and NAL will continue close dialogue to ensure mitigation measures are put in place with the expansion project to limit the impacts of its operations.

20.2.3.8 Archaeological and Heritage Potential

While there are no known archaeological sites within the boundaries of the regional study zone, a 2010 study on the area's archaeological potential had been carried out, with the goal being to adequately evaluate the probability of prehistorical and historical human occupation. This study had indicated the presence of two 25 m shorelines encircling Lake Roy and Lortie Lake having a strong archaeological potential.

As part of the expansion project's environmental studies, NAL proceeded with an updated archaeological potential study as well as a complete archaeological inventory for the study zone. The archaeological inventory of the Zone of interest (ZDP) did not reveal any archeological sites despite a previously identified potential during preliminary analyses. The report confirms that NAL can undertake it's work without constraints from an archaeological point of view.

20.3 Project Permitting

In 2023, Sayona has restarted mining and ore treatment at NAL, in accordance with existing approvals by provincial and federal authorities. The concentrator is currently authorized for a throughput of 4,500 tpd while the mining is permitted for 5,100 tpd.

At the federal level, the impact study of the initial work was carried out in accordance with the Canadian Environment Assessment Agency ("CEAA") under the Canadian Environmental Assessment Act. The CEAA issued a Study Report in February 2018. Authorization process was completed in 2022 and updated in 2025.

At the provincial level, permits have been obtained for all actual components. Some original permits were transferred to North American Lithium following acquisition of the site in 2017. Sayona acquired the rights on NAL, including all permits and authorizations following acquisition in 2021. All current permits authorize the operation of the mine and the processing plant.

20.3.1 Ministry of Environment, Fight Against Climate Change, Fauna, and Parks

The MELCCFP is the provincial authority that issues ministerial environmental permits for all industrial projects. Under section 22 of the Environment Quality Act (Q-2), the ministry authorizes industrial projects. Its authority applies to both new projects and modifications to existing projects.

To increase the milling capacity, additional authorizations will have to be obtained for the concentrator's capacity and for the implementation of new infrastructure such as TSF#2. Other authorizations will be required, such as for the implementation of the new crushing circuit, the petroleum product storage area, and air emissions control equipment.

The open pit mine expansion (Pit expansion) on Lortie Lake will be subject to more permitting effort as a complete environmental assessment process is required. This expansion project of the open pit mine also involves the addition of a waste rock pile #4 (HS#4) and a new TSF #3. All these project components are subject to the environmental assessment process under the Environment Quality Act (Q-2) and will be reviewed by the BAPE over the next two years to obtain the government decree for the extension of the mining lease.

For personal use only

20.3.2 Existing Permits

The NAL Property possesses all permits for current operations including Phase 4 mining activities up to 5100tpd as well as milling capacity of 4500tpd. These include activities, such as, but not limited to;

- Open pit mine.
- Spodumene concentrate mill.
- Lithium carbonate refinery.
- Tailings management area no. 1.
- Process water pond.
- Industrial wastewater treatment plant.
- Waste rock pile no. 2.
- Waste rock pile no. 3.
- Overburden dump no. 1.
- Overburden dump no. 2.
- Fuel pad and Above ground fuel storage tank and its equipment

20.3.3 Ongoing Permitting Activities

The permitting process is well advanced for additional Project components or modification of existing authorizations:

- Permitting Stage no.1 – Authorization to reach 4500 tpd
- Permitting Stage no.2 - Mining Phase #5 with an increase of mining and milling capacity to 6500 tpd as well as TSF no.2
- Permitting Stage no.3 – Mining Phases 6 to 8 + TSF no.3 and Waste Rock Pile no.4.

Environmental Studies have been carried out in 2025 to support the ESIA efforts for the Permitting Stage No. 3

20.3.4 Ministry of Natural Resources and Forests – Lands Sector

Various land occupation leases have been obtained from MRNF, including the leases for the industrial sector, the current HS#2, including the proposed extension, and the HS#3.

20.3.5 Ministry of Natural Resources and Forests – Forestry Sector

Permits for tree cutting will be required for new infrastructures development such as TSF#2 or pit extension and will be obtained as per the site development project timing.

20.3.6 Department of Fisheries and Oceans of Canada

It is the mandate of the DFO to ensure perennity of the fish habitat. Since part or all of Lortie Lake is expected to be affected by the expansion of the mining pit, an amendment to the DFO permit will be made during the next phases of the project. This amendment will require that fish habitat losses be offset through compensatory projects.

For personal use only

20.4 Other Environmental Concerns

20.4.1 Waste Rock, Tailings and Water Management

20.4.1.1 Tailings

In 2012, a geochemical characterization of a combined tailings sample, i.e., tailings from spodumene concentrate production and tailings from lithium carbonate production, was carried out by Golder Associates. Metals content measurements, static Acid Rock Drainage (ARD) testing and Metals Leaching (ML) static testing have been carried out on solid samples and the liquid fraction of tailings pulp.

The results showed that combined tailings and ARD tests are below the limits of the Directive 019 of the MELCCFP However, leaching tests and liquid fraction analysis showed that low pH as well as copper, lithium, zinc, sodium, and sulphate concentrations could be a concern. Therefore, a liner was installed under TSF#1.

In 2018, seven samples of tailings produced from spodumene concentrate production had been analysed. The results showed that tailings from spodumene concentrate production were below limits for both ARD, nor ML.

Whereas the geochemical test was previously relevant, it no longer represents the tailings management approach going forward. The current plan is to have only spodumene tailings. The first results of the ongoing geochemical characteristics of these tailings show that they are still below the limits for both ARD, nor ML. For this reason, and pending final confirmation, TSF #2 and #3 will be constructed with only a liner at the base of the pond to provide enhanced protection for the groundwater, while still allowing the use of filter dikes.

20.4.1.2 Waste rock

Tests on waste rock were conducted as part of a geochemical study performed by Golder Consulting in 2012. A total of 65 samples from six different overburden areas were analysed for their metal contents, ARD potential, and ML potential. A complementary geochemical study was conducted at Unité de Recherche et de Service en Technologie Minérales (URSTM) in 2013. Column testing was also carried out on four samples representing the main waste rock lithologies.

Results from the geochemical studies showed that waste rock is neither ARD, nor ML; therefore, no special requirements are required by the MELCCFP (formerly MELCC) for stockpiling and water management. In fact, the MELCCFP also allows use of waste rock for construction purposes at the site, e.g., road, lay-down areas, etc.

Static and kinetic tests are currently being conducted to confirm the absence of acid mine drainage or metal leaching. These new tests are being performed on waste rock and mine tailings from mining phases 6 and 7. Results are expected by September 2026 and will be incorporated into the project's development. Although the results are only preliminary, all indications are that the tests will be like those conducted in 2013.

Further tests are currently being conducted by the Centre de Transfert Technologique en Écologie Industrielle (CTTÉI) to explore the potential for use of certain lithologies from the waste rock. Initial results also indicate that this waste rock is safe, which could allow for its use as civil engineering materials. This parallel study would confirm the absence of ARD and ML potential.

20.4.1.3 Emissions of air contaminants

Since NAL resumed operations in 2023, the presence of crystalline silica, beryllium, arsenic, and lead has been under monitoring. These contaminants have been detected in areas with high dust levels, such as the crusher. All workers in contact with operational dust must wear appropriate PPE. NAL regularly assesses workers' exposure to these airborne contaminants, and necessary measures are immediately implemented when a risk is identified.

To address the environmental risks associated with these contaminants, the site is equipped with a range of instruments to measure atmospheric concentrations. Atmospheric concentrations of the elements measured currently are all below regulatory thresholds. As part of the increase in processing capacity and the expansion of the mining pit, atmospheric modeling involving multiple scenarios is currently underway, and preliminary results will be shared with government authorities. This study is necessary to obtain the ministerial authorizations required under the Environment Quality Act (Q-2).

20.4.2 Regulatory Context

20.4.2.1 Provincial Procedure for Environmental Impact Assessment

Mining projects are subject to Quebec's Environment Quality Act (EQA, c. Q-2). Under this act, projects requiring environmental impact studies are identified in the Regulation Respecting Environmental Impact Assessment and Review (Q-2, r. 23.1).

All greenfield mining projects are subject to this procedure. For projects which have already been authorized by the government, expansion projects do not necessarily make it subject to the environmental impact assessment procedure, except if the project triggers an increase of more than 50% of authorized area or 50% increase of the concentrator capacity. Elevra has received confirmation from both the provincial and federal governments that the project to expand the plant's capacity (Milling capacity) is not subject to environmental assessments.

Regarding the Pit Expansion project, seeing that it would impact an area greater than 15,000 m² on Lortie Lake, this would then trigger the requirement for an additional and revised environmental assessments. The expansion project of the pit (Pit expansion) will be subject to this procedure given its impact on Lortie Lake and relevant HS#4 & TSF#3.

20.4.2.2 Federal Procedure for Environmental Impact Assessment

The impact study of the initial project was submitted in February 2013 to the Canadian Environment Assessment Agency (CEAA) under the Canadian Environmental Assessment Act (S.C. 1992, c. 37). The CEAA issued a Study Report in February 2018 presenting the Agency requirements for atmospheric environment, water quality, fish and fish habitats, birds, and bird habitats as well as traditional land and resources use.

As per the Physical Activities Regulations (SOR/2019-285), the Project would be subjected to the new Impact Assessment Act (S.C. 2019, c. 28, s. 1) procedure if the expansion of the Project results in an increase in the area of mining operations of 50% or more and the total ore input capacity reaches 5,000 today or more after the expansion. Both conditions must be triggered to be subjected to this procedure, which is not the case for all phases of the expansion.

20.4.2.3 Laws and Regulations for Environmental Impact Assessment

The Project is mainly subject to several provincial and federal regulations. Main laws and regulations that are applicable are listed in Table 20-1.

For personal use only

For personal use only

Table 20-1: Provincial and Federal Acts and Regulations

Acts and Regulations
PROVINCIAL
Environment Quality Act (c. Q-2)
Regulation respecting the application of section 32 of the Environmental Quality Act (Q-2, r. 2)
Regulation respecting the supervision of activities with respect to their impact on the environment (Q-2, r. 17.1)
Regulation respecting the application of the Environment Quality Act (Q-2, r. 3)
Regulation respecting the environmental impact assessment and review of certain projects (Q-2, r.23.1)
Design code of a storm water management system eligible for a declaration of compliance (Q-2, r.9.01)
Clean Air Regulation (Q-2, r. 4.1)
Regulation respecting the operation of industrial establishments (Q-2, r. 26.1)
Snow, Road Salt and Abrasives Management Regulation (Q-2, r. 28.2)
Regulation respecting pits and quarries (Q-2, r. 7)
Regulation respecting the declaration of water withdrawals (Q-2, r. 14)
Regulation respecting mandatory reporting of certain emissions of contaminants into the atmosphere (Q-2, r. 15)
Regulation respecting halocarbons (Q-2, r. 29)
Regulation respecting hazardous materials (Q-2, r. 32)
Regulation respecting the reclamation of residual materials (Q-2, r.49)
Regulation respecting activities in wetlands, bodies of water and sensitive areas (Q-2, r.0.1)
Protection policy for lakeshores, riverbanks, littoral Zones and floodplains (Q-2, r. 35)
Water withdrawal and protection regulation (Q-2, r. 35.2)
Land protection and rehabilitation regulation (Q-2, r. 37)
Regulation respecting the charges payable for the use of water (Q-2, r. 42.1)
Directive 019 sur l'industrie minière (2025)
Protection and rehabilitation of contaminated sites policy (1998)
Mining Act (c. M-13.1)
Regulation respecting mineral substances other than petroleum, natural gas and brine (M-13.1, r. 2)
Threatened or Vulnerable Species Act (c. E-12.01)
Regulation respecting threatened or vulnerable wildlife species and their habitats (E-12.01, r. 2)
Regulation respecting threatened or vulnerable plant species and their habitats (E-12.01, r. 3)
Compensation Measures for the Carrying out of Projects Affecting Wetlands or Bodies of Water Act (M-11.4)
Act respecting the conservation of wetlands and bodies of water (2017, chapter 14; Bill 132)
Watercourses Act (c. R-13)
Regulation respecting the water property in the domain of the State (R-13, r. 1)
Conservation and Development of Wildlife Act (c. C-61.1)
Regulation respecting wildlife habitats (C-61.1, r. 18)
Act respecting the lands in the domain of the state (c. T-8.1)
Regulation respecting the sale, lease and granting of immovable rights on lands in the domain of the State (c. T-8.1, r. 7)
Sustainable Forest Development Act (c. A-18.1)
Regulation respecting the sustainable development of forests in the domain of the State (c. A-18.1, r. 0.01)
Regulation respecting forestry permits (c. A-18.1, r. 8.)
Building Act (c. B-1.1)
Safety Code (B-1.1, r. 3)
Construction Code (B-1.1, r. 2)
Explosives Act (c. E-22)
Regulation under the Act respecting explosives (E-22, r. 1)
Cultural Heritage Act (c. P-9.002)
Occupational Health and Safety Act (c. S-2.1)
Regulation respecting occupational health and safety in mines (S-2.1, r. 14)
Highway Safety Code (c. C-24.2)
Transportation of Dangerous Substances Regulation (c. 24.2, r. 43)

Acts and Regulations
FEDERAL
Impact Assessment Act (S.C. 2019, c. 28, s. 1)
Physical Activities Regulations (SOR/2019-285)
Designated Classes of Projects Order (SOR/2019-323)
Information and Management of Time Limits Regulations (SOR/2019-283)
Fisheries Act (R.S.C., 1985, c. F-14)
Authorizations Concerning Fish and Fish Habitat Protection Regulations (SOR/2019-286);
Metal Mining Effluent Regulations (SOR/2002-222)
Canadian Environmental Protection Act (S.C. 1999, c. 33)
PCB Regulations (SOR/2008-273)
Environmental Emergency Regulations, 2019 (SOR/2019-51);
Federal Halocarbon Regulations (SOR/2003-289)
National Pollutant Release Inventory
Species at Risk Act (S.C. 2002, c. 29)
Canadian Wildlife Act (R.S.C., 1985, c. W-9)
Wildlife Area Regulations (C.R.C., c. 1609)
Migratory Birds Convention Act, 1994 (S.C. 1994, c. 22)
Migratory Birds Regulations (C.R.C., c. 1035)
Nuclear Safety and Control Act (S.C., 1997, c. 9)
General Nuclear Safety and Control Regulations (SOR/2000-202)
Nuclear Substances and Radiation Devices Regulations (SOR/2000-207)
Hazardous Products Act (R.S.C., 1985, c. H-3)
Explosives Act (R.S.C., 1985, c. E-17)
Transportation of Dangerous Goods Act (1992)
Transportation of Dangerous Goods Regulations (SOR/2001-286)

20.5 Social and Community Impacts

20.5.1 Consultation Activities

As part of the management of mining operations at the site, numerous consultation activities and/or information sessions are organized on a regular basis. A monitoring committee has been in place since mining activities resumed in 2022. A good neighbour committee with Lake Legendre residents is also active. These committees allow Elevra to share information about the mine's development and public results, and to discuss issues surrounding the neighbourhood with committee members. These committees facilitate constructive dialogue on issues raised by citizens or organizations outside Elevra.

For the Pit expansion, stakeholder consultations are ongoing and will be finalized for the ESIA. The purpose of these consultations is to gather and address the concerns of these stakeholders. Those consultations are focussing on the expansion of the pit. Elevra is expected to follow up with the same stakeholders to present the changes that have been incorporated following the first round of consultations.

20.5.1.1 Committee Composition

The Monitoring Committee is composed of citizens from the Abitibi RCM, regional representatives, and representatives from the First Nations communities concerned.

The Lake Legendre Good Neighbour Committee is composed of five citizens from Lac-Legendre, the nearest residential area, and was established in 2024 to discuss concerns related to noise, vibrations, and water quality.

For personal use only

For personal use only

20.6 Water Management

Water management are important aspects of environmental compliance and operational effectiveness of the mining site. To support NAL expansion, a site-wide water balance was performed based on major infrastructure expansion footprint. Water balance shows excess of water on the overall site for all stages of development. Water infrastructure (ponds and ditches) was added to the project to ensure proper environmental and operation water management. These infrastructures are shown in Table 20-2 below and more details are provided in Chapter 18 – Project Infrastructure.

Table 20-2: New Water Management Infrastructure

Water Infrastructure
HS-4 Ditches
TSF-3 Ditches
Pond BO_14 - Mine water (Phase 5 and beyond)
Pond BO_15 - Runoff water HS-4 and TSF-3

20.7 Mine Closure and Reclamation Plan

As per the provisions of Section 232.1 of the Mining Act (R.S.Q., c.M-13.1), any entity that engages in mining exploration activities must submit a restoration plan for its mining site. The restoration plan must be prepared according to the specific requirements of the MRNF's document Guidelines for preparing a mining site rehabilitation plan and general mining site rehabilitation requirements. Since then, there have been amendments to the Regulation respecting mineral substances other than petroleum, natural gas, and brine (R.S.R.Q. section M-13.1, r.2). The regulation amendment, which came into force on July 23, 2013, has a direct impact on the calculations for the financial guarantee and payment of the contribution to this guarantee for site restoration once the mining activities have ceased.

The mining company must foresee the costs of restoring the entire site, as well as the costs associated with the closing and rehabilitation of the mining site, necessary for securing the area and returning it to a condition that is deemed compatible with its environment and that satisfies the expectations of the community and the government departments involved. The main measures for restoring the mining site will include:

- Stabilizing the natural water level, following the end of the pumping activities in the pit, at an elevation of around 410 m, which will transform the pit into a body of water.
- Seeding the slope of the overburden over the entire perimeter of the pit.
- Building a raised trench to prevent access to the pit.
- Dismantling the infrastructure of the tailings site, e.g., power line, barge, conduits.
- Reconfiguring the tailings site spillway so as to accommodate a freshet of 1:1,000 as well as the progressive flow of the runoff, based on the capacity, for receiving this flow, of the watercourses.
- Comprehensive revegetation of the accumulation sites, i.e., tailings and waste rock, by spreading a layer of overburden and then covering it with topsoil before seeding.
- Revegetation of the overburden dumps by covering them with topsoil before seeding.
- For all ponds, breaching the dam and then filling with topsoil before seeding.
- Demolition and removal of all buildings and other surface infrastructure, including power lines, pipelines, etc.
- Levelling of the process plant area and landscaping to restore the natural drainage system.
- Revegetation of the process plant area by scarification, then covering it with topsoil before seeding.

For personal use only

- Management of the matter generated during the dismantling of the facilities, by applying the principles of reduction, reuse, recycling, and reclamation and, if necessary, elimination of matter at authorized sites, according to the degree of contamination.
- Execution of a land characterization study to identify the presence of contaminants with concentrations in excess of regulatory values and taking the necessary measures, in compliance with the provisions of the Environment Quality Act and the Land Protection and Rehabilitation Regulation.
- Scarification of the roads built by NAL as part of the mining activities, restoring of the natural drainage and seeding.

Some of the restoration works will be carried out during the mining operations, with the balance done at the end of the mine life. The implementation of the proposed environmental monitoring program will allow for demonstrating that the restoration works have achieved their goals.

A former tailings facility, under the responsibility of the Province of Quebec since 2010, is located within the mineral resource footprint. The management of tailings from previous mining operations are subject to specific conditions, depending on their geochemical characteristics. The MRNF has stated in 2010 that these tailings do not show acid rock drainage potential. However, the MELCCFP requirements for geochemical characterisation have increased since 2020 and a more comprehensive characterisation is currently underway.

Finally, the responsibility for historical infrastructure will be assessed and discussed with the MRNF as additional resources beyond current permits are accessed.

20.7.1 Financial Commitment for Mine Closure

As part of approvals for the site restoration plan, the MRNF issued to the previous owners of the Project a schedule for providing the financial guarantees (i.e. closure bond, needed to cover the cost of closure). The closure cost estimate was updated from the 2024 closure cost which was acceptable by the Ministry. The same cost per unit was utilized in this update. The concept of closure remains unchanged from the previous closure plan. Additional areas were considered for the reclamation of TSF-3, HS-4. The expansion closure cost also includes additional amount for demolition and restoration of crushing and mill expansion. Table 20-3 summarizes cost closure for each scenario:

Table 20-3: Total Cost of Closure Plan

Version of Closure Plan	Closure Cost (C$)	Total Cost (C$)
MRNF Approved plan (2024) Base Case (No Expansion)	-	36 486 691 $
NAL Extension Stage 1 & Stage 2 (6500 tpd)	1,988,189 $	38,474,880 $
NAL Expansion 2026 (Stage 3) Pit Extension (6500 tpd)	23,948,953 $	62 423 833 $

20.8 Recommendations

The following recommendations for future stages of the expansion:

- Finalize waste rock and tailings characterisation testwork on resource expansion.
- Continue hydrogeological investigations to refine the hydrogeological model,
- Engagement and submission of initial permits for expansion related infrastructure and construction.
- Continue engagement to communicate with and consult stakeholders to highlight the project's positive impacts and mitigation measures.
- Continue to measure the presence of beryllium, arsenic, lead, and crystalline silica and provide a comprehensive air emissions model for the expansion project.

For personal use only

21 Capital and Operating Costs

This chapter summarizes the Capital Expenditures (CAPEX) and Operating Expenses (OPEX) estimates related to the Project installations. The Project capital and operating costs in this study centre around the addition of new equipment and infrastructure required for the expansion of NAL facilities. These additions are required to achieve the intended design throughput rate of 4,500 tpd in Stage 1 and 6,500 tpd in Stage 2 and Stage 3.

21.1 Capital Cost Estimate

The total estimated initial capital cost for Association for the Advancement of Cost Engineering (AACE) Class IV of the NAL Expansion Project is estimated at C$ 366,053,000. These costs are stated in constant dollars as of first quarter of 2026. This section describes the methodologies and basis for the preparation of the CAPEX. A breakdown of the CAPEX is shown in Table 21-1. All costs in Canadian dollar (CAD or $).

Table 21-1: Capital Costs Summary by Major Area ($M CAD)

Area	Stage 1 ($M CAD)	Stage 2 ($M CAD)	Stage 3 ($M CAD)	Total ($M CAD)
Mechanical Direct	**$14.3**	**$19.8**	**$22.9**	**$56.9**
Mechanical	$14.3	$19.8	$22.9	$56.9
Other Disciplines Direct	**$41.9**	**$38.9**	**$80.9**	**$161.8**
HVAC	$0.9	$1.2	$2.5	$4.6
Platework	$0.9	$1.7	$9.8	$12.4
Civil	$1.7	$1.2	$3.7	$6.6
Piping	$3.9	$5.3	$1.4	$10.6
Concrete	$6.9	$8.3	$22.7	$37.8
Structural	$6.9	$8.3	$21.9	$37.0
Building	$2.6	$0.8	$4.7	$8.1
Electrical	$9.2	$8.9	$10.3	$28.4
Instrumentation & Controls	$1.7	$2.4	$2.7	$6.8
Demolitions	$7.3	$0.9	$0.3	$8.5
Mobile Equipment	$0.0	$0.0	$1.0	$1.0
Indirect Costs	**$17.0**	**$22.2**	**$35.0**	**$74.1**
PCM Services	$4.0	$3.4	$11.6	$19.0
Detail Engineering	$5.0	$6.0	$5.0	$16.0
Construction indirects	$3.4	$4.3	$6.5	$14.1
Owner's costs	$1.7	$1.8	$3.1	$6.6
Operational Readiness & Pre-Production Labour	$0.3	$3.0	$1.2	$4.6
Insurances	$1.1	$1.1	$1.1	$3.3
Spares Strategic	$0.0	$0.6	$0.5	$1.1
Spares Commissioning	$0.2	$0.2	$0.4	$0.9
Transport / Delivery to Site	$1.1	$1.7	$5.2	$8.0
First Fill	$0.2	$0.2	$0.3	$0.7
Total Before Contingency	**$73.2**	**$80.9**	**$138.7**	**$292.8**
Contingency P50 (30%)	**$18.3**	**$20.2**	**$34.7**	**$73.2**
Total CAPEX	**$91.5**	**$101.1**	**$173.4**	**$366.1**

For personal use only

21.1.1 Basis of Estimate

The estimate prepared is Class 4 Capital Cost Estimate (CCE) in line with AACE with a nominal target accuracy range of ±40%. The level of estimation is supported by vendor quotation for major equipment and previous installation cost data at NAL for some items.

The estimate was developed from a combination of factoring from similar projects and more detailed estimating calculation in some areas. Equipment and material cost factors have been sourced from projects of similar scope and design with costs escalated where necessary.

The estimate was based on the following general approach:

- Major mechanical equipment costs for the expansion were obtained from vendor budget quotation.
- Secondary and minor equipment was sourced from an in-house database for similar projects.
- An estimate base date of February 2026.
- An Estimate Base Currency of Canadian Dollars (CAD).
- Project executed through a self-perform delivery model with engineering services contracted out and Elevra performing the general contractor (GC) role.
- All costs exclusive of escalation beyond the base date.
- Exclusive of taxes.

Table 21-2 summarises the Basis of Estimate.

Table 21-2: Summarised Basis of Estimate

Description	Basis of Estimate
Mechanical Equipment	The equipment supply pricing for most of the major equipment is based on recent quotes. For smaller equipment, Sedgman used inhouse data or quotes from similar projects. In addition to this equipment, costs coming from other sources are the following: • Carbonates Plant Demolition: From previous quote provided by client, however Sedgman did an independent estimate and evaluated a higher value. • Operational readiness: Cost estimated by client • The Sedgman's inhouse library of installation/modification/demolition hours for each equipment type and size, and the latest all-in labour rate was applied to these hours to calculate the installation cost for each equipment. • The mechanical platework was estimated using quantities for each equipment and the most recent rates were applied to them to estimate the cost
Civil	The cost was estimated as a percentage of mechanical. The quantities were not developed by engineering at this stage; however, the overall footprint and topography was taken into account to confirm the estimated budget for crushing plant area of Stage 3.
Structural Steel	For Stage 1 and Stage 2, the cost was estimated as a percentage of mechanical. For Stage 3, the quantities were copied from a similar design performed by Sedgman, and the local rates were applied to calculate the cost.
Concrete	For Stage 1 and Stage 2, the cost was estimated as a percentage of mechanical. For Stage 3, the quantities were copied from a similar design performed by Sedgman, and the local rates were applied to calculate the cost.
Piping and Valves	The cost was estimated as a percentage of mechanical. The quantities were not developed by engineering, however the overall dimensions of the plant, expected lengths of pipe and choice of material was considered to assess the calculated budget for each phase.
Electrical and instrumentation	The cost was estimated as a percentage of mechanical. The quantities were not developed by engineering, however the overall dimensions of the plant, expected loads of equipment, expected control requirements, and availability of existing infrastructure was considered to assess the calculated budget for each phase.
Buildings	A building list was developed, and the dimensions were measured to calculate the footprint and volume of each building. The general characteristics of each building was considered to apply the appropriate rate to calculate the overall cost.

Description	Basis of Estimate
	Building modifications to comply to the latest codes: cost estimate by the Architect.
PCM Services	The cost for PCM services includes all efforts required after full sanctioning of the Project, and which are required to bring the Project to a state of Construction and Mechanical completion. PCM services budget for the project was estimated as a percentage of direct costs.
Detail Engineering	Detail engineering costs were calculated by Sedgman as a bottom-up estimate.
Construction Indirects	Construction indirects include site vehicles, including site utilities, facilities including trailers, ablution blocks, furniture and storage containers, site running costs including stationary, cleaning, garbage and sewage disposal, temporary power, potable water, security, IT set-up and communications. This budget is to support the entire PCM and Owner's team. The subcontractor's construction indirect includes all the above-mentioned items as well as the construction equipment, tools, and consumables. This cost was calculated using a percentage of direct costs. The total was evaluated by comparing against similar projects to ensure the accuracy.
Vendor Representatives	The cost of vendors' representatives included in the CAPEX will be sufficient to bring the Project to mechanical completion. is provided by vendors or calculated based on the historical data.
Taxes and Duties	All tax and duties are excluded.
Operational Readiness and Pre-Production Labour	Operational Readiness and Pre-Production Labour were included as a bottom-up estimate provided by Elevra based on current and forecast requirements.
External Consultants and Vendor Support	Included in Owner's costs
Owners Costs	Owner's cost was calculated using a percentage of direct costs. The total was evaluated by comparing against similar projects to ensure the accuracy.
Project Insurance	A quote from a reputable insurance provider was received and used in the CAPEX cost estimate.
Spares Strategic	An allowance of (0%,1%, and 0.5% for Stage 1, 2, and 3 respectively) of direct costs were made to calculate this cost.
Spares Commissioning	An allowance of 0.4% of direct costs were made to calculate this cost.
Transport / Delivery to Site	Mostly estimated per cost item depending on the size and weight and distance. An allowance was added to compensate for any missing delivery costs.
First Fill	An allowance of 0.3% of direct costs were made to calculate this cost.
Escalation	No provision has been made for any escalation in the capital cost estimate.
Contingency (P_{50})	Factored at 25% of total project cost

21.1.2 Exclusions

The following items are considered excluded from the capital cost estimate:

- Cost changes due to currency fluctuation.
- Force Majeure issues.
- Scope changes.
- Changes due to government legislation.
- Project delays because of abnormal climatic conditions.
- Lost time due to industrial disputes, strikes, or civil unrest.
- Environmental, ecological, or cultural considerations other than those addressed in the design.
- The cost of producing any environmental related documents and studies related to obtaining permits, approvals, or variance agreements from governing authorities.
- Contract incentives to engineering contractor and other contractors, i.e., early completion bonuses.
- Closure costs (closure costs for mine closure have been estimated separately in Section 20.7 – Mine Closure and Reclamation Plan).

For personal use only

For personal use only

21.1.3 Sustaining Capital

Sustaining expenditures (SUSEX) for the base case and expansion project were estimated using current operational budgets and factors of direct plant cost. Tailings SUSEX costs were derived using updated unit rate estimates and quantities derived from current facility designs. The Expansion case includes additional sustaining costs for additional equipment which are offset by the shorter mine life of this scenario.

The existing crushing circuit will be repurposed into an ore sorting facility following the Stage 2 expansion. This change increases sustaining capital compared to the previous scoping study.

Table 21-3: Sustaining Capital Summary

Area	Base ($M CAD)	Expansion ($M CAD)
Tailings	$357.7	$357.7
TSF1	$22.0	$22.0
TSF 2	$243.1	$243.1
TSF 3	$79.9	$79.9
HS4	$9.1	$9.1
Pit Pond	$3.7	$3.7
Stay in Business Capital (SIBC)	$105.4	$120.9
SIBC – Base	$105.4	$61.2
SIBC - Stage 1	$-	$14.7
SIBC - Stage 2	$-	$16.8
SIBC - Stage 3	$-	$28.2
Mining	$22.9	$22.9
Phase 5 Site Preparation (does not include any mining activity)	$1.0	$1.0
Phase 6 Site Preparation (does not include any mining activity)	$1.5	$1.5
Phase 7 Site Preparation (does not include any mining activity)	$3.0	$3.0
Phase 8 Site Preparation (does not include any mining activity)	$1.5	$1.5
Fuel Bay	$0.8	$0.8
HS4 Dump	$5.5	$5.5
Lortie Lake	$8.7	$8.7
Ancien PAR	$0.4	$0.4
Fish Removal Cost	$0.4	$0.4
Compensation	$25.6	$25.6
Compensation - Open Pit	$20.9	$20.9
Compensation - HS4	$4.0	$4.0
Compensation - TSF2	$0.8	$0.8
Total	$511.7	$527.1

21.2 Operating Cost Estimate

Operating expenses (OPEX) are based on the LOM plan. The OPEX for the base and the three expansion stages are calculated from the NAL operating budgets. The base case is developed from an annual average feed rate of 3,780 tpd while the expansion stages are based on an average annual processing rate of 4,500 tpd for Stage 1, and an average annual processing rate of 6,500 tpd for Stage 2 and Stage 3.

The OPEX was developed in accordance with the requirement of a pre-feasibility study level with a nominal accuracy range of ± 20%. The level of estimation is supported by actual operational information including salaries, consumables, maintenance costs and established contracts and therefore are more precise given this is a brownfield project.

For personal use only

Some updated operations costs have occurred since the last publication which include more precise values on general and administrative costs and improvements in logistics concentrate transport costs that are being implemented in June 2026 and crusher consumables and temporary crushing facilities. These will be discussed below.

The OPEX results represent annual steady state operations therefore no escalation or inflation is included within the estimate. A summary of the average LOM OPEX costs (all values in CAD$) and comparison between scenarios can be found in Table 21-4. OPEX costs are evaluated commencing as of Fiscal Year 2027.

Table 21-4: Total OPEX Summary

Item	Units	Base	Stage 1	Stage 2	Stage 3
LOM	Yrs	35	20	20	20
Milling rate	Mt/yr	1.4	1.6	2.4	2.4
Mining Cost (ore and waste)	CAD$/t mined	8.6	7.9		
Processing cost	CAD$/t milled	42.6	38.7	37.5	34.2
G&A	CAD$/yr	23.6	24.6	28.3	29.9
Transport cost	CAD$/t dry conc.	142.4	133.8	118.6	118.6
Total OPEX	CAD$M	7,086	**5,949**		
C1 Cost Concentrate	CAD$/t dry conc.	1,048	**876**		

Principal drivers influencing unit cost C1 Cost reduction are driven by the impact of increased tonnage of concentrate, processed and mined. The following are additional details to help understand the changes. It is important to note that base cost is based on actual operating costs or that will be in place in 2026.

Stage 1 – Increase of 19% in throughput versus Base:

1. 13% reduction in G&A per tonne processed resultant from relatively fixed costs between scenarios with minor adjustments required for additional head count, insurance and employee benefits.
2. 6% reduction in transport costs per tonne dry concentrate directly related to increased movement of material versus elements that are fixed costs. Improvements in material handling on site with new concentrate loading facility reducing on site tramming of material and material loadout.
3. 9% reduction in Processing cost driven mostly by relative low increase in head count required, addition of line power reticulation replacing diesel generators on site for pumping. Power costs and reagents have no impact between the stages as same unit rates are used. Fixed costs from the base case not impacted by the stages provide the remainder of improvements.

Stage 2 – Increase of 72% in throughput versus Base:

1. 30% reduction in G&A per tonne processed resultant from relatively fixed costs between scenarios with adjustments required for additional head count, insurance and employee benefits. As the new crushing circuit is only available in Stage 3, all management and cost elements for the contractor are treated in the processing cost. Once Stage 3 is implemented on contractor terminated some G&A costs will increase. This is covered below.
2. 17% reduction in transport costs per tonne dry concentrate directly related to increased movement of material versus elements that are fixed costs and an estimated improvement in contract rates for variables costs considering the approximate 72% increase in volume.
3. 12% reduction in Processing cost similar to Stage 1. Despite the increased volume the fact that contractor crushing is used is the large driver that prohibits any additional savings. The additional savings will be garnered in Stage 3. Other drivers are relative low increase in head count required.

For personal use only

Stage 3 – Increase of 72% in throughput versus Base:

1. 26% reduction in G&A per tonne processed very similar to Stage 2, but as mentioned additional admin resources are counted for as the new crushing circuit is operated by owner. Health and Safety, Human Resources and Environmental costs are added to the G&A.
2. 17% reduction in transport costs the same as Stage 2.
3. 20% reduction in Processing principally impacted by the improvement from operating the new crushing circuit. Other drivers are increase in head count to operate and maintain the new crushing circuit required. The existing crushing circuit is converted to a pure marginal ore sorting circuit to upgrade low grade lithium with potential high iron content to increased lithium grade with reduced iron. The adapted circuit is considered in the operating cost.

In previous scoping study mining costs were estimated based on increased volume, use of larger shovels in waste and benefits from fixed management and administration costs relative to increased tonnage for both contractor and owner costs. Unit rates were based on current operating costs and incorporated an increase in unit rate as mining goes deeper in a similar manner as used for the establishment of the reserves.

In this updated prefeasibility study, a detailed mining cost estimate was performed using SPRY simulation software which incorporates detailed distance, elevation and equipment parameters to account for fuel consumption accurately. Rates for equipment were based on existing contract condition on site and does not account for improved rates that may come from increased fleet size which could be expected. LOM fuel cost of $1.35 /l based on historical pricing and future Brent/WTI trends published by Goldman Sachs. Costing incorporates elements of current contractor and updated quote from an equipment supplier for fleet rental required for the base case and expansion cases. All contractor mining indirect costs as well as costs from Elevra's mining technical services and operating personnel are included in costing. The expansion scenario of the LOM cost decreases from base case of $8.60/t to LOM $7.91/t. In the first 10 years of the expansion case the LOM the mining cost is an average of $7.39 /t lower than full LOM as in the latter part deepening of the pit increases the mining cost.

21.2.1 Labour

All mine, processing plant and administration site staff personnel work 10-hour shifts on a 4 on / 3 off basis. Contracted mine operations will work 12-hour shifts. For the processing plant, operations and maintenance crews will work two 12-hour shifts. There will be four shift crews rotating on a 7 on / 7 off schedule.

Staffing requirements are built as bottom-up and based off existing operations. The main increases in labour between the base and expansion case are summarised from operational site roles. The plant increase covers the most significant increase which is attributable to additional operators for grinding and floatation extensions as well as increased maintenance (mechanical / piping / electrical / instrumentation). Mine technical services are augmented to cover increased throughput, assay treatment and geology support. G&A costs are impacted by an increase in site support for Health and Safety, Environment and Increased Surface and Warehousing support.

Table 21-5: Staff and Hourly Count (Sayona Employees)

Area	Base	Stage 1	Stage 2	Stage 3
G&A	59	60	65	70
Plant	126	132	150	172
Mine	40	40	51	51
TOTAL	**225**	**232**	**266**	**293**

21.2.2 Power

Power is estimated from current power consumption with rates as per contracted supply with Hydro Quebec scaled for the additional throughput. Power is calculated to account for $2.0 / t processed for base and stages. In further studies, the benefits of a complete load study will allow for closer estimate of power savings given the expansion.

21.2.3 Reagents

Reagent costs are calculated from NAL's current operating contracts with consumptions escalated for the additional throughput.

21.3 Author's Opinion

The Author is of the opinion that the capital and operating estimating performed, and methodologies applied are relevant and of adequate nature for the expansion study economics assessment at a scoping study level.

Operating cost estimates were compiled by the Elevra team from operating data and contracts. While the Author did not directly undertake the operating estimate, the Author has reviewed and is satisfied with the basis and assumptions used in the operating cost estimates.

For personal use only

For personal use only

22 Economic Analysis

The main highlights of the Project's financial analysis are presented in Table 22-1 and Table 22-2. Financial Analysis was performed commencing as of Fiscal Year 2027.

Table 22-1: Main Financial Assumptions and Results Summary for the NAL Expansion Project

Parameters	Unit	Base	Expansion
Average Price 6% Li_2O	USD$/t	$2,260	$2,137
Life of mine (from FY2027)	yrs	35	20
Total Waste	Mt	336	336
Total Ore	Mt	47	44
Strip Ratio	-	7.14	7.14
Average Annual ROM	Mt/y	1.36	2.41
Average Feed Grade	% Li2O	1.12%	1.17%
LOM 5.4% Li_2O Produced	Mt	6.77	6.79
LOM Average Annual 5.4% Li_2O	kt/y	196	348
Average Annual 5.4% Li_2O production (post expansion)	kt/y	199	373

Notes:

- Total ore value for the expansion case is lower than the base case due to ore sorting.

Table 22-2: Project Economics

Parameters	Unit	Base	Expansion
Exchange Rate	CAD/USD	1.35	1.35
Mining Cost (ore and waste)	C$/t mined	8.60	7.91
Process cost	C$/t milled	42.57	34.81
G&A	C$/t milled	17.31	13.05
Transport Cost	C$/t conc	142.37	119.81
Total OPEX	C$M	7,086	5,949
LOM C1 Cost Concentrate	C$/t conc	1,048	876
LOM AISC	C$/t conc	1,126	954
LOM C1 Cost of Concentrate (post expansion)	C$/t conc	1,045	851
LOM AISC (post expansion)	C$/t conc	1,112	918
Total SUSEX	C$M	512	527
Total initial CAPEX	C$M	-	366
Net Cash Flow (pre-tax)	C$M	10,927	10,822
$NPV_{8\%}$ (pre-tax)	C$M	3,193	4,655
$NPV_{8\%}$ Expansion Only (pre-tax)	C$M	-	1,462
IRR Expansion (pre-tax)	%	-	58.3%
Payback (pre-tax)	Months	-	29
Net Cash Flow (post-tax)	C$M	7,471	7,307
$NPV_{8\%}$ (post-tax)	C$M	2,274	3,218
$NPV_{8\%}$ Expansion Only (post-tax)	C$M	-	943
IRR Expansion (post-tax)	%	-	49.9%
Payback (post-tax)	Month	-	34

Notes:

- All costs and sales are presented in constant 2026 CAD, with no inflation or escalation factors considered.
- $M = millions of dollars.
- The financial analysis was performed on existing Mineral Reserves as outlined in this report.
- The valuation calculations are unlevered.
- The average metallurgical recovery over the LOM is 71.2% for the expansion and 69.2% for the base case due to improvement in the mill flowsheet specifically attributable to WHIMS improvements.
- Plant availability is calculated at 90%.
- Tonnes of concentrate are presented as dry metric tonnes.
- An exchange rate of 1.35 CAD/USD was fixed over the LOM for the Project.

For personal use only

- The average 6% Li_2O concentrate (SC6) price is based on a market analysis from Benchmark Mineral Intelligence for Q1 2026 as described in the market section and varies over the LOM from US$1,260/t to US$2,430/t.
- Average LOM SC6 pricing may vary between the cases due to longer mine life at the long term US$2,430 price for the base case (2036 and beyond).
- A discount rate of 8% was used for the base case and expansion scenarios.
- Net Cash Flow and valuation calculations include investment tax credit on CAPEX.
- The numbers have been rounded. Any discrepancy in the totals is due to rounding effects.
- The expansion case ore processed is less than base case as ore-sorting is used to reject high Fe low Li_2O material which in turn increases the ore processed grade relative to the base case.

22.1 Reconciliation with Previous Scoping Study

The motivation of the revisions in this prefeasibility study from the previously published scoping study, is to reduce risk in the project execution by staging integration of new infrastructure, bring forward production increase and adjust the throughput. Indirectly the price of Spodumene is updated to ensure the pertinence of the study in the reality of the commodity price, the table below compares the previous scoping study expansion scenario to the current prefeasibility study (PFS) .

Table 22-3: Expansion Scenarios - Previous Scoping Study and Present PFS

Parameters	Unit	Previous Scoping	Present PFS	Variance
Exchange Rate	CAD/USD	1.35	1.35	-
LOM	Years	24	20	-16.7%
Average Price 6% Li_2O	USD$/t	1,392	2,137	53.5%
Mining Cost (ore and waste)	C$/t mined	7.60	7.91	4.1%
Process Cost	C$/t milled	35.4	34.8	-1.7%
G&A	C$/t milled	13.4	13.1	-2.2%
Transport Cost	C$/t conc	123.8	119.6	-3.4%
Total OPEX	C$M	6,062	5,949	-1.9%
LOM C1 Cost Concentrate	C$/t conc	877	876	-0.1%
LOM AISC	C$/t conc	952	954	0.2%
LOM C1 Cost of Concentrate (post expansion)	C$/t conc	851	851	0.0%
LOM AISC (post expansion)	C$/t conc	922	918	-0.4%
Total SUSEX	C$M	517	527	1.9%
Total Initial CAPEX	C$M	366	366	-
Net Cash Flow (pre-tax)	C$M	4,626	10,822	133.9%
NPV (8%) (pre-tax)	C$M	1,798	4,655	158.9%
NPV Expansion Only (8%) (pre-tax)	C$M	628	1,462	132.8%
IRR Expansion (pre-tax)	%	26.4%	58.3%	120.8%
Payback (pre-tax)	Months	36	29	-19.4%
Net Cash Flow (post-tax)	C$M	3,249	7,307	124.9%
NPV (8%) (post-tax)	C$M	1,284	3,218	150.6%
NPV Expansion Only (8%) (post-tax)	C$M	479	943	96.9%
IRR Expansion (post-tax)	%	26.4%	49.9%	89.0%
Payback (post-tax)	Month	46	34	-26.1%

To better understand the impact of staging improvements, the staging, operating cost and throughput increase is separated from the changes in price. The following Table 22-4 shows the contribution of each to the increase in $NPV_{8\%}$ the expansion scenario.

Table 22-4: Expansion $NPV_{8\%}$ contribution - Staging/Throughput and Price Li_2O.

Parameters	Unit	Staging / Throughput*	Price Li_2O	Total NPV increase
$NPV_{8\%}$Expansion Only (pre-tax)	C$M	409	425	834
$NPV_{8\%}$Expansion Only (post-tax)	C$M	227	237	464

*Predominantly staging/throughput in addition to other assumption changes

From the table, 51% of the impact in $NPV_{8\%}$post tax increase is predominantly a contribution of the staging and throughput increase while 49% is attributable to the increase in Li_2O price from the previous study.

22.2 Sensitivity Analysis

A sensitivity analysis was conducted on the factors presented below:

- Spodumene Price
- Exchange Rate
- Blended Li_2O Grade
- OPEX
- Project CAPEX
- Sustaining CAPEX
- Mill Recovery

Post-Tax $NPV_{8\%}$ sensitivities range from -30% to +30% for all factors. The impact of the $NPV_{8\%}$ (in CAD $M) outputs was tested at discount rate of 8%. Figure 22-1 demonstrates the $NPV_{8\%}$ value of the asset with new expansion capacity whereas Figure 22-2 demonstrates the improvement in $NPV_{8\%}$ the Expansion provides relative to remaining with the Base Case.

For personal use only




Figure 22-1: Sensitivity Analysis on $NPV_{8\%}$

For personal use only




Figure 22-2: Sensitivity Analysis on $NPV_{8\%}$ Expansion Only (difference of Expansion and Base Cases)

For personal use only

23 Adjacent Properties

The area around the Property contains several active exploration projects. No data from these projects has been used in the preparation of the MRE for the Project.

For personal use only

24 Other Relevant Data and Information

24.1 Project Execution Plan

The project execution strategy will be based on the project development sequence identified by Elevra and published in the previous ASX press release “Accelerated NAL Expansion” published on January 12th, 2026. The following dates were identified for the delivery of the three Stages:

- Stage 1: An initial 15-20% increase in annual spodumene concentrate production above current production levels commencing in mid-CY27 with an incremental reduction in unit operating costs. This increase is within the current limits of the milling permit, which is set at 4,500 tpd;
- Stage 2: A subsequent expansion of downstream milling, flotation and filtration capacity to 6,500 tpd with an anticipated corresponding concentrate production rate of 348,000 tonnes per year. The incremental feed material will be processed using a temporary mobile crushing circuit operating in conjunction with the existing crushing circuit. The further expanded production is expected to commence early CY28, with an additional incremental reduction in unit operating costs; and
- Stage 3: The replacement of the temporary mobile crushing circuit and the existing crushing circuit with a new crushing circuit capable of meeting feed requirements for a LOM average production of 315ktpa. This final step is expected to be completed in mid-CY29 and is expected to deliver crushing cost efficiencies required to meet the anticipated LOM cost reduction.

Engineering development will continue following the Mineral Reserves PFS. A feasibility study is planned to increase the accuracy of the cost estimate and further derisk the Project.

As outlined in the January 2026 ASX press release, Elevra plans to move directly to detailed engineering following the Mineral Reserves PFS to advance Stage 1 and Stage 2 to a level required for construction. Procurement of long lead items for Stage 1 and Stage 2, and early works and site preparation will be initiated shortly after the start of detailed engineering.

A preliminary project execution strategy for the remaining activity, construction of the expansion project was developed and is shown in Figure 24-1. Further development and detailed execution planning will be undertaken in the next project phase.




Figure 24-1: Indicative timeline for the NAL Expansion Project

For personal use only

For personal use only

24.2 Project Risks and Opportunities

A risk review session was held during the PFS with the participation of discipline leads from Elevra, Sedgman Novopro and Optimal Mining. This session served to provide an update on the risks and opportunities identified during the initial kick-off risk review workshop held on February 2nd, 2026 for the Updated Scoping Study phase of the Project. This initial risk workshop reviewed risks and opportunities from previous project phases and identified new risks based on past experience in other spodumene projects. These efforts lead to the development of Project's preliminary risk register documenting a total of 78 risks and 6 opportunities.

Each risk and opportunity was evaluated based on probability and consequence criteria, and were assessed across health and safety, financial, environmental, community relations, project development, regulatory compliance, systems/data, management, and operations areas. Mitigation measures were proposed for all risks, and residual ratings were reassessed following mitigation.

24.2.1 Risks

The mitigation measures for the highest rated process risks were implemented during the PFS. As these are now part of the base case, the associated risk has been removed. A subset of risks remains with high residual ratings due to their influence on the overall project. This high rating could be from insufficient mitigation measures or the high baseline of the risk itself despite the proposed mitigations. These residual risks and proposed mitigation measures are listed in Table 24-1.

Table 24-1: Project Risks

Risk Description	Mitigation Measure(s)
Increased dust production and emissions due to Stage 2 temporary contract crusher	• Mitigation measures to be determined. Contact crusher supplier to determine possible mitigation measures.
Significant increase in ROM pad traffic due to higher throughput requirements with consequence of vehicles and/or personnel impact by mine vehicle whilst accessing equipment in the vicinity of the ROM bin (on ROM pad).	• Mining team to develop ROM plan showing space and volumes. • Crusher design will be such that personnel segregation from ROM Pad will be possible with access via positive communications including radio and lights system. – Secluded area for the access to the equipment – Windrow protection – No direct access from process plant to ROM pad
Damage to existing and new equipment during construction	• Insurance during construction (bid pending at time of this report)
Increased chance of fire during construction due to hot work	• Firewatch to be implemented during construction work
Safety and health concern from release of residue accumulated on equipment from operations during demolition	• Wash area for demolished equipment
Schedule risk due to difficulties sourcing equipment (same model as in-place, shipping location)	• Possibility to source used equipment • Favor simple equipment that can be fabricated locally
Delay to start of detail engineering	• Ramp up of detailed engineering to be started as soon as possible • Sedgman and Elevra to ensure robust communications to ensure project timeline is understood at all times. • Following establishment of project strategy, engineering and implementation kick-off will need to be immediate to prevent schedule slip.
Environmental impact of temporary crushing circuit due to excessive dust and noise emissions	• Temporary crusher design to fit into current environmental limits. • Additional dust control & sound control measures to be implemented if necessary
New permitting required for Increased dump/tailings capacity needed for the expansion	• Review of dump height • Ensure social acceptance, particularly with First Nations
Difficulties obtaining permit/approval to drain nearby lake (Lortie Lake)	• PFS-level cost prepared for close-out of the lake.

	• Studies on-going to present findings on conservation of the lake and show that there is no alternative to draining.
Difficulties obtaining social license in the Project footprint due to previous noise complaints from nearby Lac Legendre community (More than 100 noise complaints per year.)	• Noise studies completed • Noise monitoring system near the lake • Procedure for noise complaints
Financing gap is longer than expected.	• Improve overall project definition by advancing engineering.
Capital escalation of equipment	• Multiple cost estimates developed to ensure rigorous cost tracking • Simplification of the plant expansion strategy • Monte Carlo analysis to reduce risk

24.2.2 Opportunities

Key process optimizations have been incorporated in the PFS expansion design; still, opportunities remain to improve the Project. The major opportunities that have been identified for the Project are summarized in Table 24-2. These opportunities exclude those typical to all mining projects, such as changes in product prices, exchange rates, etc.

Table 24-2: Project Opportunities

Opportunity Description	Benefit
Opportunity to reuse the existing colour sorters for both applications if washing can be implemented in both summer and winter effectively.	CAPEX savings from not replacing ore sorters. Noted colour performance will typically not be as good as XRT (ability to separate liberation/inclusions, etc,) so for long term this performance difference (and ability to effectively wash in winter) will need to be considered.
Reducing density in rod mill to reduce slimes generation	Reduction in slimes generation leading to increased rod mill performance.
Use of superstacks instead of stacksizers for classification. Reports by Derrick indicate that superstacks are a viable alternative to stacksizers.	Reduction in CAPEX. Derrick report indicates that superstacks is a viable alternative to stacksizer.
Further plant capacity expansion in the future due to larger ball mill included in base case. Potential for increased capacity to 8400 tpd	Potential for increased capacity to 8400 tpd. Further debottlenecking will be required to ensure downstream processes can meet the increased capacity offered by the larger ball mill
Opportunity to reuse the existing primary cyclones in Stage 2 instead of a new larger cyclone.	Reduction in CAPEX. Will add flexibility to the operation when running on one train only (improved maintainability, rod charging stability, ability to reduce power draw as required).
Opportunity to convert dilution tank to additional conditioning stage for short term improvement.	Reduction in CAPEX. Insufficient real estate to easily install new conditioning tanks in Stage 1. Additional conditioning tank is mostly relevant for Stage 1, new rougher in Stage 2 will lessen the value of additional conditioning in Stage 1
Modularization of equipment packages to reduce costs and reduce reliance on local contractors.	Reduction in CAPEX. Use a laydown and staging area in the nearby town of Barraute
Use of prefabricated concrete as an opportunity for cost and schedule benefit.	Reduction in CAPEX. Target of 50% of volume as prefabricated concrete
Federal and Provincial government incentives	Direct support or tax incentives

For personal use only

For personal use only

25 Interpretation and Conclusion

The Mineral Reserves PFS demonstrates the potential economic viability of an Expansion of the NAL Operation. The conclusions are supported by the following:

25.1 Geology and Resources

25.1.1 Geology

Geology and mineralization on the NAL Property are well understood following decades of exploration, resource evaluation and active mining.

The geological model supporting the Mineral Resource estimate has been substantially updated following the incorporation of new drilling results from the 2023 and 2024 programs. The geological model now contains a total of 117 spodumene-bearing pegmatite dyke wireframes, of which 93 demonstrate RPEEE 'reasonable prospects for eventual economic extraction'.

The NAL Mineral Resource estimate incorporates geological and analytical data for 563 surface-collared drillholes completed between 2009 and the end of 2024.

25.1.2 Mineral Resource Estimates

The NAL Mineral Resource estimate as of June 6th, 2025, is 95 Mt at 1.15% Li_2O, applying a cut-off grade of 0.60% Li_2O for open pit and 0.70% Li_2O for underground resources. The Mineral Resource estimate includes open-cut Indicated resources of 76.2 Mt at 1.17% Li_2O; and open-cut Inferred resources of 8.6 Mt at 1.13% Li_2O, applying a cut-off grade of 0.60% Li_2O. The Mineral Resource estimate also includes underground Inferred resources of 10.3 Mt at 1.01% Li_2O, applying a cut-off grade of 0.70% Li_2O.

25.2 Mining

The North American Lithium Mineral Reserves have been estimated for a total of 47.2Mt of Proven and Probable Mineral Reserves at an average grade of 1.12% Li_2O, which is comprised of 0.2Mt of Proven Mineral Reserves at an average grade of 0.93% Li_2O and 47.0Mt of Probable Mineral Reserves at an average grade of 1.12% Li_2O.

The Mineral Reserve estimate is underpinned by a detailed mine plan which includes pit phasing, a dilution model which ensures that potential ROM ore feed respects final product specifications, a detailed LOM schedule, which includes stockpiling, tailings disposal and haulage modelling, that results in a positive cash flow for the Project.

25.3 Metallurgy and Processing

The NAL expansion project is scheduled to process an annual average rate of 6,500 tpd of blended ore. Based on a plant feed Li_2O grade of 1.01%, the process design estimates a spodumene concentrate average annual 5.4% Li_2O concentrate production rate at 338,000 tpa.

The financial model considers a LOM average annual 5 production rate of 348 ktpa (or 373 ktpa post expansion). These rates are superior to the process design criteria due to the production rate being dependant on the plant feed grade; the financial model considers a 1.17% feed grade. The process design is based on lower grades but supports the rates used in the financial model.

For personal use only

The existing crusher, ore sorting, new crusher and ore storage areas are designed to operate with an availability of 65%. The processing plant, including the milling, classification, desliming, magnetic separation, flotation and dewatering, is designed to operate at 90% availability. The processing plant will operate on a 24-hour per day and 7 days per week basis.

Metallurgical recovery is improved at the onset of the stage implementation and will achieve an estimate of 71.2 % average over the life of mine as disclosed in the previous study. This recovery is well supported by previous testwork as described in Chapter 13 – Mineral Processing and Metallurgical Testing.

The recovery benefits from the existing operation will come from the following flowsheet improvements:

- Improved flotation feed sizing due to increased classification capacity and mill power.
- Improved magnetic separation circuit (LIMS and WHIMS)
- Improved flotation conditioning
- Improved rougher flotation control and flexibility
- Improved cleaner tails handling

These improvements targeting specific areas will lead to recovery gradually increasing through the staged approach with the full benefits achieved by Stage 2 with all optimisations captured.

25.4 Infrastructure and Water Management

The tailings and water management are based on a strategy of placing conventional spodumene tailings in Tailings Storage Facility 1 (TSF-1) until mid-2029.

Additional TSF-2 and TSF-3 are required and have been planned for as part of the Mineral Reserves PFS design. This planning includes site selection, integrated construction with waste rock storage, progressive embankment raises, capital and operating cost estimates.

Construction of a dyke at Lortie Lake would allow the extraction of mineral resources located beneath a portion of the waterbody. The dyke would maintain the water level in the retained section of the lake, notably to limit impacts on fish habitat, while ensuring safe conditions for mining operations.The WMP was updated to manage flows from the expansion scenario. Water management focuses on water diversion, where possible. Water management infrastructure will be phased in as required.

25.5 Market Studies

The feasibility study utilises information from the “Lithium Forecast Report” study prepared by Benchmark Minerals for Sayona dated Q1, 2026 (Benchmark Minerals, 2026).

Global lithium supply is expected to increase materially in 2026, despite the pricing pressure seen through much of 2025. Supply is forecast to rise by around 250 kt LCE year-on-year, or approximately 15%, including recycling. Despite strong supply growth, the market is still expected to remain in deficit in 2026, as robust demand growth – particularly from electric vehicles and energy storage systems – continues to outpace new supply. By 2027, the surplus remains modest at less than 1% of total market size, pointing to a market that is close to balance.

Forecast pricing for SC6 used in the financial evaluation varies between US$1,260/t in 2031 to US$2,430 in 2036.

For personal use only

25.6 Project Costs and Financial Evaluation

25.6.1 Capital Costs

The total estimated initial capital cost for AACE Class 4 of the NAL Expansion Project is estimated at C$ 366,053,000. These costs are stated in constant dollars as of February 2026.

The Capex estimate includes all the direct and indirect project costs, complete with the associated contingency. The estimating methods include quotations from vendors and suppliers specifically sought for this project, factoring and historic projects and allowances based on past projects.

25.6.2 Operating Costs

Operating costs for the project have been calculated at C$1,048 per tonne of concentrate for base case and C$876 per tonne of concentrate for the expansion scenario.

The OPEX for the base and the three expansion stages are calculated from the NAL operating budgets. The base case is developed from an annual average feed rate of 3,780 tpd while the expansion stages are based on an average annual processing rate of 4,500 tpd for Stage 1, and an average annual processing rate of 6,500 tpd for Stage 2 and Stage 3.

The OPEX was developed in accordance with the requirement of a Scoping Study level study with a nominal accuracy range of ± 20%. The level of estimation is supported by actual operational information including salaries, consumables, maintenance costs and established contracts and therefore are more precise given this is a brownfield project.

25.6.3 Project Economics

Analysis of the financial model on the key economic assumptions indicates that the Project is robust in terms of operating costs and Capex. The Project is most sensitive to changes in commodity prices, exchange rates, and recoveries.

The Project demonstrates robust operational and financial metrics, with the key Project assumptions and outputs shown in the tables below. The main highlights of the Project's financial analysis are presented in Table 25-1 and Table 25-2. Financial Analysis was performed commencing as of Fiscal Year 2027.

Table 25-1: Main financial assumptions and results summary for the NAL Expansion Project

Parameters	Unit	Base	Expansion
Average Price 6% Li_2O	US$/t	$2,260	$2,137
Life of mine (from FY2027)	yrs	35	21
Total Waste	Mt	336	336
Total Ore	Mt	47	44
Strip Ratio	-	7.1	7.1
Average Annual ROM	Mt/y	1.34	2.24
Average Feed Grade	% Li_2O	1.12%	1.17%
LOM 5.4% Li_2O Produced	Mt	6.78	6.80
LOM Average Annual 5.4% Li_2O	kt/y	193	323
Average Annual 5.4% Li_2O production (post expansion)	kt/y	199	373

Notes:

- Total ore value for the expansion case is lower than the base case due to ore sorting.

Table 25-2: Project Economics

Parameters	Unit	Base	Expansion
Exchange Rate	CAD/USD	1.35	1.35
Mining Cost (ore and waste)	C$/t mined	8.60	7.91
Process cost	C$/t milled	42.57	34.81
G&A	C$/t milled	17.31	13.05
Transport Cost	C$/t conc	142.37	119.81
Total OPEX	C$M	7,086	5,949
LOM C1 Cost Concentrate	C$/t conc	1,048	876
LOM AISC	C$/t conc	1,126	918
LOM C1 Cost of Concentrate (post expansion)	C$/t conc	1,045	851
LOM AISC (post expansion)	C$/t conc	1,112	918
Total SUSEX	C$M	512	527
Total initial CAPEX	C$M	-	366
Net Cash Flow (pre-tax)	C$M	10,297	10,822
$NPV_{8\%}$ (pre-tax)	C$M	3,193	4,655
$NPV_{8\%}$Expansion Only (pre-tax)	C$M	-	1,462
IRR Expansion (pre-tax)	%	-	58.3%
Payback (pre-tax)	Months	-	29
Net Cash Flow (post-tax)	C$M	7,471	7,307
$NPV_{8\%}$ (post-tax)	C$M	2,274	3,218
$NPV_{8\%}$Expansion Only (post-tax)	C$M	-	943
IRR Expansion (post-tax)	%	-	49.9%
Payback (post-tax)	Month	-	34

Notes:

- All costs and sales are presented in constant 2026 CAD, with no inflation or escalation factors considered.
- $M = millions of dollars.
- The financial analysis was performed on existing Mineral Reserves as outlined in this report.
- The valuation calculations are unlevered.
- The average metallurgical recovery over the LOM is 71.2% for the expansion and 69.2% for the base case due to improvement in the mill flowsheet specifically attributable to wet high-intensity magnetic separator (WHIMS) improvements.
- Plant availability is calculated at 90%.
- Tonnes of concentrate are presented as dry metric tonnes.
- An exchange rate of 1.35 CAD/USD was fixed over the LOM for the Project.
- The average 6% Li_2O concentrate (SC6) price is based on a market analysis from Benchmark Mineral Intelligence for Q1 2026 as described in the market section and varies over the LOM from US$1,260/t to US$2,430/t.
- Average LOM SC6 pricing may vary between the cases due to longer mine life at the long term US$2,430 price for the base case (2036 and beyond).
- A discount rate of 8% was used for the base case and expansion scenarios.
- Net Cash Flow and valuation calculations include investment tax credit on CAPEX.
- The numbers have been rounded. Any discrepancy in the totals is due to rounding effects.
- The expansion case ore processed is less than base case as ore-sorting is used to reject high Fe low Li_2O material which in turn increases the ore processed grade relative to the base case.

For personal use only

For personal use only

26 Recommendations

This NI 43-101 compliant technical report on North American Lithium's Expansion Project was prepared by experienced and qualified independent consultants using established engineering methodologies and standards. It provides a comprehensive summary of findings across key areas, including exploration, geological modelling, mineral resources, open pit mine design, metallurgy, process design, infrastructure, environmental management, waste and water management, capital and operating costs, and economic analysis. The depth of investigation in each area meets or exceeds the standards typically expected of a scoping study.

The study's results demonstrate that the Project is technically feasible and has the potential to be value accretive under the Mineral Reserves PFS case assumptions. Analysis of the results and findings from each major area investigated in this Mineral Reserves PFS suggests several recommendations for further studies.

26.1 Geology and Resources

The following actions are recommended for the next phase of the Project:

- Continue resource definition drilling within the conceptual resource pit shell to upgrade remaining Inferred resources to Indicated category and improve geological continuity.
- Continue exploration drilling outside of the conceptual resource pit shell to assess the potential for additional Mineral Resources growth.
- Complete additional bulk density measurements across pegmatite and waste rock to support the calculation of a density regression formula. Apply the regression formula to support more accurate Mineral Resource characterization.
- Complete additional iron analyses for pegmatites and waste rock to support more accurate Mineral Resource characterization.
- Continue detailed geological mapping of exposed pegmatite dykes in open cut pit faces and incorporate results in a future update of the geological model.
- Regularly review and update Mineral Resource estimation methodology as new drilling data becomes available. Test sensitivity of estimated ore volumes and grades to different data preparation, domaining and Li_2O grade estimation methods.
- Reconcile modelled pegmatite domain geometries, volumes and Li_2O grades against recent mine production data.

26.2 Mining and Reserves

The following actions are recommended for the next phase of the Project:

- A fleet selection study should be completed with the results of this study used as the basis for the assessment. The fleet selection study must evaluate the potent mining costs savings which can be realised through the use of larger equipment, without negatively impacting loss and dilution of the ore. The results of the fleet selection study should provide guidance on the potential increase in Reserves and life-of-mine physicals.
- Focus on the securing of approvals for all aspects of the life-of-mine plan, in particular the HS-4 waste storage area. Gaining of approvals to store waste in the HS-4 facility will provide operating economic benefits due to the closer proximity of HS-4 to the pit compared to other waste storage areas.

- The benefit that backfilling of mined out voids provides should be thoroughly evaluated. Backfilling of mined out voids will provide lower operating costs, reduce the size of the final pit void and reduce the height or size of the out-of-pit dumps. This will only be an option if the surrounding host rock has been drilled sufficiently to ensure that no potentially recoverable ore is sterilised.

26.3 Metallurgy and Processing

The process design proposed for the Mineral Reserves PFS is based on previous metallurgical studies and experience acquired from work on similar spodumene projects across the world. The work completed should be further advanced during a detailed engineering phase to bring the engineering to a level suitable for construction.

The work described below is underway and will help confirm and support design parameters used in the Mineral Reserves PFS.

- Plant trials on operating the existing WHIMS in parallel. These trials will help validate the increases in recovery assumed in the design.
- Flotation conditioning tests in the processing plant to increase understanding of the potential improvements and impact on downstream flotation.
- Repeat surveys and simulations to assess the new flotation feed PSD and expected slimes generation.

To further de-risk the project, the following test is recommended in addition to the planned testwork described above. This additional testwork program would be completed in the next phase of the project.

- Optimisation testwork on the WHIMS to understand the limitations and set targets for plant operations.

26.4 Waste and Water Management

The waste and management design proposed for the Mineral Reserves PFS is based on previous geotechnical and hydrogeological investigations and experience acquired from similar projects. The work completed should be further advanced during a detailed engineering phase to bring the engineering to a level suitable for construction.

- Advance the detailed geotechnical and hydraulic design of TSF-2 and TSF-3, including centreline embankment configuration, seismic and dam safety criteria, and integration of waste rock into embankment construction, to support the next study phase and permitting. This includes the completion of a site-specific seismic hazard assessment.
- Complete additional geotechnical and hydrogeological investigations, particularly for the TSF-3 footprint and new waste rock storage areas, to reduce key uncertainties and confirm foundation conditions and long-term performance for the expanded mine waste storage system.
- Finalize the design of site water management infrastructure (basins B1–B5, drainage ditches, sedimentation ponds and surge pump basins) and the associated treatment scheme, ensuring adequate capacity under design storm and freshet events and compliance with applicable provincial and federal water quality requirements.
- Refine the closure and monitoring framework for TSF-1, TSF-2, TSF-3 and waste rock storage areas, including beach reclamation, long-term drainage to spillways, and instrumentation and water quality monitoring programs from operations through post-closure, so that commitments are clearly reflected in the updated closure plan and regulatory approvals.

For personal use only

26.5 Project Costs and Financial Evaluation

Several items mentioned in the previous chapters will reduce costs and improve the financial position of the deposit. The Mineral Reserves PFS CAPEX is on the level of an AACE Class 4, and a Definitive Feasibility Study phase is planned to increase the accuracy of the estimate to a Class 3 and further derisk the Project.

Elevra is planning on moving directly to Detailed Engineering for Stages 1 and 2 following the Mineral Reserves PFS to bring the engineering to a level appropriate to meet the construction timelines outlined in this Mineral Reserves PFS. It is recommended to proceed with the DFS and Detailed Engineering as described in the preliminary Project Schedule.

For personal use only

27 References

Agence Canadienne d'Évaluation Environnementale. (2018). *Projet de mine de spodumène North American Lithium.* Rapport d'étude approfondie. 107 p.

Asselin, R. (2016). *Final – Procédures Forages de Surface 2016.* Internal North American Lithium report (in French).

BBA. (2023). *Tailing Storage Facility 2 – Geotechnical Baseline Study – Geotechnical Investigation Report.* Report n° 6015037-023100-41-ERA-0001-R01.

BBA. (2023). *Updated Definitive Feasibility Study Report for the Authier Lithium Project.* Prepared for Sayona Mining Limited, dated April 14, 2023.

Benchmark Minerals. (2022). *Lithium Forecast | Q1 2022.* Benchmark Mineral Intelligence.

Benchmark Minerals. (2026). *Lithium Forecast | Q1 2026.*

Blanchet, D., Hardie, C., Lavery, M., Lemieux, M., Nussipakynova, D., Shannon, J., & Woodhouse, P. (2011). *Feasibility Study Update, NI 43-101 Technical Report, Québec Lithium Project, La Corne Township, Québec.* Prepared for Canada Lithium Corp.

Breaks, F., & Tindle, A. (1997). *Rare-Metal Exploration Potential of the Separation Lake Area: An Emerging Target for Bikita-Type Mineralization in Superior Province, Northwestern Ontario.* Ministry of Energy, Northern Development and Mines Publication OFR5966.

Canada Lithium Corp. (2012). *Feasibility Study Update – NI 43-101 Technical Report, Québec Lithium Project, La Corne Township, Québec, October, 2012.*

Canadian Dam Association (CDA). (2007, Edition 2013). *Dam Safety Guidelines.*

Canadian Dam Association. (2013). *Application of Dam Safety Guidelines to Mining Dams.*

Canadian Dam Association. (2014). *Application of Dam Safety Guidelines to Mining Dams.*

Carrier, A., & Kerr-Gilespis, F. (2016). *Note technique préliminaire de diligence raisonnable sur la campagne de forage de surface et d'échantillonnage.* InnovExplo due diligence report, 10 p. (in French).

Castro, L., & El Madani, F. (2010). *Feasibility Pit Slope Design.* Québec Lithium Open Pit Project - report no. 10-1221-0017-3000-Rev0.

Černý, P. (1991). *Rare Element Granitic Pegmatites. Part I: Anatomy and Internal Evolution of Pegmatite Deposits.* Geoscience Canada, v.18, (pp. 46-67).

Corfu, F. (1993). *The evolution of the southern Abitibi greenstone belt in light of precise U-Pb geochronology.* Economic Geology (1993) 88 (6): 1323–1340.

Dawson, K. (1966). *A Comprehensive Study of the Preissac-La Corne Batholith, Abitibi Country, Québec.* Geological Survey of Canada, Bulletin 142. .

Derry, D. (1950). *Lithium-bearing Pegmatites in Northern Québec.* Economic Geology, v. 45(2), (pp. 95-104).

Direction de la sécurité des barrages (DSB). (2024). *Chapitre S-3.1.01 – Loi sur la sécurité des barrages.*

Elevra Lithium Limited. (2026). *ASX Announcement "Accelerated NAL Expansion".* Dated January 12th, 2026.

Englobe. (2025). *Analyse hydrologique du lac Lortie.* Report n° 05-02502921.000-0100-GS-R-0001-0A.

Englobe. (2025). *Digue du lac Lortie.* Rapport n° 05-02502921.000-0100-GS-R-0004-00.

Englobe. (2025). *Rapport géotechnique et hydrogéologique factuel de la zone d'étude Nord.* Rapport n° 05-02502921.000-0100-GS-R-0006-00.

Englobe. (2025). *Stabilité géotechnique du Parc Québec Lithium – Conditions existantes.* Rapport n° 05-02502921.000-0100-GS-R-0005-00.

Englobe. (2026). *Analyse dynamique des sols et évaluation du potentiel de liquéfaction - Projet de conception géotechnique d'un ouvrage de retenue pour le parc à résidus miniers de Québec Lithium, Québec.* Rapport n° 05-02502921.002-0100-GS-N-0003-00.

Englobe. (2026). *Étude intégrée et modélisation numérique des eaux souterraines – Agrandissement phase 5.* Rapport n° 05-02601707.000-0400-GS-R-0001-0B.

Englobe. (2026). *Rapport géotechnique factuel de l'Ancien PAR et du lac Lortie.* Rapport n° 05-02502921.002-0100-GS-R-0001-0A.

Englobe. (2026). *Stabilité du mort-terrain de la fosse projeté.* Rapport n° 05-02502921.000-0100-GS-N-0004-00.

Environment Canada. (2016). *Guidelines for the Assessment of Alternatives for Mine Waste Disposal.*

For personal use only

For personal use only

Feng, R., & Kerrich, R. (1991). *Single zircon age constraints on the tectonic juxtaposition of the Archean Abitibi greenstone belt and Pontiac Subprovince, Québec, Canada.* Geochimica et Cosmochimica Acta, volume 55 Issue 11.

Gariépy, C., & Allègre, C. (1985). *The lead isotope geochemistry and geochronology of late-kinematic intrusives from the Abitibi greenstone belt, and the implications for late Archaean crustal evolution.* Geochimica et Cosmochimica Acta, volume 49 Issue 11.

GCM Consultants. (2022). *Avis technique – Critères de conception pour l'enveloppe de fosse de niveau préfaisabilité – Site minier Lithium Amérique du Nord, Lacorne, Québec.* Rapport n° 22515754-148-MTF-Rev0.

Golder. (2017). *Niveau Maximum d'Opération du Parc à Résidus #1 – Phase 1B+.*

Golder. (2022). *Analyse de l'impact du projet minier sur le lac Lortie et mesures d'atténuation.* Report n° 143-21482889-RF-Rev0.

Golder Associates. (2012). *Caractérisation géochimique d'échantillons de résidu combiné du projet Québec Lithium.* 13 p. + appendices.

Golder Associates. (2012). *Caractérisation géochimique d'échantillons de stériles miniers du projet Québec Lithium.* Québec Lithium inc. 9 p. + appendices.

Golder Associés Ltée. (2010). *Investigation hydrogéologique - Exploitation à ciel ouvert, Québec Lithium - Secteur du Lac Lortie.*

Golder Associés Ltée. (2013). *Développement du parc à résidus No. 1, Mine Québec Lithium, La Corne (Québec) – Rapport de conception Phases 1B et 1C.* Report n° 003-12-1221-0118-2000-RF-Rev0.

Golder Associés Ltée. (2017). *Caractérisation hydrogéologique complémentaire – Secteur du lac Lortie.* Report n° 002-1665476 Rev0.

Golder Associés Ltée. (2017). *Investigation hydrogéologique - Exploitation à ciel ouvert, Québec Lithium - Secteur du Lac Lortie.*

Golder Associés Ltée. (2018). *Memorandum Technique, TMF Chapter for NI-43101 Update – June 17.*

Golder Associés Ltée. (2022). *Avis Technique – Critères de Conception pour l'Enveloppe de Fosse de Niveau Pré-faisabilité – Site Minier Lithium Amérique du Nord, La Corne, Québec.*

Hardie, C., Live, P., & Palumbo, E. (2016). *Technical Report 43-101 on the Pre-Feasibility Study for the Québec Lithium Project.* Prepared for Canada Lithium Corp., (pp. 135).

Hardie, C., Stone, M., Lavery, M., Lemieux, M., Blanchet, D., & Woodhouse, P. (2011). *Technical Report NI 43-101 on the Feasibility Study for the Québec Lithium Project, La Corne Township, Québec.* Prepared for Canada Lithium Corp., (pp. 146).

Hardy, C. A. (2017). *Technical Report of August 2017 (unpublished).*

Hawley, M., & Cunning, J. (2017). *Guidelines for Mine Waste Dump and Stockpile Design.* CRC Press/Balkema. .

Karpoff, B. (1955). *Pegmatitic Lithium Deposit of the Québec Lithium Corporation.* Internal Report of Québec Lithium Corporation.

Karpoff, B. (1993). *Évaluation Technique de la Propriété Minière Québec Lithium.* Internal Report for Cambior Inc. (in French).

Kramer, S. (1996). *Geotechnical Earthquake Engineering, Prentice Hall Inc.* Englewood Cliffs, NJ.

Laboratoires d'Expertises de Québec ltée. (1996). *Analyse de stabilité d'une digue.* Rapport n° 4171-01-02.

Lavery, M. E., & Stone, M. (2010). *Technical Report, Québec Lithium Property, La Corne Township, Québec.* Prepared for Canada Lithium Corp., (pp. 146).

Leblanc, I., Piciacchia, L., Jarry, M., Dupuis, P., Richard, P., & Quinn, J. (2023). *NI 43-101 Technical Report Definitive Feasibility Study Report for the North American Lithium Project.* Prepared for Sayona Mining Limited and dated April 14th, 2023.

London, D. (2008). *Pegmatites.* The Canadian Mineralogist Special Publication 10.

McCracken, et al. (2022). *Prefeasibility Study Report for the North American Lithium Project, Québec Lithium Property, La Corne, Québec, Canada.* Prepared for Sayona Mining Limited.

Ministère de l'Énergie et des Ressources Naturelles. (2016). *Guide de préparation du plan de réaménagement et de restauration des sites miniers au Québec .* Direction de la restauration des sites miniers.

Ministère de l'Environnement, de la Lutte contre les changements climatiques, de la Faune et des Parcs (MELCCFP). (2025). *Directive 019 sur l'industrie minière.*

Ministère des Ressources Naturelles. (2014). *Approbation de la mise à jour du plan de restauration du site minier Québec Lithium.* Direction de la restauration des sites miniers.

For personal use only

Ministère des Ressources Naturelles et des Forêts (MRNF). (2024). *Guide de préparation du plan de réaménagement et de restauration des sites miniers du Québec.*

Ministère du Développement durable, de l'Environnement et des Parcs. (2012). *Directive 019 sur l'industrie minière.*

Mulja, T., Williams-Jones, A., Wood, S., & Boily, M. (1995). *The Rare-Element enriched Monzogranite-Pegmatite-Quartz Vein System in the Preissac-La Corne Batholith, Québec.* Geology and Mineralogy, Canadian Mineralogist, v. 33, (pp. 793-815).

North American Lithium. (2019). *Rapport de Production (Internal document), June 2017 to March 2019.*

Palumbo, E., & Hardie, C. (2016). *Technical Report on Laboratory Testwork and Operational Issues.* Prepared for North American Lithium Inc. by BBA Inc. (Technical Report No. 5939017-000000-49-ERA-0002, Rev 00, December 12, 2016), (pp. 112).

Poniewierski, J. (2017). *Pseudoflow Explained - A discussion of Deswik Pseudoflow Pit Optimization in comparison to Whittle LG Pit Optimization.* (pp. 4).

Primero. (2022). *North American Lithium Mine - Concentrate Belt Filter Upgrade Study - 24003-REP-PR-001 Rev. C, February 8th, 2022.*

Rowe, R. (1953). *Pegmatitic Beryllium and Lithium Deposits, Preissac-La Corne region, Abitibi County, Québec.* Geological Survey of Canada, Paper 53-3.

Roy, T. (2023). *Thèse de doctorat « Comportement hydrogéochimique de rejets miniers issus de pegmatites à spodumène ».*

Sayona Mining Limited. (2025). *ASX announcement "NAL Expansion Scoping Study Confirms Lower Costs and Strong Returns".* Dated September 15th, 2025.

Sayona Mining Limited. (2025). *ASX Announcement "NAL Reserves up 124% to 48.6 Mt and Resource increases to 95 MT" and accompanying JORC (2012) Table 1.* Dated August 27th, 2025.

Selway, J., Breaks, F., & Tindle, A. (2005). *A Review of Rare-Element (Li-Cs-Ta) Pegmatite Exploration Techniques for the Superior Province, Canada, and Large Worldwide Tantalum Deposits.* Exploration and Mining Geology (2005) 14 (1-4): 1–30.

SGS Canada Inc. (2010). *A Pilot Plant Investigation into the Flotation Recovery of Lithium, Québec Lithium Project.* Final Report prepared for Canada Lithium Corp., October 25, 2010.

SGS Canada Inc. (2019). *15818-004A Flot Test NAL-Sayona.*

SGS Canada Inc. (2021). *15818-05A Flot Test-Nov. 18.*

SGS Canada Inc. (2022). *15818-05A Flot Test-March 13.*

SGS Canada Inc. (2022). *15818-05A/MI4537-NOV21, Semi-Quantitative X-Ray Diffraction.*

SGS Canada Inc. (2023). *15818-05A Flot Testwork-March 05.*

Shannon, J., Nussipakynova, D., & Pitman, C. (2011). *Québec Lithium Property, La Corne Township, Québec, Technical Report for Canada Lithium Corp.* Prepared by AMC Mining Consultants (Canada) Ltd., December 5, 2011, (pp. 115).

SNC. (1974). *Report of Lithium Property, Barraute, Quebec for Sullivan Mining Group.* Montreal, Quebec. 63 pp.

Steiger, R., & Wasserburg, G. (1969). *Comparative U-Th-Pb systematics in 2.7 × 109yr plutons of different geologic histories.* Geochimica et Cosmochimica Acta, Volume 33, Issue 10, Pages 1213-1232.

Stone, M., & Ilieva, T. (2010). *Independent Technical Report, Québec Lithium Property, La Corne Township, Québec.* Prepared for Canada Lithium Corp. by Caracle Creek International Consulting Inc., (pp. 227).

Stone, M., & Selway, J. (2009). *Independent Technical Report, Québec Lithium Property, La Corne Township, Québec, Prepared for Canada Lithium Corp.* by Caracle Creek International Consulting Inc., (pp. 132, plus appendices).

Thompson, P. a. (2006). *Hydraulic Design of Energy Dissipators for Culverts and Channels.* Hydraulic Engineering Circular No. 14, Third Edition, Publication No. FHWA-NHI-06-086. Federal Highway Administration, U.S. Department of Transport.

Tremblay, L. (1950). *Fiedmont Map Area, Abitibi County, Québec.* Geological Survey of Canada, Memoir 253.

URSTM. (2015). *Essais cinétiques sur quatre lithologies du projet Québec Lithium.* 54 p.

Wave International. (2025). *Preliminary Economic Assessment for the North American Lithium Expansion Project.* Prepared for Elevra Lithium Limited.

Wood Mackenzie. (2022). *Global lithium strategic planning outlook – Q1 2022.*

Woodhouse; et al. (2011). *Updated Feasibility Study for the Quebec Lithium Project – Process Section.* Prepared for Canada Lithium Corp. by Technology Management Group, (pp. 66).

WSP Golder. (2022). *Étude hydrogéologique du secteur de la fosse au site minier de Lithium Amérique du Nord, La Corne, Québec.*
WSP Golder. (2022). *Mise à jour de l'évaluation des piliers de surface de la mine Lithium Amérique du Nord.*
WSP Golder. (2023). *Memorandum Technique, Préliminaire - Recommandations pour les angles de pentes pour l'étude de faisabilité de la réouverture de la fosse Lithium Amérique du Nord - Lacorne, Québec, Canada.*
WSP Golder. (2023). *Revue sommaire de l'enveloppe de fosse du 21 février 2023.*

For personal use only

28 Qualified Persons

For personal use only